(1) பக்கங்களின் எண்ணிக்கை 12

(2) புதுக்கித் திருப்பிய நாள் பிப் 1991

(3) ஆதாரங்குறிப்பவர் சுருக்கொப்பம் 10

தமிழ்நாடு ஆவணக் காப்பகம்.

தமிழ்நாடு அரசு

பொதுப்பணித் துறை

அரசாணை எண். / மு. கோப்புத் தாள் எண். 582

அச்சகம் / பலவகை

நாள் : 6-3-1893

498

மடிக்கவோ கண்டபடி கையாளவோ கூடாது

ஆவண. கா-1—18,000—15-6-87.

1/582 7/-

6TH MARCH 1893, No. 582 W., PUBLIC WORKS.

GOVERNMENT OF MADRAS.

PUBLIC WORKS DEPARTMENT.

Buildings and Roads.
Civil Works.

READ—the following paper:—

From Colonel A. T. FRASER, R.E., Superintending Engineer, III Circle, to the Inspector-General of Registration, dated Bellary, 13th December 1892, No. 2610.

I have the honour to forward, for your countersignature and transmission to Government for sanction, plan and estimate, amounting to Rs. 2,810, for constructing a Sub-Registrar's office at Harpanahalli prepared as per design approved in G.O., No. 2230 W., dated 21st July 1888.

T. No. 83.

Submitted for the sanction of Government.

2. The construction of an office building for the Sub-Registrar of Harpanahalli was sanctioned in G.O., No. 93, Judicial, dated 15th January 1893.

(Signed) S. HARI ROW,
Ag. Inspector-General of Registration.

CUDDAPAH,
21st January 1893.

To the Acting Chief Secretary to Government.

No. 344, Judicial.

Approved and transferred to the Public Works Department.

(By Order.)

(Signed) A. BUTTERWORTH,
Ag. Under-Secrecary.

20th February 1893.

ORDER—dated 6th March 1893, No. 582 W., Public Works.

The estimate, amounting to Rs. 2,810, for constructing a Sub-Registrar's office at Harpanahalli in the Bellary district, is sanctioned for execution when funds are available.

2. This sanction has been registered as Provincial No. 120 W. of 1892–93 and classified as Civil Buildings, Original Works.

(True Extract.)

Major, R.E.,
Under-Secy. to Govt., P.W.D.

To the Superintending Engineer, III Circle, with six enclosures.
" Examiner of Public Works Accounts.
" Judicial Department.
Editors' Table.

Exd. C. A. Munisawmy.
Spare Copies

BUILDINGS AND ROADS.
CIVIL WORKS.

Govt. of {1893} Madras.

PUBLIC WORKS.

Dated March, 6th.

Recd.

Encl.

G.O., 6th March 1893, No. 582 W.

MARCH.

Sub-Registrar's Office

Estimate of Rs. 2,810 for constructing a — at Harpanahalli in Bellary district, sanctioned.

2/582

Public Works Department.

Current No. 1625
Letter No. 344
Dated 25th February 1893
From the Judicial Dept

Landed
alle
1.2.B

B
1/3/93

TECHNICAL NOTE.

Name of Work Sub Registrar's office at Harpanahalli . Bellary District

Amount of Estimate, Rs. 2,810

PARTICULARS OF ESTIMATE.

Main Building	Office	Rs.	2533
Subsidiary Buildings		"	—
Contingencies	5%	"	127
Petty Supervision	Maistry for 5 months		100
Land compensation		"	50
Total Rupees ...			2,810

PARTICULARS OF CONSTRUCTION.

Surface soil red earth to a depth of 3 ft

Sub soil gravel

Foundations are to be made 4 feet deep, the lower one foot to be of concrete & the upper 3 feet of coursed rubble in chunam 2d sort

Basement is to be raised 2 feet high & built of coursed rubble in chunam 1st sort

Walls are to be raised 12 feet high & built of coursed rubble in chun with archwork over doors & win
:dows

astering or Pointing the interior faces are to be plastered with chunam 2 coats & the exterior pointed with chunam.

Flooring is to be of 18" sq. slabs laid on 4" of cement except for the record room which is to be of 3/4" asphalte laid on 4" of concrete

oofing is to be terraced with brick on edge &c. for the rooms & sloping terrace for the verandahs.

oors and Windows are to be of the description noted in the estimate of teakwood & painted with 3 coats of Carson's paint.

oof timbers are to be of teakwood.

antlings are correct

ates a few of the rates are in excess of the Divisional schedule but data lists are submitted in support of them.

he plinth area of the main building is 1004 square feet, and the cost per square foot will be Rs. 2. 12. 0.

Site

he plans and estimates have been countersigned by the Inspector General of Registration and approved in the Judicial Dept. ~~Department~~

REMARKS.

This estimate has been framed with reference to G.O. No. 232 W dated 23rd Jany 1892 & provides for constructing a Sub Registrar's Office at Harpanahalli in the Bellary Dist. as per type design circulated with G.O. No. 2230 W dated 21st July 1888 for smaller offices, terraced roof.

The site selected is private land & for which compensation to the extent of Rs 50 has been provided in the estimate.

The following rates are ~~slightly~~ slightly in excess of the Divisional schedule :—

Cement rubble 1st sort	17 . . .	against	16 . . .
Plastering 2 coats	2 . 4 . .	do	4 . . .
Painting with Carson's paint	4 . 4 . .	do	4 . . .
asphalte flooring	23 . . .	do	22 . 8 . .

data lists is submitted for the first

first item & as for the other items the saving by adoption of schedule rates will be trifling viz Rs 12.

28.II.93

CURRENT NO. 592

No. 2610.

3/582

Superintending Engineer's Office, 3rd Circle
Bellary, 13 December 1892.

From
Colonel A. J. Fraser, R.E.,
Superintending Engineer,
IIIrd Circle

To
The Inspector General
of Registration, Madras.

Enclosures – 6.

Sir,

I have the honor to forward for your Countersignature and transmission to Government for sanction plan and Estimate amounting to Rs 2810.0.0 for constructing a Sub Registrar's Office at Harpanahally prepared as per design approved in G.O. No. 2230, W, dated 21 July 1888.

I

I have the honor to be,

Sir,

Your most obedient Servant,

(Signed), A. J. Fraser, Colonel, R.E.,

Superintending Engineer,

III Circle.

I. No. 83, dated 21 January 1893,
Cuddapah.

Submitted for the sanction of Government.

2. The construction of an office building for the Sub Registrar of Harpanahalli was sanctioned in G.O. Judicial, dated 16 January 1892, No. 93.

S. Harrison
Ag. Inspector General of Regn.

To
The Ag. Chief Secretary to Government,
Fort Saint George.

Edmds

~~CURRENT NO.~~

~~JUDICIAL (1893) DEPARTMENT.~~

"REGISTRATION."

P. W. CURRENT No. 1625

~~2230W: 21.7.88~~
93: 15-1-92 mis

From

Ag.
THE INSPECTOR-GENERAL OF
REGISTRATION,
Madras,

To

Ag.
THE CHIEF SECRETARY
TO GOVERNMENT,
Fort St. George.

Dated
Despd. 21/11-2-93 January 1893.
Received
Regd 13th Feby/93.

No. 83 Enclos 6 (1 Plan)

Recd: 21-2-93

ENCLOSURE ~~S. two~~

No.

CHIEF SECRETARY
11 FEB 93
GOVERNMENT, MADRAS

No. 202 W d/ 31-1-1893.

Submitting for the approval and sanction of Government plan and estimate amounting to Rs 2810 for the construction of an office building for the Sub Registrar of Harpanahali, Bellary District

R 13/2
to 14/2

Hd 18 Feby

Dd 20 Feby 1893 No 344.

Approved and transferred to the Public Works Department.

(By order)

A. Butterworth.
Ag. Under Secretary

Dr 7 Feby

To the Public Works Dept. with encls.

14/2

C. 17/2
R 18/2

23.5.93

No. 582 W d/ 6th March 1893

PUBLIC WORKS DEPARTMENT.

5/582

Bd
Civil Works

PROCEEDINGS OF THE MADRAS GOVERNMENT.

READ the following

From the Inspector General of Registration T. No: 83 d/ 21 January 1893
Endorsement by the Judicial Department No: 344 d/ 20 February 1893.

The estimate amounting to Rs. 2,810, for constructing a sub-registrar's office at Harpanahalli in the Bellary District, is sanctioned for execution when funds are available.

2. This sanction has been registered as Provincial No: 120 W of 1892-93, and classified as Civil Buildings, Original Works.

Hd
3 Mar

Note. It is proposed to communicate this G. O. to the Editors' Table

2/3/93

4/3
14/3

To The Supty. Engr. III Circle with 6 enclos
" Examiner of P. W. Accounts
" Judicial Department
" Editors' Table

Maj

6/582

C No. 1625

Govt. of (1893) Madras.
PUBLIC WORKS.

Dated

Recd.

G.O. 6 March 1893, No. 582 W.

Sub Registrar's Office

Estimate of Rs. 2810 for constructing a — at Harpanahalli in Bellary District, sanctioned.

74

13 F 6/3.