

- (1) பக்கங்களின் எண்ணிக்கை 6
 (2) புதுக்கித் திருப்பிய நாள் 17/11/1991
 (3) ஆதாரங்குறிப்பவர் சுருக்கொப்பம் 10/11

தமிழ்நாடு ஆவணக் காப்பகம்.

தமிழ்நாடு அரசு

மொத்தப்பணித் துறை

அரசாணை எண். <u>694 W</u>	அச்சகம் பலவகை
மு. கோப்புத் தாள் எண்.	
நாள் : <u>14-3-1893</u>	<u>198</u> .

42

மடிக்கவேண்டிய கையாளலோ கூடாது

14TH MARCH 1893, No. 694 W., PUBLIC WORKS.

GOVERNMENT OF MADRAS.
PUBLIC WORKS DEPARTMENT.

Buildings and Roads.
Civil Works.

ORDER—dated 14th March 1893, No. 694 W., Public Works.

Errata in the printed estimate for Sub-Registrars' offices circulated with G.O., No. 2230 W., dated 21st July 1888.

The dimensions of doors and windows have now been calculated within frames in conformity with appendix G to the standard specifications.—

Terraced and tiled buildings.

Detailed estimates, pages 3, 7 and 8.

	For	Read
Venetian and panel door with frames, &c., complete	$1 \times 4' 0'' \times 8' 0'' = 32 \text{ sq. ft.}$	$1 \times 5' 6'' \times 7' 6'' = 26 \text{ sq. ft.}$
Batten door with frames, complete	$1 \times 4' 0'' \times 8' 0'' = 32 \text{ „}$	$1 \times 3' 6'' \times 7' 6'' = 26 \text{ „}$
Venetian windows with frames, complete, for office	$2 \times 3' 6'' \times 5' 0'' = 35 \text{ „}$	$2 \times 3' 0'' \times 4' 6'' = 27 \text{ „}$
Venetian windows with frames and glazed inner shutters, complete, for office	$2 \times 3' 6'' \times 5' 0'' = 35 \text{ „}$	$2 \times 3' 0'' \times 4' 6'' = 27 \text{ „}$
Batten windows with frames, iron bars $\frac{3}{4}$ square and inner glazed shutters, complete, for record-room	$4 \times 3' 6'' \times 5' 0'' = 70 \text{ „}$	$4 \times 3' 0'' \times 4' 6'' = 54 \text{ „}$

Abstract estimate.

Pages 5 and 10:

	For	Read
Venetian and panel door with frames, hooks and rim lock, complete	32 sq. ft.	26 sq. ft.
Batten door do. do. do.	32 „	26 „
Venetian windows with frames, hooks, &c., complete	35 „	27 „
Do. do. and glazed inner shutters, hooks, &c., complete	35 „	27 „
Batten windows with frames, iron bars and inner glazed shutters, hooks, &c., complete	70 „	54 „

(True Extract.)

Major, R.E.,
Under-Secy. to Govt., P.W.D.

To Superintending Engineers.
„ the Consulting Architect to Government.
„ the Judicial Department.

Exd. C. A. Munisawmy.
Spare Copies

BUILDINGS AND ROADS.
CIVIL WORKS.

Govt. of (1893) Madras.
PUBLIC WORKS.

Dated March, 14th.

Read.

Encl.

G.O., 14th Mar. 1893, No. 694 W.

MARCH.

Sub-Registrars' Offices

Errata in the printed estimate for —
circulated with G.O., No. 2230 W., dated
31st July 1888.

Amends in the printed estimate for Sub-Registrars' Office
circulated with G.O. No. 2230 W. dated 21st July 1888.

The dimensions of doors & windows have been calculated within frames in accordance with Appendix G to the standard specifications for
terraced & tiled buildings

Detailed estimate, pages 3, 7 & 8.

	For	Read.
Venetian & panel door with frames + complete	1 x 4'0" x 8'0" = 32 sq ft	1 x 3'6" x 7'6" = 26 sq ft
Batten door with frames complete	1 x 4'0" x 8'0" = 32 sq ft	1 x 3'6" x 7'6" = 26 sq ft
Venetian windows with frames complete = plates for office	2 x 3'6" x 5'0" = 35 sq ft	2 x 3'0" x 4'6" = 27 sq ft
Venetian windows with frames & glazed inner shutters complete for office	2 x 3'6" x 5'0" = 35 sq ft	2 x 3'0" x 4'6" = 27 sq ft
Batten windows with frames, iron bars 3/4" square & inner glazed shutters complete for second room	4 x 3'6" x 5'0" = 70 sq ft	4 x 3'0" x 4'6" = 54 sq ft

Abstract estimate

pages 5 & 10.

Venetian & panel door with frames, hooks & rim locks complete	32 sq ft	26 sq ft
Batten door — do — do	32 sq ft	26 sq ft
Venetian windows with frames, hooks & complete	35 sq ft	27 sq ft
do — do — do — & glazed inner shutters, hooks & complete	35 sq ft	27 sq ft
Batten windows with frames, iron bars & inner glazed shutters, hooks & complete	70 sq ft	54 sq ft

cc

1893 .

Public Works Department.

No.

694 W

Dated

14 March 1893.

Despatched

Received

SUBJECT.

Sub Registrars' offices
=

Errata in the
printed estimate for
circulated with
L.O. No. 230 W of
21 July 1888

250
12

30.11/3

3.11/3.

1-2