

25TH MAY 1894, No. 1315 W., PUBLIC WORKS.

GOVERNMENT OF MADRAS.
PUBLIC WORKS DEPARTMENT.

Buildings and Roads.
Civil Works.

READ—the following papers :—

From Colonel A. T. FRASER, R.E., Superintending Engineer, III Circle, to the Chief Engineer, Public Works Department, dated Bellary, 20th April 1894, No. 192.

With reference to G.O., No. 2723 W., dated 24th October 1893, I have the honour to forward, for favour of sanction, plan and estimate, amounting to Rs. 7,300, for constructing out-houses, urinals and raising eastern compound wall of Collector's Cutcherry, Bellary.

Note by the Chief Engineer, Public Works Department.

The foundations of the buildings should be laid with concrete throughout to ground level, instead of concrete and rubble masonry as provided for in the estimate. The additional cost will be only about Rs. 50.

(Signed) J. PENNYCUICK, Colonel, R.E.,
Chief Engineer, P.W.D.
19th May 1894.

ORDER—dated 25th May 1894, No. 1315 W., Public Works.

The estimate, amounting to Rs. 7,200, for additions and improvements to the Collector's office at Bellary, is sanctioned for execution when funds are available.

2. Attention is drawn to the note by the Chief Engineer, Public Works Department, recorded above.

3. This sanction has been registered as Provincial No. 16 W. of 1894-95 and classified as Civil Buildings, Original Works.

(True Extract.)

Under Secy. to Govt., P.W.D.

To the Superintending Engineer, III Circle, with 16 enclosures.
" Examiner, Public Works Accounts.
" Revenue Department.

Exd. C. A. Munisawmy.
Spare Copies

BUILDINGS AND ROADS.
CIVIL WORKS.

Gobt. of {1894} Madras.
PUBLIC WORKS.

Dated May, 25th.

Recd.

Encl.

G.O., 25th May 1894, No. 1315 W.

MAY.

Collector's Office, Bellary

Estimate of Rs. 7,200 for additions and improvements to the —, sanctioned with remarks.

Public Works Department.

No. 1315 W. 25/5/94

Current No. 3047

Letter No. 192

Dated 16th April 1894

From the Super Engineer in Charge.

NOTE BY TECHNICAL SECTION.

Name of work Constructing out houses & to the Collectors office at Bellary

Amount of estimate Rs 7200

The estimate under review has been framed with reference to G.O. No. 2723 W. dated 24th Oct 93 & provides for constructing out houses & raising the eastern compound wall of the Collectors Office at Bellary.

The amount of the estimate is divided as follows:-

Store room	Rs 1570
Tiffin room	1570
Ryots shed	1480
Coach house	850
Latrine	1220
Urinal	250
Raising compound wall	360
Total	Rs 7300

The estimate provides for the following buildings:-
a storeroom with 2 apartments one measuring 21' x 18' & the other 9' x 18'.

1) As concrete foundations to ground level would entail only Rs. 50 extra I think they should be altered accordingly.

2) The estimate gives particulars of the curved corrugated iron roof for the coach house: but the mode of its construction is not clear. A detailed working drawing would be necessary before commencing the work. The S.E. might be indicated accordingly.

3) The S.E.'s signature on the drawings is so very faint that it will fade away in a few months if not sooner.

C.H.S.

18/5/94

Living room with 2 apartments, one measuring 21' x 18' & the other 9' x 18'.

Ryots shed ————— 36' x 21'

Coach house ————— 55' x 12'

Lathies in 2 compartments of 10

seats each ————— 60' x 13'

Urinal for 5 divisions —

Raising eastern compound wall 2 feet high for a length of 800 feet.

The walls are proposed to be built of coursed rubble in mortar throughout except the partition & screen walls of the latrine which are to be of brick in chunam & the roofs of Mangalore tiles laid over teak rafters except for the Coach house which is to be of curved corrugated iron laid on iron trusses.

The scantlings provided for roof timbers are correct.

The rates are fair except for corrugated iron roof which is slightly in excess of the schedule rate, viz Rs 30 against Rs 28-6.. The saving by adopting schedule rate will be trifling.

The curved roof for the Coach house does not appear to be clear provision has been made in the estimate for 2 T iron purlins with flat iron tie bars & struts. It is thought that one T iron ridge at crown & two L iron purlins at the struts with the necessary tie bars etc. may be allowed, as sketched in pencil on plan but as this is a matter of

of detail in construction it may be left to the discretion of the SE.

If the foundations are to be laid of concrete throughout in lieu of concrete & rubble masonry as proposed, to ground level, the amount of the estimate will be increased by Rs 50.

The plan & estimate have been counter-signed by the Collector but they have not been approved in the Revenue Dept.

[Signature]
11. V. 94.

OW
Submitted, and
approved & recommended
to the SE for
approval
CC
12/5/94

C. No. 3047

P. W. Secretariat.

Note by Budget Section.

Work *Additions and Improvements to the Collector's office, Bellary.*

Fund	Provincial
Service Head	Civil Buildings
Departmental Head	Original Works
Amount of Estimate	Rs. 7300
Expenditure in previous year	" "
Allotment in current year	" "
Balance required to complete	" 7300
Total Rs...	7300

Note of available Funds.

X. Note
The work appears in Part I - class B works of the final issue of the Provincial Civil Works Budget for the current year. Vide items 35 to 39. As all the demands on account of incomplete works of last year have not yet come in, the money available for other works out of the Provincial reserve cannot be determined at present.

[Signature]
12. V. 94

Note by Budget Section.

No. 192

Superintending Engineer's Office,

3RD CIRCLE,

Bellary 20th April 1894

FROM

Col. A. I. Fraser R.E.

SUPERINTENDING ENGINEER.

IIIRD CIRCLE.

To

THE

Chief Engineer
P. W. Deptt
Madras.

Sir,

Enclosures. 16

2 Plans &
1 Report

1 Specification
1 Detail Estimate

1 Abstract

1 General

Abstract

9 Enclosures

of G.O. No. 27234

24-10-93 of

16 R. Govt. Post

With reference to G.O. No. 27234
of 24th October 1893, I have the honor
to forward for favor of sanction
plan & estimate amounting to Rs. 7300
for constructing out houses, urinals
and raising eastern compound wall
of Collector's Catchery Bellary.

I have the honor to be
Sir

Yours most obedt Servt

A. I. Fraser Col. R.E.

Superintending Engineer
III Circle

No. 1315 W. d. 25th May 1894

P. W. CURRENT No. 3047

No. 82 C of 8-1-91
602 W of 3-3-91
16 W of 5-1-91
2723 W of 24-10-93

From

Col. A. I. Fraser R.E.
Superintending Engineer
3rd Circle Bellary

To The Chief Engineer
P.W.D.

Que: 21-6-94 Madras
Dated 16th April 94

12-192

Enclosures 16 (3 sheets)

Collector's Bungalow
at Bellary -
Forwarding plan and
estimate amounting to
Rs 7300/- for constructing
out-houses animals &
raising eastern compound
wall of

Note by the Chief Engineer P. W. D.

The foundations of the buildings
should be laid with concrete throughout
to ground level, instead of concrete and
rubble masonry as provided for in the
estimate. The additional cost will be
only about Rs. 50.

S
E. W.

C. W. S.
195-94

195

2275

one 63

R. S.

No. 1315 W. d. 25 May 1894.

PUBLIC WORKS DEPARTMENT.

PROCEEDINGS OF THE MADRAS GOVERNMENT.

Read the following

From the Suptg. Engineer III circle No: 192 d/16 April 1894.

Note by the Chief Engineer, P. W. Department of Bellary 1894.

The estimate amounting to

Rs. 7,200, for additions and improvements to the collector's office at Bellary, is sanctioned for execution when funds

are available.

2. Attention is drawn to the note by the Chief Engineer P. W. D. recorded above.

3. This sanction has been registered as Provincial No: 16 W of 1894-95, and classified as Civil Buildings, Original Works.

To The S. E. III circle with 16 files
" Examiner P. W. Accounts
" Revenue Department.

Cross
19.6.94

S

11/21/5

~~#8~~
#5

Estimate for additions and
improvements to the Collector's
office at Bellary.

Rs
90

To The Honble
The Secy to Govt. Revenue
Department for favor of counter-voucher

Rs 63/-
Rs 24/5/94
Rs 24/5/94
Rs 23/5/94

CN^o 3047

Govt. of 1894 Madras.

PUBLIC WORKS.

27/7/94

Date

Recd.

Recd.

G.O. 25th May 1894 No 13156

Collector's office,
Bellary

≡

Estimate of Rs. 7200
for additions and
improvements to the —
austioned with
remarks.

100/5

24. 25/5

14
28/5

Man who was in a ...