

10241

Govt. of Madras.
PUBLIC WORKS

10/2/1894 3626

Government Press
Buildings, Madras

Estimate of Rs. 15,900
for additions to the
sanctioned, and the
Eng. Architect directed
to report what sum
can be spent on the
work during the
current year.

100/5

J.C. 14/11

1-4
INDEXED
14/2

H.2 - 100/5

10TH FEBRUARY 1894, No. 362 W., PUBLIC WORKS.

GOVERNMENT OF MADRAS.
PUBLIC WORKS DEPARTMENT.

Buildings and Roads.
Civil Works.

READ—the following paper:—

Office-note from R. HILL, Esq., Superintendent, Government Press, to the Chief Secretary to Government, dated Madras, 5th October 1893, No. 3147.

In continuation of office-note No. 3088, dated 2nd October 1893, and at the request of the Consulting Architect to Government, the Superintendent, Government Press, submits the plans and estimates for the additional buildings to be erected for the Government Press.

No. 2145, Public.

Approved and transferred to the Public Works Department.

1st December 1893.

(Signed) J. F. PRICE,
Chief Secretary.

ORDER—dated 10th February 1894, No. 362 W., Public Works.

The estimate, amounting to Rs. 15,900, for additions to the Government Press buildings at Madras is sanctioned.

2. The Consulting Architect will report at once what sum can be spent on the work during the current official year.

3. This sanction has been registered as Provincial No. 139 W. of 1893-94 and classified as Civil Buildings, Original Works.

(True Extract.)

Major, R.E.,
Under Secy. to Govt., P.W.D.

To the Consulting Architect to Government,
with 6 enclosures.
" Examiner, Public Works Accounts.
" Public Department.
Editors' Table.

Exd. C. A. Munisewmy.
Spare Copies

BUILDINGS AND ROADS.
CIVIL WORKS.

Govt. of {1894} Madras.

PUBLIC WORKS.

Dated February, 10th.

Recd.

Encl.

G.O., 10th Feb. 1894, No. 362 W.

FEBRUARY.

Government Press buildings,
Madras

Estimate of Rs. 15,900 for additions to the —, sanctioned, and the Consulting Architect directed to report what sum can be spent on the work during the current official year.

Government Press,
Madras,
5th October 1893.

No. 3147

Office Note.

1 Per

Cuo 2669.

In continuation of
Office Note No. 3088, dated
2nd October 1893, and at the
request of the Consulting -
Architect to Government,
the Superintendent, Govt. Press,
submits the plans and estimates
for the additional buildings
to be erected for the Govt. Press.

R. Hill

Superintendent.

To

The Chief Secretary

to Government.

From P. W. CURRENT No. 10241

The Superintendent,
Govt. Press,

To
The Chief Secretary
to Government.



Dated 5th }
Received 6th } October 1893

Order No. 24293

Enclosures (3 Plans)

- 1 Report
- 3 Plans
- 1 Detailed Estimate
- 1 Abstract - do -

Subject

Submits plans and estimates for additional buildings for the Govt. Press.

(From Order)

C.S.
29. XI.

No 1853 of 23-6-92
- 2273 of 17-8-92
- 1425 of 30-5-93
- 2357 of 13-9-93

2 Pm
14 Dec 1893
Approved and transferred
to the Public Works Department.

ment.
Redmickhill
Chief Secretary

Public Works Department.

Current No. 10241

Letter No. 2145

Dated 18 December 1893

From the Public Dept.

NOTE BY TECHNICAL SECTION.

B. 2/27/93
Name of work Addition to the Govt. Press
buildings at Madras.

Amount of Estimate Rs 15900

This estimate has been framed with reference to G.O. No. 1425 of 30th May 1893 & provides for alterations & additions to the Govt. Press buildings at Madras.

The amount of the estimate is made up of the following items:-

- | | |
|--|---------|
| (a) Cost of a new binding room | Rs 5019 |
| (b) - do - new store room | 4250 |
| (c) Extending Compositors room | 3480 |
| (d) - do - type store room | 949 |
| (e) Cost of waste paper room | 725 |
| (f) - do - Carpenter's shed | 650 |
| (g) - do - Covered passage between Binding & Machine rooms | 413 |
| (h) - do - Compound wall near waste paper room | 197 |
| (i) - do - oil store room | 90 |
| (j) Minor alterations & additions | 127 |

Total Estimate Rs 15900

The

The additions & alterations proposed are

(a) A new binding room 55'6" x 20' with a passage 8 feet wide is to be added to the west of the existing binding room. This new room is to be 12'9" high to bottom of terrace provided with 4 large doors each 5' x 9'6" and 7 windows each 4 1/2' x 7'. The terrace to be of brick on edge carried over teak joists & steel girders. The girders are to be of a section 8 3/8" x 20" placed 9'3" apart. The passage between the existing & proposed binding rooms is to be 11 feet high to bottom of terrace & the terrace carried over teak joists 3" x 6" in section.

(b) New store room. This room is to be 45' x 24' with a passage 8 feet wide & to be built adjoining the machine room, as per site plan. The room & passage to be terrace, the former on steel girders & teak joists & the latter on teak joists. The girders are to be of a section 8 3/8" x 20" weighing 100 lbs per foot and to be placed 9 feet apart. The room is to have 3 large doors each 5' x 9'6" and 7 windows each 4 1/2' x 7'. The floor is to be of 3/4" asphalt laid over 6 inches of concrete. The height of the room to be 12'9" to bottom of terrace.

(c) Extension to the compositor's room. This extension is to be on the north

north end of the existing building & is to contain 2 rooms one 45' x 24' & another at right angles facing east 30' x 16', as per plan. The roof of the extension is to be tiled carried on trusses placed 8'8" apart in the large room & 10 feet apart in the small room, an archway 10 feet wide to be opened out between the existing & proposed rooms.

(d) New type store room. This room is to be built at the south western end in the space left vacant. The room is to measure 27' x 15' & to be provided with 3 large windows 4' x 5' on the north face & 3 other windows each 4' x 3' on the south face. The roof is to be tiled on trusses placed 9 ft. apart, an archway 10 feet wide is to be opened out between the existing & proposed type store.

(e) Waste paper room. This room is to be constructed in the vacant space to the north east of the compositor's room. The proposed room is to measure 30' x 12' & built against the north compound wall. The walls are to be raised solid to a height of 3 feet above floor level & above built with honey comb work. The roof to be tiled on

idea on leak roof
supported in front with masonry
pillars, as shown on plan.

(f) Carpenter's shed. This room
is to measure 22' x 12' & to be built
east of the proposed carpenter's
room. The roof is to be a lean to
roof & the mean height of the
room is to be 11 feet. Provision
has been made for 4 windows
each 3' x 4' & a gateway 8 feet
wide.

Provision has also been made
for a room 19' x 9' for storing
oil at a cost of Rs 90, a com-
pound wall 6 feet high with
gate near the proposed waste
paper room & for minor alter-
ations pointed out by the Supdt.
Govt. Press, such as dismantling
& rebuilding a masonry trough
5 feet long in dumping room,
alterations in doors & windows,
removing shelves &c. &c.

The rates are fair.

The scantlings for roof
timbers are correct but no
provision has been made for
wall plates under joints of
in timbered roof & under rafters
in the lean to roof.

The plans & estimates have
been countersigned by the Supdt.
Govt. Press & approved in the
Public Dept.

1. E. 94.

N^o 36^o W of 10th February 1894.

PROCEEDINGS OF THE MADRAS GOVERNMENT.

Read the following

From the Superintendent {H.C. No. 3147 of 5th October 1893)
Government Press

End^d in the Public Dept. (" " 2145 of 1st Dec^r 1893)

The estimate
amounting to Rs 15,900 for
additions to the Govt.
Press buildings at Madras
is sanctioned.

2. The Consulting
Architect will report at
once what sum can be
spent on the work during
the current official year.

3. This sanction
has been registered as
Provincial No. 139 W of
1893-94 and classified
as Civil Buildings, Original
Works.

Do I understand that the present
additions are all that the Supdt. of
the Govt. Press requires - or will he
come up again for more, if the
Army List has to be printed by him?

Office Note to Chief
Secy
DESPATCHED
21 FEB. 94
118

The Commg. Architect to Govt.
with 6 enclos.

" Exar: P. W. acts
" Public Dept.
" Editors Table.

Attention for:

H.S.

Mr. [unclear]

Govt. Press buildings
Machines.

Estimate for
additions to the —

J. H.
B.
Need 13/14

Note: It is proposed to
place this on the Editor's
table.

10/10/01

4

all [unclear]

copy of [unclear]

[unclear]

[unclear]

[unclear]

[unclear]

[unclear]

[unclear]

[unclear]

[unclear]