

CN 2036
Govt. of 1894 Madras.
PUBLIC WORKS.

Dated

Recd

Encl

G.O. 2 3/4 1894 No. 1047 W

Special Assistant
Collectors' office at
Malappuram

The estimates aggregating
Rs 7580 for improvements
& additions to the —
in the Malabar St.,
sanctioned with remarks.

INDEXED
24/4

20/4

Classified as Civil
Buildings, Original
Works.

4. Attention is drawn
to the note by the Chief
Engineer above recorded.

CMB

10.4.54

[Signature]

Note: It is proposed to place
this on the Editor's
Table.

CMB

10.4.54

4/5
To the S.E. to Circle
with plans & estimates
Exar. P.W. Acct. 7
Rev. Dept.
Editor's Table

No. 1047 W. d. 23 April 1894.

PUBLIC WORKS DEPARTMENT.

PROCEEDINGS OF THE MADRAS GOVERNMENT.

Read the following

Pres. of the Board of Rev. (d. and Rev.) No. 821 No. d. 17. 2. 94
Endorsement thereon in the Rev. Dept. No. 1049 No. d. 10. 3. 94
Note by the Chief Secy No. 2 dated 10 April 1894

The estimates, aggregating
Rs. 7580, for improvements
and additions to the
Special Assistant Collector's
office at Malappuram
in the Malabar District,
are sanctioned.

2. The question of allotting
funds for the work will
be considered after the
demands on account of
the incomplete work of
the past official year
have been provided for.

3. This sanction has been
registered as Provincial
No. 6 W of 1894-95 and

Classified

for the accommodation of clerks &

W. - Secretary.

should be suitable for the
purpose and
6.4.94

~~Dr~~ Draft note herewith sub-
mitted for approval.

The note may be read in the
sanction order & a para in-
serted drawing attention to the
note.

~~W. W. G.~~

In returning the official sanction, draft a letter pointing out the defect of building masonry on concrete foundation of the same width as the masonry and describe the concrete to ground level by provided, and which must be 2 feet wider than the basement walls. And also point out that concrete to ground level with 9" footings

for the accommodation of clerks & records.

The new Court room with measure 30' x 15' & the private room 10' x 15' with verandahs 9' 6" wide all round & connected to the existing building by a covered way 15 feet long & 10' 9" wide.

The roof of the existing building is reported to be leaking & in a unsafe condition owing to many of the rafters & rafter beams decayed & partly eaten by white ants. It is therefore proposed to demolish the roof & relay with new roof timbers where required & drainage tiles so as to suit the proposed extension.

The soundings for roof timbers are correct & the rates are fair.

The plinth area of the extension is 2125 sq ft & the cost per sq ft will be Rs 2-9-5.

The plans & estimates have been countersigned by the Collector & approved in the Revenue Dept.

W. M. G. A.

W. - Foster.

I would suggest that the foundations be of concrete to ground level and 2 feet (i.e. on four each side) broader than the superincumbent masonry. In the accompanying drawing the concrete is 20 inches wider than the masonry on top.

The foundations for the compound wall might be similarly treated. Key 9" footings would in that case be sufficient.

C. M. V.

5-4-94

P. I. I presume the soil is really hard as stated. The soil is a depth of only 2 feet high - prove insufficient. C. M. V.

D. S. G.

Presumably not all the soil is sufficient if it is not.

Public Works Department.

Current No. 2036.

Letter No. 1049 Mins.

Dated. 10th March 1894.

From the Revenue Dept.

Sanction

NOTE - TECHNICAL SECTION.

2594 B 203

Name of work. Extending & improving the office of the Special Asst. Collector at Malapurm in the Malabar District.

Amount of estimate Rs 7580

This estimate has been framed with reference to G.O. No. 1043 W dated 14th April 1893 & provides for extending & improving the office of the Special Asst. Collector at Malapurm.

The amount of the estimate is divided as follows:-

- (a) Providing a new Court with private room — Rs 5500
- (b) Improving the existing office. 2080
- With Balances 7580

The accommodation in the existing office building is stated to be quite insufficient for the establishment of the Special Asst. Collector's office. It is therefore proposed to provide additional accommodation by building a new Court with private room, as per plan, and to improve the existing building for

HC

Please attach to CN^o 2036

94

1047

23 4 94

3 P
Note by the Chief Engineer P.W.

The undersigned ^{considers} recommends that instead of building masonry or concrete foundations of the same width, ~~as proposed~~ the foundations ^{should} be of concrete throughout to ground level and 2 feet wider than the basement walls. The foundations for the ~~con-~~ ^{skipped} poured wall ~~should~~ be similarly treated, though 9" projection on each side would be sufficient in the case.

CWMD

10.4.94

10: April 1894

S

SW

C

P. W. CURRENT No. 2036
5,000-7-9-93

ABSTRACT.

(1894.)

REVENUE DEPARTMENT.

Current Number 1404.

From

The Board of Revenue
Land Revenue

2 P
Encl. N-1049 (11)

The plans and estimates are approved and will be transferred to the Public Works Department for sanction.

Dated 17th Feb/94.

Received 20th

Enclosures 13/4 (3 plans)

Recd: 14.3.94 No. 821 (11)

L. S. D. M. S. S.

At Moulvi to four

SUBJECT.

Submitting for the sanction of Government plans and estimates for improving and extending the special appt. Collector's office building.

For the Board of Revenue

10 March 1894

The Commr. of Land Revenue
with the Collr's letter of 2 Feb/94
No. 1081 & Enc. 10.
Public Works Dept.
with 13 Encls.

Proceedings of the Board of Revenue.
(Land Revenue.)

Dated 17 February 1894.

N^o 821 Ins.

Read the following letter from Herbert Bradley Esq^r, Agt Collector of Malabar, dated 1st Feb 1894, Ref. on C. No. 317 to the Secretary to the Commissioners of Land Revenue.

With reference to the Board's Proceedings dated 11th April 1893, N^o 2216 Ins. I have the honor to forward herewith copy of a letter from the Superintending Engineer IV Circle requesting that the sanction of Government may be obtained for the provision of funds for the following works:

- (a) Providing additional accommodation to the special Assistant Collector's office at Malapparam - Rs. 5,500.
(b) Improvements to the existing office - Rs. 2,080.
Total - Rs. 7,580.

2. It has become necessary to repair the existing building also, as its rafters and roof are to a great extent decayed and destroyed by white ants.

3. The plans and estimates as per enclosed list are also submitted.

Resolution - The plans and estimates received from the Collector of Malabar for improving and extending the special Assistant Collector's office at Malapparam at an aggregate cost of Rs. 7,580 are submitted for the sanction of Government with reference to G.O. dated 31-5-93 No. 1225.

2. The necessity for the works has been fully explained in the reports accompanying the estimates.

/ True Copy & Extract /
/ Sd/ L. M. Wignesh /
Secretary

To, The Secretary to Govt. Revenue Dept.
with C. Nos. -

Resd.

2036/54

1894.
REVENUE DEPARTMENT.
Enclosure No. 13
Current No. 1401

List of Enclosures accompanying Malabar
Collector's letter dated 1st February 1894

1. Superintending Engineer's letter ^{35-2m} 26-1-94 ... 1
2. Plan of the proposed extension ... 1
3. " Survey of the Spl. Asst. Collector's Office }
+ Compound ... 1
4. " of the Wooden Gate ... 1
5. Additions to the Spl. Asst. Collector's Bungalow.
 - (1) Report to accompany Estimate
 - (2) Specification " "
 - (3) Data for flooring " "
 - (4) Estimate form (Abstract) ... 11 Ha
 - (5) " (Detail) Sheets
 - (6) Estimate form (Abstract)
6. Improvements to the Special Asst's Bungalow
 - (1) Report to accompany Estimate
 - (2) Estimate form (Detail.) ... 3 Ha
 - (3) " (Abstract) Sheets

Malabar Collector's Office }
Calicut 1st Feb 1894 }

for as Collector

BUILDINGS AND ROADS.
CIVIL WORKS.

Govt. of {1894} Madras.

PUBLIC WORKS.

Dated April, 23rd.

Recd.

Encl.

G.O., 23rd Apr. 1894, No. 1047 W.

APRIL.

Special Assistant Collector's
office at Malappuram

The estimates aggregating Rs. 7,580 for
improvements and additions to the — in the
Malabar district, sanctioned with remarks.

List of Enclosures accompanying Malabar
Collector's letter dated 1st February 1894

1. Superintending Engineer's letter ³⁵⁻⁷¹ 26-1-94 ... 1
2. Plan of the proposed extension ... 1
3. " Survey of the Spl. Asst. Collector's Office }
+ Compound ... 1
4. " of the Wooden Gate ... 1

5. Additions to the Spl. Asst. Collector's Bungalow.

- (1) Report to accompany Estimate
- (2) Specification " "
- (3) Data for flooring " "
- (4) Estimate form (Abstract)
- (5) " (Detail)
- (6) Estimate form (Abstract)

--- 11 Half
Sheets

6. Improvements to the Special Asst's Bungalow

- (1) Report to accompany Estimate
- (2) Estimate form (Detail)
- (3) " (Abstract)

... 3 Half
Sheet

Malabar Collector's Office
Calicut 1st Feb 1894

for a Collector

20 15 16 W 86.6-87
23RD APRIL 1894, No. 1047 W., PUBLIC WORKS.

GOVERNMENT OF MADRAS.

PUBLIC WORKS DEPARTMENT.

Buildings and Roads.
Civil Works.

Read—the following papers:—

Proceedings of the Board of Revenue (Land Revenue), dated 17th February 1894, Mis. No. 821.

Read—the following letter from H. BRADLEY, Esq., Acting Collector of Malabar, to the Secretary to the Commissioners of Land Revenue, dated 1st February 1894, Ref. on C. No. 317-P. :—

With reference to the Board's Proceedings, dated 11th April 1893, Mis. No. 2216, I have the honour to forward herewith copy of a letter from the Superintending Engineer, IV Circle, requesting that the sanction of Government may be obtained for the provision of funds for the following works:—

	RS.
(a) Providing additional accommodation to the Special Assistant Collector's office at Malappuram ...	5,500
(b) Improvements to the existing office ...	2,080
Total ...	7,580

2. It has become necessary to repair the existing building also, as its rafters and reapers are, to a great extent, decayed and destroyed by white ants.
3. The plans and estimates as per enclosed list are also submitted.

Resolution—dated 17th February 1894, Mis. No. 821.

The plans and estimates received from the Collector of Malabar for improving and extending the Special Assistant Collector's office at Malappuram at an aggregate cost of Rs. 7,580 are submitted for the sanction of Government with reference to G.O., dated 31st March 1893, No. 1225.

2. The necessity for the works has been fully explained in the reports accompanying the estimates.

(True Copy and Extract.)

(Signed) L. M. WYNCH,
Secretary.

Mis. No. 1049, Revenue.

The plans and estimates are approved and will be transferred to the Public Works Department for sanction.

FORT ST. GEORGE,
10th March 1894.

(Signed) L. E. BUCKLEY,
Ag. Under Secy. to Govt.

Note by the Chief Engineer, Public Works Department.

The undersigned considers that instead of building masonry on concrete foundations of the same width, the foundations should be of concrete throughout to ground level and 2 feet wide than the basement walls. The foundations for the compound wall should be similarly treated, though 9" projection on each side would be sufficient in this case.

10th April 1894.

(Signed) J. PENNYCUICK, Colonel, R.E.,
Chief Engineer, P.W.D.

ORDER—dated 23rd April 1894, No. 1047 W., Public Works.

The estimates aggregating Rs. 7,580 for improvements and additions to the Special Assistant Collector's office at Malappuram, in the Malabar district, are sanctioned.

2. The question of allotting funds for the work will be considered after the demands on account of the incomplete works of the past official year have been provided for.

3. This sanction has been registered as Provincial No. 6 W. of 1894-95 and classified as Civil Buildings, Original Works.

4. Attention is drawn to the note by the Chief Engineer above recorded.

(True Extract.)

Under Secy. to Govt., P.W.D.

To the Superintending Engineer, IV Circle, with plans and estimates.
" Examiner, Public Works Accounts.
" Revenue Department.
Editors' Table.