

Government of Madras.

1895.

P. W. DEPARTMENT.

CURRENT No.

From

The Examiner

P. W. Accounts.

ENCLOS

No. 1839 D

Dated 23.5.95

Received 28.5.95

SUBJECT.

L. Parancusiah, clerk.
P.W. workshops, Madras.

Stating that — cannot
begin on more than the
minimum pay of his appoint-
ment (viz) Rs 15 per mensem.

no 1610 of 15.1.91

5260 of 10.12.92

4020 DISPOSAL.

2.2.95

18340 of 15.5.95

Recd: 28.5.95

No.

dated


No. 1359 W dated 8th June 1895

B. J. J.

Under Article 172
C.S. Regus: the clerk
must commence on
the minimum pay of
his grade.

Sr

copy



W. R. Circle

25/113

25/6

25/6

4102

BOARD OF REVENUE (LAND REVENUE), 2ND MAY 1895, No. 128.

PROCEEDINGS OF THE BOARD OF REVENUE
(LAND REVENUE).

Read—the following Government Order, dated 20th April 1895, Mis. No. 1560, Revenue:—

Read—the following Government Order, dated 19th February 1895, No. 427 W., Public Works:—

Read—the following papers:—

From H. IRWIN, Esq., C.I.E., Consulting Architect to the Government of Madras, to the Chief Engineer, Public Works Department, dated Chepauk, 3rd November 1894 No. 2301.

With reference to Government Order, No. 1937 W., dated the 4th August 1894, I have the honour to submit a standard design with schedule of quantities for a Stationary Sub-Magistrate's office with terraced roofing. The plan has been approved by the Board of Revenue.

2. The design with tiled roofing is under preparation.

Government Order, dated 15th December 1894, Mis. No. 4941, Revenue.

Read—endorsement of the Public Works Department, dated 23th November 1894, No. 3811 C.

Order—dated 15th December 1894, Mis. No. 4941, Revenue.

The standard design for a Stationary Sub-Magistrate's office is approved.

(True Extract.)

(Signed) R. C. C. CARR,
Under Secretary to Government.

Order—dated 19th February 1895, No. 427 W., Public Works.

The type design, with schedule of quantities, for a Stationary Sub-Magistrate's office with terraced roofing is circulated to officers of the Public Works Department.

(True Extract.)

(Signed) J. PENNYCUICK, Colonel, R.E.,
Secretary to Govt., P.W.D.

To all Superintending Engineers.
" the Consulting Architect to Government.
" the Revenue Department.
" the Judicial "

APPENDIX.

STANDARD design for a Stationary Sub-Magistrate's office with terraced roofing according to drawing signed by the Consulting Architect to Government on 2nd November 1894.

DESCRIPTIVE SPECIFICATION.

Foundations.—A depth of 4½ feet is provided in the quantities, but this should be locally settled according to the nature of the soil.

Walling.—The walls will be carried up in English bond according to the various thicknesses shown on the drawing, 1½ and 2 bricks thick.

Stonework.—Stone slabs should be placed at the bearing of beams. The steps may also be of stone if procurable without great expense.

Woodwork.—The beams and joists to be of well-seasoned Burma teakwood or any other durable wood proof against white-ants.

Doors and Windows.—To be of well-seasoned Burma teakwood. All doors opening into verandah will be one-third panel and two-thirds venetians; inner doors to be pannelled throughout. The windows for the record and retiring rooms will have single venetian shutters opening outside with fixed glass heads and ¾" square iron bars set diagonally. The ventilators will consist of a glazed shutter to open and shut on side pivots.

Cornice.—In place of the usual cornice, Cuddapah or any other similar slabs resting on brick corbels will be fixed throughout the building. The slabs to be well fitted and the joints neatly pointed with cement.

Roofing.—The roofing to consist of "pucca terracing," care being taken that proper slopes are made towards the weep-holes to be made about 2 feet apart in the parapet wall; the rain water will flow over the slabs and fall clear of the building.

Flooring.—The floor will consist of Cuddapah slabs about 2" thick laid on a 4" bed of concrete and neatly pointed with asphalt. If Cuddapah slabs are not easily procurable, the floor may be of square bricks on a bed of concrete, in which case the record room should be floored with asphalt; where the soil is damp the filling in below the floor should be of river sand. The floors of verandahs will be laid with a fall outwards of 1 inch to 4 feet.

Interior and exterior finishing.—The interior walls will be fine plastered and polished or plastered and whitewashed. Where good bricks or stone is obtainable, the exterior should be pointed. In damp soil the exterior plinth and walls inside rooms 3 feet above floor should be plastered with Portland cement. The beams and joists to be stained with three coats wood-oil and the doors and windows painted with three coats oak paint.

The different kinds of work to be done will be executed in conformity with the standard specification of the Public Works Department.

ESTIMATE FORM—Detail Measurements.

Detail of work.	Number.	Measurement in feet			Area or contents.	Total quantity of each description of work.
		Length.	Breadth.	Depth.		
1	2	3	4	5	6	7
<i>Excavation for foundations.</i>						
Court room walls	..	92 0				
Private room walls	..	40 6				
Clerks' do.	..	67 6				
Record do.	..	68 6				
Verandah walls	..	215 6				
		484 0	4 0	4 6	8,712	
Retiring room side walls	2	4 0	3 0	4 6	108	
Dais	1	16 4½	3 0	1 6	74	
Steps, front	1	19 0				
Do. rear	1	11 0				
Do. sides	2	11 6				
		53 6	3 0	0 6	80	
Total cubic feet of excavation for foundations	..	..	..	..	..	8,974

Estimate Form—Detail Measurements—cont.

Detail of work.	Number.	Measurement in feet.			Area or contents.	Total quantity of each description of work.
		Length.	Breadth.	Depth.		
1	2	3	4	5	6	7
<i>Concrete.</i>						
Walls as above	..	484 0	4 0	4 0	7,744	
Retiring room sides	2	4 0	3 0	4 0	96	
Walls of dais	1	16 4½	3 0	1 6	74	
Steps as above	..	53 6	3 0	0 6	80	
Total cubic feet	..	..	..	..	..	7,994
<i>Brickwork in foundations and basement.</i>						
Court room walls	..	92 0				
Private room walls	..	42 7½				
Clerks' do.	..	69 7½				
Record do.	..	70 7½				
Verandah walls	..	217 7½				
		492 6	1 10½	2 6	2,309	
Retiring room sides	2	6 1½	1 6	2 6	46	
Walls of dais	1	18 1½	1 1½	2 0	41	
Steps, front	1	18 6				
Do. rear	1	10 6				
Do. sides	2	11 0				
		51 0	3 0	0 6	77	
Steps, front	1	16 6				
Do. rear	1	8 6				
Do. sides	2	9 0				
		43 0	2 0	0 6	43	
Steps, front	1	14 6				
Do. rear	1	6 6				
Do. sides	2	7 0				
		35 0	1 0	0 6	18	
Total cubic feet of foundations and basement	..	..	..	..	..	2,534
<i>Brickwork in superstructure.</i>						
Court room walls	..	92 0	1 6	18 6	2,553	
Private do.	..	43 0				
Clerks' do.	..	70 0				
		113 0	1 6	14 0	2,373	
Record room walls	..	71 0				
Verandah do.	..	218 0				
		289 0	1 6	11 0	4,769	
Retiring room side walls	2	6 6	1 1½	11 0	161	
Dais walls	..	18 6	0 9	1 0	14	
Dais steps	2	3 0	1 0	0 6	3	
Total cubic feet	..	..	..	..	..	9,873
<i>Deductions—</i>						
Verandah openings	7	7 0	1 6	7 3	533	
Do.	10	6 6	1 6	7 3	707	
Do.	2	5 10½	1 6	7 3	128	
Do.	2	5 0	1 6	7 3	109	
Do.	1	4 0	1 6	7 3	44	
Do.	8	4 6	1 6	8 6	459	
Doors	1	3 0	1 6	8 6	38	
Do. private room	1	2 6	1 1½	7 0	20	
Do. retiring room	6	4 6	1 6	5 9	233	
Windows	6	4 6	0 4½	2 9	28	
Do. for recess	2	3 0	1 6	5 9	52	
Do. court room	2	3 0	0 4½	2 9	6	
Do. for recess	10	2 0	1 6	4 6	135	
Do. in record and retiring room	10	2 0	0 4½	2 9	21	
Do. recess	6	3 0	1 6	1 9	47	
Ventilators in court room	..	..	..	..	574	
Archwork as per details	..	..	..	..		
Total deduction cubic feet	..	..	..	..	3,134	
Total cubic feet of superstructure	..	..	..	..	..	6,739

Estimate Form—Detail Measurements—cont.

Detail of work.	Number.	Measurements in feet.			Area or contents.	Total quantity of each description of work.
		Length.	Breadth.	Depth.		
1	2	3	4	5	6	7
<i>Brickwork in parapets, cornice, &c.</i>						
Parapet over court	..	90 6				
Do. clerks room	..	69 3				
Do. private room	..	42 3				
Do. verandah and record room ..	..	273 9				
		475 9	1 1½	2 3	1,204	
Cornice under Cuddapah slabs—						
Court room	..	99 6				
Clerks' room	..	73 9				
Private do.	..	46 9				
Verandah and record room ..	..	285 0				
		505 0	0 4½	1 0	189	
Brackets in cornice	76	1 0	0 4½	1 0	29	
String course at head of piers, &c. ..	..	205 0	0 3	0 9	38	
Cornice over arches, windows, &c. ..	..	242 0	0 3	0 3	16	
Total cubic feet of parapets, cornice, &c. ..	..	..	..	..	..	1,475
<i>Archwork, segmental.</i>						
Verandah arches	7	9 0				
Do.	10	8 3				
Do.	2	7 9				
Do.	2	7 0				
Do.	1	6 0				
		181 0	1 6	1 1½	305	
Over doors and windows	14	6 0				
Do. do.	3	4 6				
Over windows	10	3 3				
Over ventilators	6	4 6				
		157 0	1 6	1 1½	265	
Over retiring room door	1	3 6	1 1½	1 1½	4	
Total cubic feet	..	..	..	..	..	574
<i>Stone work.</i>						
Stone slabs under beams	14	2 0	1 6	0 6	21	
Total cubic feet of stone slabs ..	..	..	..	..	..	21
<i>Earth filling in basement—</i>						
Court room	..	24 7½	17 7½	1 6	651	
Clerks' room	..	25 1½				
Private room	..	11 7½	15 7½	1 6	1,459	
Record room	..	25 7½				
Verandahs and retiring room ..	..	182 7½	6 1½	1 6	1,678	
Dais	1	6 6	5 0	1 0	33	
Total cubic feet	..	..	..	..	..	3,821
<i>Teakwood, wrought, and put up.</i>						
Court room—						
Beams	2	20 6	0 10	1 4	46	
Joists, centre, bay	13	9 0				
Do. end, bay	26	9 3	0 3	0 5	37	
Clerks' room—						
Beams	2	18 6	0 9	1 2	32	
Joists, centre, bay	12	9 1½				
Do. end, bay	24	9 3½	0 3	0 5	35	
Private room—						
Joists	12	13 6	0 3	0 8	27	
Record room—						
Beams	3	18 6	0 7½	1 2	40	
Joists	48	7 0	0 3	0 4½	32	
Verandah—						
Angle beams	7	12 0	0 6	0 7	25	
Joists including retiring room ..	92	8 0	0 3	0 4½	69	
Do. at angles	14	7 6				
Do. do.	14	6 0				
Do. do.	14	4 6	0 3	0 4½	28	
Do. do.	14	3 0				
Total cubic feet	..	..	..	..	..	371

Estimate Form—Detail Measurements—cont.

Detail of work.	Number.	Measurements in feet.			Area or contents.	Total quantity of each description of work.
		Length.	Breadth.	Depth.		
1	2	3	4	5	6	7
<i>Teakwood, wrought, and put up—cont.</i>						
Record racks (6' × 2' 3" × 9' 11")—						
Uprights	6	9 11	0 3	0 3	4	
Horizontal pieces	28	2 10½	0 2	0 3	3	
Ends and cross pieces	21	2 3	0 2	0 3	2	
Horizontal pieces for shelves ..	42	2 10½	0 3	0 1	3	
Total for one rack	..	..	..	..	12	
Total for six racks	..	..	..	..	..	72
Record racks (6' × 1' 3" × 9' 11")—						
Uprights	6	9 11	0 3	0 3	4	
Horizontal pieces	28	2 10½	0 2	0 3	3	
Ends and cross pieces	21	1 0	0 2	0 3	1	
Horizontal pieces for shelves ..	14	2 10½	0 3	0 1	1	
Total for one rack	..	..	..	..	9	
Total for three racks	..	..	..	..	..	27
Total cubic feet of teakwood work for record racks. ..	..	..	..	..	..	99
<i>Venetian and panel doors.</i>						
Doors opening into verandahs	5	3 11	..	7 11	155	
Do. in private room	1	2 6	..	8 0	20	
Total square feet	..	..	..	..	..	175
<i>Panelled doors.</i>						
Inner doors	3	3 11	..	7 11	93	
Door in retiring room	1	2 0	..	6 6	13	
Total square feet	..	..	..	..	..	106
<i>Venetian windows.</i>						
Windows outer	6	4 0	..	5 3	126	
Do. rear of court	2	2 6	..	5 3	26	
Total square feet	..	..	..	..	..	252
<i>Venetian windows with glazed tops and ½ inch square iron bars.</i>						
Record and retiring room	10	1 9½	..	4 1	73	
Total square feet	..	..	..	..	..	73
Ventilators with glazed shutters moving on side pivots	6	2 6	..	1 9	26	
Total square feet	..	..	..	..	..	26
Cuddapah slabs cornice	..	517	..	3 0	1,551	
Total square feet	..	..	..	..	..	1,551
<i>Terrace roofing.</i>						
Court room	1	26 0	19 0	..	494	
Clerks' room	1	23 6	17 0	..	451	
Private room	1	13 0	17 0	..	221	
Record room	1	27 0	17 0	..	459	
Verandahs and retiring room ..	..	187 9	7 6	..	1,408	
Total square feet	..	..	..	..	..	3,033
<i>Flooring with Cuddapah slabs on a 4 inches bed of concrete.</i>						
Court room	..	25 0	18 0	..	450	
Clerks' room	..	25 6		..		
Private room	..	12 0	16 0	..	1,016	
Record room	..	26 0		..		
Retiring room	..	6 6	6 6	..	42	
Verandahs	..	177 3	6 6	..	1,152	
Door pieces	8	4 6	1 1	..		
Do.	1	3 0	1 1	..	42	
Do.	1	2 6	0 8½	..	2	
Window pieces	6	4 6		..		
Do.	2	3 0	0 4½	..	20	
Do.	10	2 0		..		
Verandah openings	7	7 0		..		
Do.	10	6 6		..		
Do.	2	5 10½	1 6	..	210	
Do.	2	5 0		..		
Do.	1	4 0		..		
Total square feet	..	..	..	..	..	2,934

NOTE.—Doors and windows taken out in accordance with Appendix G—standard specification.

Estimate Form—Detail Measurements—cont.

Detail of work.	Number.	Measurements in feet.			Area or contents.	Total quantity of each description of work.
		Length.	Breadth.	Depth.		
1	2	3	4	5	6	7
<i>Plastering, interior.</i>						
Court room	..	86 0	..	17 6	1,505	
Clerks' room	..	83 0	..	13 0	1,807	
Private room	..	56 0	..	..	..	
Record room	..	84 0	..	10 0	1,100	
Retiring room	..	26 0	..	..	..	
Door jambs and soffits	8	22 0	..	1 1	213	
Do. do.	1	20 6	..	..	..	
Do. do.	1	17 0	..	0 9	13	
Window jambs and soffits	6	16 6	..	..	..	
Do. do.	2	15 0	..	1 1	265	
Do. do.	10	11 6	..	..	..	
Window sills	6	4 6	..	..	..	
Do.	2	3 0	..	0 7½	33	
Do.	10	2 0	..	..	..	
Windows, sides of recesses	36	0 4½	..	2 9	37	
Ventilators sides, soffits and cills	6	9 6	..	1 1	62	
Interior of parapet	..	463 0	..	2 6	1,158	
Total square feet	..	..	..	..	6,193	
<i>Deductions—</i>						
Doors	11	4 6	..	8 6	446	
Do.	1	3 0	..	..	..	
Do.	1	2 6	..	7 0	18	
Do.	6	4 6	..	..	..	
Windows	2	3 0	..	5 9	190	
Do.	10	2 0	..	4 6	90	
Do.	6	3 0	..	1 9	32	
Ventilators	..	..	..	..	..	
Total deductions square feet	..	..	..	..	776	
Total plastering square feet	..	..	..	..	..	5,417
<i>Painting, exterior.</i>						
Plinth	..	283 6	..	2 3	638	
Steps, sides	8	2 0	..	1 6	24	
Verandah and record room, exterior walls including parapet	..	282 0	..	13 0	3,666	
Interior of verandahs	..	380 6	..	10 0	3,805	
Clear storey over court (front and rear) including parapet	..	60 0	..	10 6	630	
Clear storey over court at (sides) including parapet	2	19 0	..	7 6	285	
Clear storey over clerks' room including parapet	..	73 0	..	6 0	438	
Clear storey private room including parapet	..	46 0	..	6 0	276	
Jambs and soffits of verandah openings	7	21 0	..	..	..	
Do. do.	10	20 6	..	..	..	
Do. do.	2	20 0	..	1 6	675	
Do. do.	2	19 6	..	..	..	
Do. do.	1	19 0	..	..	..	
Total square feet	..	..	..	..	10,437	
<i>Deductions—</i>						
Verandah openings	14	7 0	..	..	..	
Do.	20	6 6	..	..	..	
Do.	4	5 10½	..	7 3	2,026	
Do.	4	5 0	..	..	..	
Do.	2	4 0	..	..	..	
Doorways	5	4 6	..	8 6	217	
Do.	1	3 0	..	8 6	..	
Do.	1	2 6	..	7 0	18	
Windows	6	4 6	..	5 9	190	
Do.	2	3 0	..	5 9	..	
Do.	10	2 0	..	4 6	90	
Ventilators	6	3 0	..	1 9	32	
Total deductions square feet	..	..	..	..	2,573	
Total pointing square feet	..	..	..	..	..	7,864
<i>Painting doors and windows with 3 coats oak paint.</i>						
Venetian and panel doors	5	4 6	..	8 6	574	
Do.	1	3 0	..	8 6	51	
Panel doors	3	4 6	..	8 6	230	
Do.	1	2 6	..	7 0	35	
Venetian windows	6	4 6	..	5 9	466	
Do.	2	3 0	..	6 9	104	
Do.	10	2 0	..	4 6	270	
Ventilators	6	3 0	..	2 0	36	
Total painting square feet	..	..	..	..	..	1,766

Estimate Form—Detail Measurements—cont.

Detail of work.	Number.	Measurements in feet.			Area or contents.	Total quantity of each description of work.
		Length.	Breadth.	Depth.		
1	2	3	4	5	6	7
<i>Wood-oiling roof timbers.</i>						
Court room—						
Beams	2	18 0	..	3 6	126	
Joists	13	25 0	..	1 1	352	
Clerks' room—						
Beams	2	16 0	..	3 1	99	
Joists	12	25 6	..	1 1	332	
Private room—						
Joists	12	12 0	..	1 7	228	
Record room—						
Beams	3	16 0	..	2 11½	142	
Joists	12	26 0	..	1 0	312	
Verandah angle—						
Beams	7	9 6	..	1 8	111	
Joists	92	6 6	..	1 0	598	
Do. at angles	56	5 3	..	1 0	294	
Total square feet for main building	..	..	..	..	..	2,594
<i>Record racks (6' 0" × 2' 6" × 9' 11")—</i>						
Uprights	6	10 0	..	1 0	60	
Horizontal pieces	28	2 9	..	0 10	64	
Ends and cross pieces	21	2 0	..	0 10	35	
Horizontal pieces for shelves	42	2 9	..	0 8	77	
Total for one rack	..	..	..	..	236	
Total for six racks	..	..	..	..	..	1,416
<i>Record racks (6' 0" × 1' 3" × 9' 11")—</i>						
Uprights	6	10 0	..	1 0	60	
Horizontal pieces	28	2 9	..	0 10	64	
Ends and cross pieces	21	0 9	..	0 10	13	
Horizontal pieces for shelves	14	2 9	..	0 8	27	
Total for one rack	..	..	..	..	164	
Total for three racks	..	..	..	..	..	492
Total square feet of wood-oiling, three coats	..	..	..	..	..	4,502
Dais railing	..	..	..	..	14	Lineal feet.
<i>Pankahs.</i>						
Court room	1	10 0	..	..	..	Lineal feet.
Private room	1	6 0	..	..	16	Lineal feet.
Wooden movable ladder	..	..	..	..	1	

ESTIMATE FORM—Abstract.

Quantity.	Description of work.	Rate.	Per.	Amount.	Total.
1	2	3	4	5	6
		RS. A. P.		RS.	RS.
8,974 c. ft.	Excavation for foundations	4 10 0	1,000 c. ft.	41	..
7,994 "	Concrete in foundations with broken clinker bricks	14 0 0	100 "	1,119	..
2,534 "	Brickwork in foundations and basement with stock bricks	20 0 0	..	507	..
6,739 "	Brickwork in superstructure with stock bricks	22 0 0	..	1,483	..
1,475 "	Brickwork in parapets, cornice, &c., ...	24 0 0	..	354	..
574 "	Archwork	25 0 0	..	144	..
21 "	Stone slabs dressed under beams	2 0 0	Cubic foot.	42	..
3,821 "	Earthfilling in basement	3 0 0	1,000 c. ft.	11	..
371 "	Teakwood, wrought, and put up	3 8 0	Cubic foot.	1,299	..
99 "	Do. for record racks	4 0 0	..	396	..

Estimate Form—Abstract—cont.

Quantity.	Description of work.	Rate.	Per	Amount.	Total.
1	2	3	4	5	6
175 sq. ft.	Venetian and panel doors with iron fittings	RS. A. P. 1 1 0	Sq. foot.	RS. 186	RS. ..
106 "	Panel doors do. do.	0 14 0	..	93	..
252 "	Venetian windows do. do.	1 1 0	..	268	..
73 "	Do. with iron bars do. do.	1 12 0	..	128	..
26 "	Ventilators with glazed shutters do. do.	1 0 0	..	26	..
1,551 "	Cuddapah slabs for cornice including fixing, complete ..	25 0 0	100 sq. ft.	388	..
3,033 "	Terrace roofing with brick on edge 3" concrete and 3 courses of flat tiles plastered and polished on top and ceiling	25 0 0	..	758	..
2,934 "	Flooring with Cuddapah slabs 2" thick on a 4" bed of concrete pointed with tar and asphalte	22 0 0	..	645	..
5,417 sq. ft.	Plastering interior with chunam, 2 coats, polished ..	2 8 0	..	135	..
7,864 "	Pointing exterior black with tar and asphalte ..	3 0 0	..	236	..
1,766 "	Painting doors and windows with 3 coats oak paint ..	2 5 0	..	41	..
4,502 "	Wood-oiling roof timbers, 3 coats	0 15 0	..	42	..
14 L. ft.	Wooden railing for dais including fixing and varnishing, complete	1 8 0	L. foot	21	..
16 "	Punkahs, complete, including wheel, &c.	1 8 0	..	24	..
1 "	Wooden movable ladder	16 0 0	each	16	..
	Total	..	..	..	8,385
..	Petty supervision	2 8 0	cent.	..	210
..	Contingencies	5 0 0	cent.	..	420
	Grand total of estimate	..	..	..	9,015

Order—dated 20th April 1895, Mis. No. 1560, Revenue.

Recorded.

(True Extract.)

(Signed) W. B. AYLING,
Ag. UnderSecy. to Government.

To the Board of Revenue (Land Revenue).

RESOLUTION—dated 2nd May 1895, No. 128.

Communicated to all Collectors, except those of Madras and Nilgiris.

2. The Government will be requested to furnish the Board with twenty copies of the standard design for distribution to Collectors.

(True Copy and Extract.)

(Signed) R. C. C. CARR,
Acting Secretary.To all Collectors, except Madras and Nilgiris.
„ the Secretary to Government, Revenue Department.

APPENDIX.

Government Order, dated 4th August 1894, No. 1937 W., Public Works.

Read—the following papers:—

From M.R.Ry. S. GOPALAKRISTNIER, Avargal, Rai Bahadur, B.C.E., Executive Engineer, Salem Division, to the Superintending Engineer, IV Circle, dated 5th June 1894, No. 285 S.E.

I have the honour to inform you that the final issue of the Provincial budget for 1894-95 includes among its B. works offices at Atur and Námakkal for Stationary Sub-Magistrates. The taluk cutcherries here are comparatively new buildings constructed as per old standard design. I request to know if there is a standard design or if a standard design is likely to be shortly issued for Stationary Sub-Magistrate's office in places where it is to be constructed apart from Tahsildars' cutcherries.

2. The accommodation required by the Collector for the office is a court room:—

A court room 30' × 20',
Private room about 18' × 11',
Clerks' room (2 clerks and 1 attender) 18' × 12',
Record room 12' × 10';

Against—

A court room 25' × 18',
Private room 18' × 11',
Record room 9½' × 8' 5½",

provided for in the new standard design of taluk cutcherries. He considers court room 25' × 18' and record room 9½' × 8' 5½" too small.

3. In case there is no standard design nor one likely to be shortly issued, I request to be informed for what accommodation I may submit plans and estimates for the offices under reference.

No. 238 W.

Copy submitted to the Chief Engineer, Public Works Department, for favour of instructions.

(Signed) J. HANNAN,
Suptg. Engineer, IV Circle.

11th June 1894.

No. 398 D.

Referred to the Revenue Department for decision as to what accommodation should be provided for the Stationary Sub-Magistrates in cases such as that mentioned by the Executive Engineer and as to whether a standard design should be prepared.

OOTACAMUND,
19th June 1894.(Signed) J. PENNYCUICK, Colonel, R.E.,
Secretary to Govt., P.W.D.

Proceedings of the Board of Revenue (Land Revenue), dated 4th July 1894, Mis. No. 3668.
Read—Government Order, dated 22nd June 1894, No. 2442, Revenue.

Resolution—dated 4th July 1894, Mis. No. 3668.

In reply to Government Order, dated 22nd June 1894, Mis. No. 2442, the Board begs to state that in its opinion a standard plan for Stationary Sub-Magistrate's office should be prepared for use in cases where such buildings have to be executed separately.

2. The standard plan for Deputy Tahsildars' offices is unsuitable as it provides for sub-jail wards and a police guard, &c., for which accommodation is not required in a Stationary Sub-Magistrate's office. Officers of the latter class have the same establishments as Deputy Tahsildars, and the Board considers therefore that the dimensions of the office rooms should be the same

in each case; that is to say, the accommodation to be provided in a Stationary Sub-Magistrate's office should be as under:—

Court room 25' x 18'.
Private room 16' x 12'.
Clerks' room 25½' x 16'.
Record room 26' x 16'.

(True Copy and Extract.)

(Signed) L. M. WYNCH,
Secretary.

Mis. No. 2887, Revenue.

Transferred to the Public Works Department with an expression of concurrence in the Board's remarks.

OOTACAMUND,
24th July 1894.

(Signed) E. GIBSON,
Ag. Secy. to Government.

From the Superintending Engineer, II Circle, to the Executive Engineer, Nellore Division,
dated 19th June 1894, No. 212 N.L.

[Reference.—Executive Engineer's No. 199 N.L., dated 7th June 1894.]

Has the honour to inform the Executive Engineer that there is no separate design for a Stationary Sub-Magistrate's office; the design sanctioned in Government Order, No. 3122 W., dated 28th November 1891, communicated with this office endorsement No. 415 G1, dated 14th December 1891, for a Deputy Tahsildar's office may be adopted for a Stationary Sub-Magistrate's office.

No. 213 N.L.

Forwarded to the Chief Engineer, Public Works Department, for favour of opinion whether any alteration should be made in the type design referred to when adopted for Stationary Sub-Magistrates' offices.

19th June 1894.

(Signed) A. H. MORIN,
for Suptg. Engineer, II Circle.

Order—dated 4th August 1894, No. 1937 W., Public Works.

The Consulting Architect will prepare a standard design for a Stationary Sub-Magistrate's office providing the accommodation specified by the Board.

(True Extract.)

(Signed) J. PENNYCUICK, Colonel, R.E.,
Secretary to Govt., P.W.D.

To the Consulting Architect.
" Superintending Engineers.
" the Revenue Department.
" the Judicial "

REVENUE DEPARTMENT.

1895.

Board of Revenue

(Land Revenue),

MADRAS.

Printed May th.

Proceedings, 2nd May 1895, No. 128.

Communicating to all Collectors, except Madras and Nilgiris, Government Order circulating the type design for a Stationary Sub-Magistrate's office with terraced roofing.

Pⁿ—1,000—23-12-04.
1

REVENUE DEPARTMENT.

PROCEEDINGS OF THE MADRAS GOVERNMENT.

Copy attached.

X.
Read—Proceedings of the Board of Revenue, *Land Revenue*
dated *2nd May* 1895, No. *128*.

Order thereon, *27th May* 1895, No. *2104 Mis*.

Recorded.
2. The Public Works Department will be requested to furnish the Board of Revenue with 20 Copies of the type design required for distribution to Collectors.

(True Extract.)

W. H. S. P.
Ag. Under Secretary to Government.

To the Board of Revenue, L. R.

a Public Works Dept.

h.w.