

1ST MAY 1895, No. 1029 W., PUBLIC WORKS.

GOVERNMENT OF MADRAS.

PUBLIC WORKS DEPARTMENT.

Buildings and Roads.
Civil Works.

READ—the following papers :—

From the Inspector-General of Police, Madras, dated 19th Mar. 1895, No. 1543.

I have the honour to submit, for the sanction of Government, plans and estimates, amounting to Rs. 6,875, for additions to my office main building and to the store godowns prepared by the Consulting Architect to the Government of Madras. This work was sanctioned in G.O., No. 2580, dated 29th October 1894, Judicial Department.

2. The addition, as suggested by the Consulting Architect, of two rooms on the eastern side of the main building at the ends instead of a verandah along the whole length as formerly proposed does not interfere with the light in office room marked D in the plan forwarded with my letter No. 5905, dated 12th October 1894.

R. No. 385, Judicial.

Approved and transferred to the Public Works Department.

FORT ST. GEORGE,
1st April 1895.

(Signed) L. DAVIDSON,
Ag. Under Secretary.

Note by the Chief Engineer, Public Works Department.

The undersigned considers that the wall 85' 9" long proposed for the store godown is liable to bulge unless bonded by cross walls. Subject to this qualification, the estimate is recommended for the sanction of Government.

26th April 1895.

(Signed) J. PENNYCUICK, Colonel, R.E.,
Chief Engineer, P.W.D.

ORDER—dated 1st May 1895, No. 1029 W., Public Works.

The estimate, amounting to Rs. 6,875, for additions to the office of the Inspector-General of Police at Madras, is sanctioned and the amount is appropriated from the Provincial reserve.

2. Attention is drawn to the note by the Chief Engineer, Public Works Department, recorded above.

3. This sanction has been registered as Provincial No. 12 W. of 1895-96 and classified as Civil Buildings, Original Works.

(True Extract.)

Under Secy. to Govt., P.W.D.

To the Consulting Architect, with eight enclosures.
" Examiner, Public Works Accounts.
" Judicial Department.

Exd. C. A. Munisawmy.
Spare Copies

BUILDINGS AND ROADS.
CIVIL WORKS.

Govt. of {1895} Madras.
PUBLIC WORKS.

Dated May, 1st.

Recd.

Encl.

G.O., 1st May 1895, No. 1029 W.

MAY.

Office of the Inspector-General
of Police, Madras

Estimate of Rs. 6,875 for additions to
the —, sanctioned, and the amount appro-
priated from the Provincial reserve.

[G]
69
1,000-1-3-15.



Memorandum.

Read the following :

From the Inspector General of
Police, Madras, of 19th March 1895, No. 154.

I have the honour to submit
for the sanction of Government, plans and
estimates amounting to Rs 6,875 for additions
to my office main building and to the stor-
go-downs, prepared by the Consulting Architect
to the Government of Madras. This work was
sanctioned in G.O. No. 2580, dated 29th October
1894. J.D.

2. The addition as suggested by the
Consulting Architect, of two rooms on the
eastern side of the main building at the
ends instead of a verandah along the whole
length as formerly proposed does not interfere
with the light in office room marked 2
in the plan forwarded with my letter
5905 dated the 12th October 1894.

R.P.385-

Approved and transferred to the Public Works

For Mr George
1st April 1895.

Donald Davidson

To The Public Works Department Under Secretary

Smals 8 (plan)
 Area: 5-4-95

- no 3094 w 8 22-11-86
- " 2806 w 7 7-10-92
- " 525 10 8 22-2-93
- " 281 w 8 4-2-93
- " 3008 w 8 4-9-93
- " 3153 w 8 5-12-93
- " 2592 w 8 16-10-94
- " 2845 w 8 2-11-94
- " 1221 c 8 22-3-95

ref 31
 21/5

Information
 COM
 455

20

Note by the Chief Engr. P. W. D.

The undersigned considers
 that the wall 85' 9" long proposed
 for the store godown is liable to
 bulge unless ~~bounded~~ by cross walls.
 Subject to this qualification,
 the estimate is recommended
 for the sanction of Govt.

S

E. W. W.

corrs
 26/95

E. S.

Public Works Department.

Current No. 2716

Letter No. 385

Dated 1st April 1895

From the Judicial Department

NOTE BY TECHNICAL SECTION.

Name of work Addition to the Office
of the Insp^t General of Police, Madras

Amount of Estimate Rs 6,875

The plans & estimate under
review, amounting to Rs 6,875
have been framed with refer-
ence to G.O. No. 2845 dated
8th November 1894, and provide
for increased accommodation
for clerks in the main build-
ing by constructing two rooms
one 34 x 21'6" and another 20 x
on the eastern face of the build-
ing & for an additional en-
85'9" x 8'0" in rear of the exist-
ing store godowns, as shown
on plans in red.

The amount of the estimate
is divided as follows:-

Main building -	Rs 5,600
Store godown -	1,275
Total	Rs 6,875

The nature of soil is stated

staked to the sandy & the foundations are proposed to be laid with concrete to ground level.

The scantlings for roof timber & other steel girders are correct, and the rates fair.

It is submitted that a room 85.9' long without any partitions between, as proposed for the godowns, ~~without~~ does not appear to be safe, particularly for a store room. It would be well to have arched partitions as shown in pencil on plan, so as to bond the old & new work.

The plans & estimates have been countersigned by the D.C. of Police & approved in the Judicial Dept.

[Signature]
22.11.95

Yes. Such a length of wall is liable to bulge unless banded by cross walls.

Subject to this qualification the estimate may be sanctioned.

C.A. 188
 $\frac{25}{4} 95$

[Signature]
For orders

[Signature]

C. No. 2716

P. W. Secretariat.

Note by Budget Section.

Work Additions to the office of the Inspector General of Police, Madras.

Fund	Provincial
Service Head	Civil Buildings
Departmental Head	Original Works.
Amount of Estimate	Rs. 6,875
Expenditure in previous year	"
Allotment in current year	"
Balance required to complete	"
Total Rs.	6,875

Note of available Funds.

The work appears as item No 84 under Class B Works in the preliminary budget for 1895-96. The final budget has not yet been issued. The amount set apart for Reserve with the Govt in the preliminary budget was Rs 5,58,145.

[Signature]
23/11/95

07/31

Note by Budget Section.

PUBLIC WORKS DEPARTMENT.

N^o 1029 W. dated 1st May 1895

PROCEEDINGS OF THE MADRAS GOVERNMENT.

Read the following

Memorandum in the Judicial Department. R. No. 35 d/1 April 1895.
Note by the Chief Engineer, P.W.D. dated 26 April 1895.

The estimate amounting to Rs. 6,875, for additions to the Office of the Inspector General of Police at Madras, is sanctioned and the amount is appropriated from the Provincial reserve.

2. Attention is drawn to the note by the Chief Eng. P.W.D. recorded above.

3. This sanction has been registered as Provincial No. 12 W of 1895-96, and classified as Civil Buildings, Original Works.

*The Cons. Architect with 8 cubs
" Examiner of P.W. Accts
" Judicial Department.*

(40-4,000-14-3-95.)

CHOR

26/5

4.8.

Restimate for additions to
the office of the Inspector
General of Police at Madras

T. K.
B. M.

27/6
Govt. of 118⁹⁵ Madras.
PUBLIC WORKS.

Dated

Recd.

Encl.

G.O. 1st May 1895, No. 1029 W.

Office of the Inspector General
of Police, Madras.

—
Sum of Rs. 6875 for
additions to the —
sanctioned
the amount ap-
propriated from the
provincial reserve.

90
6

INDEXED
24/5