



Proceedings of the Board of Revenue

(Land Revenue).

Dated 1 June 1895.

No. 2807. Mis

READ the following letter from Herbert Brad Cuff, Esq., Collector of Coimbatore, dated 21 May 1895 Ref. on No. 1238 to the Secretary to the Commissioners of Land Revenue, Madras.

With reference to Board's Pro-
ceedings, No. 6997 mis dated
20 December 1894 sanctioning
the construction of the Taluk
Katchery Harar, I have the
honor to forward herewith estimate
received from the Super-
intending Engineer, 4th Circle,
and to request that you will
be

X coming to Mr -
S.O. 12-12-94
No 4854

be good enough to get the sanction
of Government.

Resolution

12-12-94 No 4894

Submitted for the sanc-
-tion of Government with reference
to G.O. dated 12-12-94 No. 4894 bis.

/ True copy & Extract /

Recd
ag. Secretary

To
The Secretary to Govt.
Revenue Dept. with
3 encls.

CS

576

(1895.)

REVENUE DEPARTMENT.

Current Number. 4126

No 3253 of 18-12-94

From

The Board of Revenue,
Land Revenue.

Received 25/6/95

Dated 1st June 1895

Received 8th June 1895

Enclosures 3.

Mis. No. 2807.

SUBJECT.

Submitting for the sanction
of Govt. estimate for con-
-structing a new Taluk Cut-
-cherry at Karur, Coimbatore
District.

P. W. CURRENT No. 4917.

ABSTRACT.

Endorsement No. 2469 mis

Approved and
transferred to the Public
Works Department.

W. B. AYLING
Ag. Under Secy to Govt.
Ootacamund } 22nd June 1895
22nd June 1895 } O. No. 27-6-95

To:
The Public Works Dept

For examination

163

19TH JULY 1895, No. 1795 W., PUBLIC WORKS.

GOVERNMENT OF MADRAS.

PUBLIC WORKS DEPARTMENT.

Buildings and Roads.
Civil Works.

READ—the following papers:—

Proceedings of the Board of Revenue (Land Revenue), dated 1st June 1895,
Mis. No. 2807.

Read—the following letter from HERBERT BRADLEY, Esq., Collector of
Coimbatore, to the Secretary to the Commissioners of Land Revenue,
dated 21st May 1895, Ref. on No. 1238/C. Rev.:—

With reference to Board's Proceedings, dated 20th December 1894, Mis.

No. 6997,* sanctioning the construction of
the Taluk cutcherry, Karur, I have the
honour to forward herewith estimate, &c.,
received from the Superintending Engi-
neer, IV Circle, and to request that you will be good enough to get the sanction of
Government.

Resolution—dated 1st June 1895, Mis. No. 2807.

Submitted for the sanction of Government with reference to G.O., dated 12th
December 1894, Mis. No. 4894.

(True Copy and Extract.)

(Signed) R. C. C. CARR,
Acting Secretary.

Mis. No. 2469, Revenue.

Approved and transferred to the Public Works Department.

Ootacamund,
22nd June 1895.

(Signed) W. B. AYLING,
Ag. Under Secy. to Government.

ORDER—dated 19th July 1895, No. 1795 W., Public Works.

The estimate amounting to Rs. 32,100, for constructing a new taluk office with
out-houses at Karur in the Coimbatore district, is sanctioned and a sum of Rs. 10,000
is appropriated for the work from the Provincial reserve.

2. This sanction has been registered as Provincial No. 44 W. of 1895-96, and
classified as Civil Buildings, Original Works.

(True Extract.)

Under Secy. to Govt., P.W.D.

To the Superintending Engineer, IV Circle, with four enclosures.
,, Examiner, Public Works Accounts.
,, Revenue Department.

Exd. T. K. Narayana Aiyangar.
Spare Copies

BUILDINGS AND ROADS.
CIVIL WORKS.

Govt. of {1895} Madras.
PUBLIC WORKS.

Dated July, 19th.

Recd.

Encl.

G.O., 19th July 1895, No. 1795 W.

JULY.

Taluk office with out-houses
at Karur

Estimate of Rs. 32,100 for constructing
a new — in Coimbatore district, sanctioned,
and a sum of Rs. 10,000 appropriated for
the work.

Public Works Department.

Current No. 4917
Letter No. 2459 M
Dated 22nd June 1895.
From the Revenue Department.

NOTE BY TECHNICAL SECTION.

Name of Work Constructing a new Taluk Office
with out houses at Karur, Coimbatore Dist.

Amount of Estimate, Rs. 32,100.

PARTICULARS OF ESTIMATE.

Main Building <u>Office.</u>	Rs. <u>29,760</u>
Subsidiary Buildings <u>Cook room</u>	<u>350</u>
<u>Latrine</u>	<u>190</u>
<u>Wire fencing the compound.</u>	<u>500</u>
Contingencies <u>about 5% (Rs 1311)</u>	<u>"</u>
Petty Supervision <u>2 1/2% (Rs 730)</u>	<u>"</u>
Land compensation	<u>1050</u>
<u>Well</u>	<u>250</u>

Total Rupees ... 32,100

PARTICULARS OF CONSTRUCTION.

Surface soil earth to a depth of 1'6"
Sub soil hard gravel.
Foundations are to be laid 3 feet deep
of concrete to ground level.

Basement is to be raised 2 feet & built
of table moulded bricks in chunnam.
Walls are to be raised as per heights
shown on the type design & built
of table moulded bricks in chunnam
with flat & circular archwork over
doors & windows &c.

the interior of the building is to be plastered with 2 coats of chunnam & polished & the exterior face painted with lin & as : phalli.

Plastering or Pointing

Flooring is to be of 8" square bricks laid over 6" of concrete & painted with cement throughout except the second room & jail wards which will be of 3/4" asphaltic over 6" of concrete.

Roofing is to be terraced with brick on edge & supported on teak beams & joists completely.

Doors and Windows are to be of teakwood of the descriptions noted in the estimate & painted with 3 coats of Carson's oak.

Roof timbers are to be of teakwood for the main building & jungle wood for the out-houses.

Scantlings are correct.

Rates The rates have been examined with the old schedule dated 1884 & found to be fair, the new schedule being with "W"

The plinth area of the main building is 10854 square feet, and the cost per square foot will be Rs. 2-10-1.

The plan and estimates have been countersigned by the Collector of the District and approved in the Revenue Department.

REMARKS.

The estimate under review has been framed with reference to G.O. No. 3253 W dated 18th Decr 1894 & provides for constructing a new Taluk office at Karur with out-houses in the Coimbatore Dist.

The estimate for the main building has been based on the types designed for taluk offices circulated with G.O. Nos. 3023 W & 2393 W dated 11th March 1891 & 19th Sept. 1893 respectively & that for the out-houses as per designs circulated with G.O. No. 1409 W dated 28th May 1889 for the kitchen & W. 1709 W of 9th July 1894 for the latrine.

Provision has been made for 24 wooden record racks & a movable slip ladder, as per design appended in G.O. No. 802 W dated 19th March 1891.

Compounded with 5 lines of plain wire 4 feet high. a lump sum of Rs 1050 has been allowed as compensation for taking up private land 360 feet square & Rs 250 for sinking a well in the compound of the proposed office.

Ans. 6.VII.95.

1795

C No 4917

S.a.d.

As the Collector recommends the early construction of the new office for the Taluk office at Karur (vide para 4 of his letter embodied in G.O. No. 3253 W of 18.12.94), an allotment of Rs 10000 has been proposed for the work in the draft order herewith submitted.

8/7/95

Rs 290,606.



The S.D. Circle with 4 copies.

" Secy P.W. Accts

" Revenue Deptt

(40-4,000-14-3-95.)

Public Works Department.

19 July 1895
OF THE MADRAS GOVERNMENT.

Read the following
Revenue (Land Revenue) No. 2807 Mis. of 1 June 1895
Revenue Deptt. No. 2469 Mis. of 22 June 1895

The estimate, amounting to Rs 32,100 for constructing a new taluk office with out-houses at Karur in the Coimbatore District, is sanctioned, and a sum of Rs 10,000 is appropriated for the work from the Provincial Reserve.

2. This sanction has been registered as Provincial No. 44 W of 1895-96, and classified as Civil Buildings, Original Works.

Cr

~~1/2~~

Estimate for a Saluk office
at Karur Coimbatore

T. Ho.
B. CMB

~~1/2~~
1/2
1/2

4917

Govt. of Madras.

PUBLIC WORKS.

Dated

Recd.

Encl.

G.O. 1917/ 1895, No. 1795a.

Salut office with
outhouses at Karur.

≡

Estimate of Rs. 32,100 for
constructing a new
in Coimbatore DT,
sanctioned and a sum
of Rs. 10,000 appropriated
for the work.

90/6

INDEXED

1917