

GOVERNMENT OF MADRAS.
PUBLIC WORKS DEPARTMENT.

Buildings and Roads.
Civil Works.

READ—the following papers:—

Proceedings of the Board of Revenue (Land Revenue), dated 26th November 1894, Mis. No. 6528.

Read—the following paper:—

From the Superintending Engineer, II Circle, to the Collector, Kistna, No. 1740 K.S., dated 31st October 1894.

With reference to G.O.,* No. 1692 W., dated 24th June 1891, I have the honour to forward herewith plans and estimates, amounting to Rs. 40,900, for constructing a first-class taluk cutcherry at Vinukonda in the Kistna district, and to request that you will be so good as to countersign and send them on to Government for early sanction.

2. An allotment of Rs. 20,000 has been provided for this work in the budget for 1895-96.

Endorsement by J. N. ATKINSON, Esq., Acting Collector of Kistna, dated 9th November 1894, Ref. on C. No. 4461-Ver.

Submitted with enclosures to the Secretary to the Commissioners of Land Revenue, Madras.

Resolution—dated 26th November 1894, Mis. No. 6528.

Submitted for the sanction of Government with reference to Government Order, dated 9th June 1891, No. 3391, Revenue.

(True Copy and Extract.)

(Signed) L. M. WYNCH,
Secretary.

No. 4989, Revenue.

The plans and estimates are approved and will be transferred to the Public Works Department for sanction.

FORT ST. GEORGE,
18th December 1894.

(Signed) R. C. C. CARR,
Under Secretary to Govt.

Note by the Chief Engineer, Public Works Department.

The foundations of the taluk office at Vinukonda are proposed to be laid partly of concrete and partly of coursed rubble. The undersigned considers that they should be of concrete throughout to ground level and two feet broader than the masonry immediately above. By this alteration a saving of Rs. 1,460 will be effected. The estimate has accordingly been reduced.

30th January 1895.

(Signed) J. PENNYCUICK, Colonel, R.E.,
Chief Engineer, P.W.D.

ORDER—dated 4th February 1895, No. 267 W., Public Works.

The estimate, amounting to Rs. 39,440 as reduced by the Chief Engineer, for constructing a first-class taluk office at Vinukonda in the Kistna district is sanctioned.

2. An allotment of Rs. 600 was made for the work in G.O., No. 148 W., dated 19th January 1895. The Superintending Engineer will report whether any additional grant is required for the current year and what amount can be spent during the next official year.

3. Attention is drawn to the Chief Engineer's note recorded above.

4. The sanction accorded in paragraph 1 has been registered as Provincial No. 96 W. of 1894-95, and classified as Civil Buildings, Original Works.

(True Extract.)

Under Secy. to Govt., P.W.D.

To the Superintending Engineer, II Circle, with seventeen enclosures.
,, Examiner, Public Works Accounts.
,, Revenue Department.

BUILDINGS AND ROADS.
CIVIL WORKS.

Govt. of {1895} Madras.
PUBLIC WORKS.

Dated February, 4th.

Recd.

Encl.

G.O., 4th Feb. 1895, No. 267 W.

FEBRUARY.

First-class taluk office
at Vinukonda

Estimate of Rs. 39,440 for constructing
a —, in the Kistna district, sanctioned with
remarks.

Proceedings of the Board of Revenue.
Land Revenue.

Dated 26th Nov. 1894.

N^o 6528 Inis.

Recd Copy of letter N^o 1740 Ks, dated 31st Oct. 1894,
from the Super^r Engineer, II Circle, to the Collector,
Kistna.

With reference to G.O. N^o 1692 W, dated
24th June 1891, I have the honor to forward herewith
the plans and estimates amounting to Rs. 40,900
for constructing a first class Taluk Catechery at
Venekonda in the Kistna District and to request
that you will be so good as to countersign and
send them on to Government for early sanction.

2. An allotment of Rs. 20,000 has been
provided for this work in the budget for 1895-96.

The following endorsement of J. H. Atkinson
Esq. Ag Collector of Kistna, dated 9th Nov. 1894,
Ref. on G.O. N^o 4461 ver.

Submitted with enclosures to the
Secretary to the Commissioners of Land Revenue,
Madras.

Resolution.

Submitted for the sanction of
Government with reference to Government
order, dated 9th June 1891, N^o 3391 Revenue.

/ True Copies & Extract /
/ Signed / L. M. Wynne
Secretary.

To, The Secretary to Govt.

R. D. with plans & estimates.

Enclosures 8.

1. Data

1. Abstract, etc.
- make for record
- racks.

1. site plan.

1. General abstract.

1. District Abstract
for main build-
ing.

1. D^o for latrine.

1. D^o for work room.

1. D^o for wire fencing.

7. Communicating
Rev. Department
G.O. N^o 3391 of the
9th June 1891.

(1894)

REVENUE DEPARTMENT.

Current Number 8870.

From

The Board of Revenue
Land Revenue.

Recd: 21.12.94

Dated 26th

Received 29th

Enclosures 12.17 (4 plans)

No. 6328 Sm.

SUBJECT.

Submitting for the
sanction of Government plans
and estimates for constructing
a Taluk Cakcherry at Venu-
Konda, Krishna Dist.

ABSTRACT.

No. 1692 & 24-6-91 ✓
4444C - 10-10-91 ✓
4837C - 2-11-91 ✓
4913C - 7-11-91 ✓
942W - 22-3-92 ✓
46W - 9-1-94 ✓
803W - 21-3-94 ✓
148W - 19-1-95 ✓ put up with
C.W. 745.

Indt. No. 4989.

The plans and
estimates are approved &
will be transferred to the
Public Works Department
for sanction.

T. E. C. C. S.
Under Secy to Govt.

For H. George
18. Decr 1894

To The Public Works Dept.
with 12 Encls.
Board of Revenue L.P.

Indt.
19.12.94

C. No. 9816 P.W.D.

Note by the Chief Engineer P.W.D.

30

The foundations of the taluk
office at Venukonda are proposed
to be laid partly of concrete
and partly of coursed rubble.
The undersigned considers
that they should be of concrete
throughout to ground level
and two feet broader than
the masonry immediately
above. By this alteration a
saving of Rs 1460 will be
effected. The estimate has
accordingly been reduced.

E. W.

C.W.
30.9.95

C.W.

Public Works Department.

No 2676 dated 14 February 1894

Current No. 9816

Letter No. 4989

Dated 18 December 1894

From the Revenue Department.

NOTE BY TECHNICAL SECTION.

Name of Work Constructing a First Class Taluk Office at Kunkundah, Kistna District

Amount of Estimate, Rs. 40,900

PARTICULARS OF ESTIMATE.

Main Building	Rs.	35,474
Roof & ladder	"	1,460
Subsidiary Buildings	"	750
Well in compound	"	930
Contingencies 5% (1813)	"	816
Petty Supervision 2 1/2% (905)	"	
Land compensation	"	500
Wire fencing with gates &c.	"	970
Total Rupees ...		40,900

PARTICULARS OF CONSTRUCTION.

Surface soil Cotton soil to an average depth of 3'3"

Sub soil Soft rock below.

Foundations are to be carried down 4 1/2 feet, the lower 2 1/2 feet to be laid with concrete & the upper 2 1/2 feet in the footings to be built with burnt stone in chunam. The verandah supporting walls to be 4 feet deep, 2 ft. concrete & 2 ft. masonry.

Basement is to be 2 feet high & built of burnt stone in chunam.

Walls are to be raised as per heights noted on the type design & built of concrete rubble in chunam with flat & arched circular archways over door openings of brick in chunam.

Plastering or Pointing

the interior of the building is to be plastered with 2 coats of chunam & the exterior is to be plastered with 2 coats of chunam & the interior is to be plastered with 2 coats of chunam.

Flooring

is to be of kapa slab stones 2" thick & laid over a bed of cement 4 1/2" thick & pointed with cement.

Roofing

is to be of flat & corrugated iron laid over teak rafters, rafters 12" & supported on teakwood timbers & the valleys provided with lead sheeting.

Doors and Windows

are to be of teakwood of the description noted in the estimate & painted with 3 coats of chocolate paint.

Roof timbers

are to be of teakwood & painted with 3 coats of zinc white paint.

Scantlings

are correct.

Rates

many of the rates cannot be checked owing to the schedules being meagre but data lists are submitted for the rates.

The plinth area of the main building is

10,793 square feet, and the cost per square

foot will be Rs. 3.4.7 including steps.

The plans and estimates have been countersigned

by the Collector of the District.

and approved in the Revenue Department.

REMARKS.

The estimates under review amounting to Rs. 40,900 for constructing a first class taluk office with subsidiary buildings at Venukonda in the Krishna Dist. have been framed with reference to G.O. W. 1692 W. dated 24th June 1891.

The estimate for the main building has been based as per revised type design approved & circulated with G.O. W. 2393 W. dated 19th Sept. 1893 & that for the out-houses as per plan circulated with G.O. W. 1409 W. dated 28th May 1889.

Provision has been made for 24 round racks & a movable wooden ladder as per design circulated with G.O. W. 802 W. dated 19th March 1891 also for sink.

ing a well 10 feet in diameter in the compound & for enclosing the compound with plain wire fencing with necessary straining & angle iron posts, a wooden main gate & 2 wrought iron hand gates.

The site has been selected by the Collector.

Collector of the Dist. for which a sum of Rs. 500 has been provided under compensation for land.

The foundations are proposed to be laid partly of concrete & partly of curved rubble, if concrete be provided throughout to ground level & with one foot projection on either side of the basement, as shown in pencil in foundation section. The saving will be Rs. 1460 including percentage charges for contingencies & petty expenses.

Site plan
should be signed
by the Collector
28/9/95

The site plan has
been signed by the Collector
28/9/95

The
19.1.95

267 W. d. 4 February 1895

PUBLIC WORKS DEPARTMENT.

PROCEEDINGS OF THE MADRAS GOVERNMENT.

READ the following

Proceedings of the Board of Revenue (Land Revenue) No. 6528 his. d. 26 Nov. 1894.
Endorsement thereon in the Revenue Department No. 4989 d. 18 Dec. 1894.
Note by the Chief Engineer P.W. Department d. 30 January 1895.

The estimate amounting

to Rs. 39,440 as reduced by the

W
1 Feb

Chief Engineer, for constructing

a first class taluk office at

Venukonda in the Krishna Dist.,

is sanctioned.

2. An allotment of Rs. 600

was made for the work in G.O.

No. 148 W. dated 19th January 1895.

The Supdy. Engineer will report

whether any additional grant

is required for the current year

and what amount can be

spent during the next official

year.

year.

3. Attention is drawn to the Chief Engineer's note recorded above.

4. The sanction accorded in para 1. has been registered as Provincial No 96W of 1894-95, and classified as Civil Buildings, Original Works.

Estimate for a first class
Taluk Office at Vankonda,
Kistna Dt.

Close
30/5/95
Σ
90-1

T₁ Km
B

He S. E. II Circle with 17 miles.
Byyar P.W. Accts
Revenue Deptt
1895

Cu
24/2

cn^o 9876
Govt. of (1895) Madras.
PUBLIC WORKS.

3344

Dated

9/2/95

Recd.

Encl.

G.O.

4/2

1895

No.

267W

First class taluk office
at Virukonda

Estimate of Rs 39,440
for constructing a —, in
the Kistna Dist sanctioned
with remarks.

90
3

T.C.C.