

CM^o 1643
Govt. of Madras.
PUBLIC WORKS.

Dated

23/3

Recd.

Encl.

G.O. 23/3 1895, No. 724W

New Police station house
at Royapettah, Madras.

Estimate of Rs 5130 for
constructing a —, same =
= toned with remarks
for execution when funds
are available.

90/5

T. C.
23/3

23RD MARCH 1895, No. 724 W., PUBLIC WORKS.

GOVERNMENT OF MADRAS.

PUBLIC WORKS DEPARTMENT.

Buildings and Roads.
Civil Works.

READ—the following papers :—

G.O., dated 1st March 1895, No. 453, Judicial.

Read—the following letter from the Commissioner of Police, Madras, dated 13th February 1895, No. 15 :—

I have the honour to forward, duly approved and countersigned, the plan and estimate, prepared by the Consulting Architect to Government as directed in paragraph 2 of G.O., No. 374, dated 16th February 1894, Judicial, for constructing a new Police station on the site of the old station at Royapettah. The amount of estimate is Rs. 5,130, and I request that Government will be pleased to sanction the same.

Order—dated 1st March 1895, No. 453, Judicial.

The plan and estimate will be approved and transferred to the Public Works Department.

(True Extract.)

(Signed) J. F. PRICE,
Chief Secretary.

Note by the Chief Engineer, Public Works Department.

The undersigned considers that the sections of the latrine bressummers might with advantage be increased from 4" × 5" to 4" × 6".

20th March 1895.

(Signed) J. PENNYCUICK, Colonel, R.E.,
Chief Engineer, P.W.D.

ORDER—dated 23rd March 1895, No. 724 W., Public Works.

The estimate, amounting to Rs. 5,130, for constructing a new Police station-house at Royapettah, Madras, is sanctioned for execution when funds are available.

2. Attention is drawn to the Chief Engineer's note recorded above.

3. This sanction has been registered as Provincial No. 121 W. of 1894-95 and classified as Civil Buildings, Original Works.

(True Extract.)

Under Secy. to Govt., P.W.D.

To the Consulting Architect to Government, with four enclosures.

" Examiner, Public Works Accounts.
" Judicial Department.

Exd. C. A. Munisawmy.

Spare Copies

BUILDINGS AND ROADS.
CIVIL WORKS.

Govt. of {1895} Madras.
PUBLIC WORKS.

Dated March, 23rd.

Recd.

Encl.

G.O., 23rd Mar. 1895, No. 724 W.

MARCH.

New Police station-house at
Royapettah, Madras

Estimate of Rs. 5,130 for constructing a
—, sanctioned, with remark, for execution
when funds are available.

[G.]
53
250-31-7-94.

*Read the following paper
G.O. dated 1st March 1895, No. 453, Judicial*



Judicial Department.

PROCEEDINGS OF THE MADRAS GOVERNMENT.

Read the following paper:—

From the Commissioner of Police, Madras, 16th February 1895 No. 15.

I have the honor to forward duly approved and countersigned the plan and estimate prepared by the Consulting Architect to Government as directed in paragraph 2 of G.O. No. 674 d/ 16th February 1894 Judicial for constructing a new Police station on the site of the old station at Royapettah. The amount of estimate is Rs. 5,130 and I request that Government will be pleased to sanction the same.

order d/ 1st March 1895 No. 453, Judicial

The plan and estimate will be approved and transferred to the Public Works Department.

/True Extract/

Lionel Davidson
for Chief Secretary.

To

The Public Works Department with enclosures.
" Commissioner of Police.

Gobt. of {1895} Madras.

1643

To

The Public Works
Dept

Encl 4 (11/11/94)
Recd. No. 3-85

No. 497 wa/22-2-94 ✓

" 1706 w - 7-7-94 ✓

Proceedings dated, 1st March 1895,
No. 453

Subject.

Approving & transferring
to the Pub. W. D. the
plan & estimates for
Constructing the new
Rozapetah Police
Station.

Copy
4/5

P.W.D.

2P

Note by the Chief Engineer P.W.D.

The undersigned considers
that the sections of the latrine
pressummers might with
advantage be increased
from 4" x 5" to 4" x 6"

I am
E.W.

copy
2/95
3

R.W.

Public Works Department.

Current No.

1603

Letter No.

A59

Dated

1st March 1895

From the

Indian Dept.

NOTE BY TECHNICAL SECTION.

Name of Work

Constructing a new Police Station house at Rayapetah, Madras

Amount of Estimate, Rs.

5130

PARTICULARS OF ESTIMATE.

Main Building

Rs.

A. 551

Demolishing old building

Subsidiary Buildings

making drains & repairing roads

108

Contingencies

5%

234

Petty Supervision

2 1/2%

120

Land compensation

1068 1/2 C. at 250 Rs. per C. = 267 1/2

112

Total Rupees ...

5130

PARTICULARS OF CONSTRUCTION.

Surface soil

Loam 2 feet deep.

Sub soil

Loamy clay.

Foundations

are 15 in wide 5 feet deep, the lower 4' 6" to the concrete 3 feet wide & the upper 6 inches built of stock bricks in mortar.

Basement

is 15 in raised 1' 6" & built of stock bricks in mortar.

Walls

of the Hall are 15 in raised 18 feet & the other rooms 14 feet & built of Clayline press bricks for the exterior walls & stock bricks in common for interior walls, with niches over doors & windows.

Plastering or Pointing

the interior of the building is to be plastered with 2 coats of chunnam & the exterior pointed.

Flooring

is to be of Cuddalore chabai laid over 4" of Cuddalore pointed with cement.

Roofing

is to be tiled throughout with brick on edge &c. except the latrine which is to be of Mangalore tiles.

Doors and Windows

are to be of teakwood of the descriptions noted in the estimate & painted with 3 coats of silicate paint.

Roof timbers

are to be of teakwood & provided 3 coats.

Scantlings

are correct except for the latrine bressumer, which appears to be slightly weak.

Rates

are fair.

The plinth area of the main building is

2000 square feet, and the cost per square foot will be Rs. 2.8.11.

The plans and estimates have been countersigned

by the Commissioner of Police

and approved in the Judicial Dept

Department.

REMARKS.

The plan submitted under no. 112 has been framed with reference to G.O. No. 497 W dated 22nd Feb 1894 & provide for constructing a new Police Station house at Royapettah on the site now occupied by the old station house, which will be demolished to make room for the new station house.

Provision has been made for purchasing 1068 1/2 sq ft of land at a cost of Rs. 112 & for constructing drains, repairing roads &c.

The accommodation proposed is as follows:-

Hall	21'6" x 20'0"
Constables room	22'0" x 14'0"
Station house officer room	15'0" x 14'0"
Store room	11'3" x 6'6"
Cell on back up	18'9" x 10'0"

Latrine ——— 10'0" x 4'9"
& a front verandah 20'0" x 7'6"

The section of the bressumer to the latrine, viz. 4" x 5" appears to be slightly weak & may be increased to 4" x 6" as the distance between points of support is 10 feet.

12.11.95

Sanction with effect that the section of the latrine bressumer is to be increased from 4" x 5" to 4" x 6". C.A.M.S.

15/3/95

PUBLIC WORKS DEPARTMENT.

No. 724 W. dated 23rd March 1895.

PROCEEDINGS OF THE MADRAS GOVERNMENT.

Read the following

Proceedings of Govt in the Judicial Deptt No. 453 of 1st March 1895
Note by the Chief Engineer, P.W. Deptt of 20th March 1895

30

W
22 Mar

The estimate, amounting to Rs 5130, for constructing a new Police Station-house at Royapettah, Madras, is sanctioned for execution when funds are available.

2. Attention is drawn to the Chief Engineer's note recorded above.

3. This sanction has been registered as Provincial No. 121 W of 1894-95, and classified as Civil Buildings, Original Works.

The C.A. to Govt with 4 enclos.

.. Exar, P.W. Deptt

.. Judicial Deptt

(40-1,000-4-2-95.)

20/3/95

11/6
Estimate for a new Police
Station-house at Royapettah,
Madras.

I to
B Col

4
=