

Public Works (1896) Department.

G.O., No. 1696 W

DATED 8 June 96

[Despatch Abstract.]

Sub Registrar's office at Katpadi
North Arcot Dh. Estimate for
Constructing a ————— sanctioned

BUILDINGS AND ROADS.
CIVIL WORKS.

Govt. of {1896} Madras.

PUBLIC WORKS.

Dated June, 8th.

Recd.

Encl.

G.O. No. 1696 W., 8th June 1896.

JUNE.

Sub-Registrar's office at
Katpadi, North Arcot District

Estimate of Rs. 3,580 for constructing a
—, sanctioned, and the amount appropriated
from the Provincial reserve.

A. No 1696 W, dy 8-June 1896.

PUBLIC WORKS DEPARTMENT.

PROCEEDINGS OF THE MADRAS GOVERNMENT.

Read the following

Proceedings of Court: in the Judicial Deptt No 845 dy 11 May 1896

The estimate, amounting
to Rs 3,580, for constructing a
Sub-Registrar's office at Katpadi
in the North Arcot District,
is sanctioned, and the
amount is appropriated
from the Provincial reserve.
2. This sanction has been
registered as Provincial
No 25 W of 1896-97 and classi-
fied as Civil Buildings,
Original Works.

To The S.E. IV Circle with benches.
" Kexar P.W. Accts
" Judicial Deptt

DE.

CR
16.86.

[Faint handwritten text, likely bleed-through from the reverse side of the page. Some legible words include: "estimate for a sub-Registrar's office at Katpadi, North Arcot District, Madras Presidency."]

Plastering or Pointing *the interior of the build-
ing is to be plastered with*
2 coats of chunam & the interior pointed
with chunam.
Flooring *is to be of square bricks laid over 3"*
*concrete throughout except for the re-
ar room which is to be of 3/4 asphaltic.*
Roofing *is to be tenaced throughout with*
bricks on edge & complete over leak
proof.
Doors and Windows *are to be of teakwood of the*
descriptions noted in the estimate &
painted with 2 coats of canvas paint.
Roof timbers *to be of teakwood & wood-oiled*
2 coats
Scantlings *are correct*
Rates *fair, vide data list submitted*

The plinth area of the main building is
1274 square feet, and the cost per square
foot will be Rs. 2.9.1 less steps.
The plans and estimates have been countersigned
by the *Inspector General of Registrations*
and approved in the *Judicial Department*
Department.

REMARKS.
The plan & estimate under re-
view, amounting to Rs. 3580, have
been framed with reference to G.O.
No. 2258 W dated 10th September 1895
& provide for constructing a Sub
Registrar's Office at Katpadi in
the North Arcot District, as per
type design, circulated with G.O.
No. 1320 W dated 13th May 1891 with
tenaced roofing.
The site proposed has been se-
lected in consultation with the Sub
Registrar. It is ^{reported to be} Govt. land, consequently
no provision has been made in the
estimate for compensation of land.
This site, it is ^{also} reported to be ~~in the~~
situated in the heart of the village,
therefore has been made

Compounded wall for a length
of 190 feet with a gate-way
10 feet wide. The compounded
wall is to be 4 1/2 feet above ground
level.
The building is to face the
west side site plan.

[Signature]
28.1.96

Contd
1.6.96.

[Signature]

138

Public Works Department.

No. 1696 W, dt 8 June 1896.

Current No. 4580
Letter No. 845
Dated 11 May 1896
From the Judicial Department.

NOTE BY TECHNICAL SECTION.

Name of Work Constructing a Sub Registrars Office at Katpadi in the North Arcot District.

Amount of Estimate, Rs. 3580.

PARTICULARS OF ESTIMATE.

Main Building Office Rs. 3270
Subsidiary Buildings Compound wall " 310
Contingencies about 2 1/2 % Rs 89. ..
Petty Supervision do 2 1/2 % (Rs 93). ..
Land compensation nil

Total Rupees ... 3580.

PARTICULARS OF CONSTRUCTION.

Surface soil } reported to be ordinary loam.
Sub soil }

Foundations are proposed to be laid to a depth of 4 feet with concrete to ground level.

Basement is to be raised 2 feet & built of table moulded brick in mortar

Walls are to be raised as per heights indicated on the type design & built of table moulded bricks in chunam with archwork over all voids.

[G
15]

Govt. of (1896) Madras.

To

The Public Works Dept

Proceedings, No. 845 dated 11-5-1896

Subject.

Approving & transferring to P.W.D. the plans and estimates amounting to Rs 3580 for constructing a Sub-registry office at Katpadi, N. Arcot Dt.

P. W. CURRENT No. 4580

Ends 6 (2 plans)

Acas: 18.5.96

Co 2258 Wd / 10/6/95

Judicial Department.



PROCEEDINGS OF THE MADRAS GOVERNMENT.

Read the following paper—

Letter from the Superintending Engineer
4th Circle, dated 13th March 1896,
N^o 90 to the Inspector-General of Registration.

With reference to your
letter N^o 275 dated 6th February 1896,
I have the honour to transmit the
plan and estimate amounting to Rs 3,588
(as now revised) for constructing a
sub-registrar's office at Katpadi.
The site now selected is the one
pointed out by you in your letter
under reference.

Endorsement of the Inspector -
General of Registration, Madras, dated
20th April 1896, by N^o 1734.

Submitted for the sanction
of Government.

2. The construction of an

office building for the sub-registrar
of Katpadi in the North Arcot District
was sanctioned in G. O. N-1767 Judicial
dated 24th August 1895.

Order N-845, dated 11th May 1896

The plans and estimates
are approved and will be transferred
to the Public Works Department.

(True Extract)

J. H. C.

Under Secretary, P. W. D.

for Chief Secretary

To
The Public Works Department

Inspector General of Registration
with inclos. in origl.