Public Works (1896) Department.

G.O., No. 1719W

DATED 10 June 96

[Despatch Abstract.]

Police Stationhouse at Adoni, Bellary Dt. Estimate for constructing a first class — Sanctioned

[P. W. 20.
500—38-9-90.]

BACK PAPERS.

G.O.	No.	Department.	Date.	G.O.	No	Department.	Date.

FURTHER PAPERS.

G.O.	No.	Department.	Date.	G.O.	No.	Department.	Date.

BUILDINGS AND ROADS.
CIVIL WORKS.

Govt. of {1896} Madras.

PUBLIC WORKS.

Dated June, 10th.

Recd. *Encl.*

G.O. No. 1719 W., 10th June 1896.

JUNE.

Police Station-house at Adoni, Bellary District

Estimate of Rs. 2,984 for constructing a first-class —, sanctioned with the remark that Rs. 3,000 has been allotted for the work in the current year's budget.

ORDER.

No. 1719 W., 10th June 1896.

GOVERNMENT OF MADRAS.

PUBLIC WORKS DEPARTMENT.

Buildings and Roads.
Civil Works.

Read—the following papers :—

G.O. No. 822, Judicial, dated 6th May 1896.

Read—the following letter from the Inspector-General of Police, dated Madras, 15th April 1896, No. 1591:—

I have the honour to submit, for the sanction of Government, a plan and estimates amounting to Rs. 3,010 for the construction by the Public Works Department of a first-class station-house at Adóni in the Bellary district.

2. This work was approved of in G.O. No. 3096, Judicial, dated 14th December 1894.

3. It is intended that the proposed station-house should be built on the site of the present one, pushing it back to the extreme southernmost point of the platform, keeping its frontage to the north. The buildings marked in the plan as empty room and "lock-up" will be demolished, and the debris available therefrom utilized for levelling the platform. By erecting the Police station-house on the southern side, three sides of a square will be available as a parade ground, the want of which is much felt, and by the station facing north a good view of the bazaars will be obtained. A portion of the present station-house was occupied as a village choultry till March 1895.

4. A sum of Rs. 3,000 is provided for this work in the preliminary issue of the Public Works Department budget for 1896-97.

Order—No. 822, Judicial, dated 6th May 1896.

The plans and estimates are approved and will be transferred to the Public Works Department.

(True Extract.)

(Signed) F. J. WILSON,
for Chief Secretary.

Note by the Chief Engineer, Public Works Department.

The foundations should be laid to ground level with concrete throughout, instead of partly concrete and partly rubble masonry as proposed. This deviation will reduce the estimate from Rs. 3,010 to Rs. 2,984, and the estimate, as thus reduced, is recommended for sanction.

(Signed) D. McNEIL CAMPBELL, Colonel, R.E.,
Chief Engineer, P.W.D.

3rd June 1896.

Order—No. 1719 W., dated 10th June 1896.

The estimate, amounting to Rs. 2,984, as altered by the Chief Engineer, Public Works Department, for constructing a first-class Police station-house at Adóni in the Bellary district, is sanctioned.

2. There is an allotment of Rs. 3,000 for the work in the current year's budget.

3. Attention is drawn to the note by the Chief Engineer recorded above.

4. This sanction has been registered as Provincial No. 28 W. of 1896-97, and classified as Civil Buildings—Original Works.

(True Extract.)

Under Secy. to Govt., P.W.D.

To the Superintending Engineer, III Circle, with seven enclosures.
,, Examiner, Public Works Accounts.
,, Judicial Department.

Exd. T. K. Narayana Aiyangar.
Spare Copies

A

No. 1719 W, d/ 10-June 1896.

Public Works Department.

Bl Civil works

PROCEEDINGS OF THE MADRAS GOVERNMENT.

Read the following

Print

Proceedings of Govt. in the Judicial Dept., No. 822, d/6th May 1896.

Note by the Chief Engineer, P.W. Department, dated 3rd June 1896.

48

A.S.H
7.6.96

The estimate, amounting to Rs. 2,984 as altered by the Chief Engineer, P.W.D., for constructing a first class Police Station-house at Adoni in the Bellary District, is sanctioned.

2. There is an allotment of Rs. 3,000 for the work in the current year's budget.

3. Attention is drawn to the note by the Chief Engineer recorded above.

4. This sanction has been registered as Provincial No. 28 W of 1896-97, and classified as Civil Buildings, Original Works.

3/6/96

Cursd
3.6.96.

DESPATCHED

The Suptg. Engineer III Circle,
with 7 enclosures.

,, Examiner, P.W. Accounts.

,, Judicial Department.

(40—4,000—14-3-95.)

Mai

H.2

Estimate for a first class
Police station-house at
Adoni, Bellary District.

I/B

A

Superseded

PROCEEDINGS OF THE MADRAS GOVERNMENT.

READ the following

Print

Proceedings of Govt in the Judicial Deptt No 822 d/ 6th May 1896

Note by the C. E. P. W. D d/

The estimate, amounting to Rs 3010, 2984, as altered by the C. E. P.W.D. for constructing a first class Police Station-house at Adoni in the Bellary District, is sanctioned.

2. There is an allotment of Rs 3,000 for the work in the current year's budget.

3. This sanction has been registered as Provincial No of 1896-97 and classified as Civil Buildings, Original Works.

~~4~~ 3 Attention is drawn to the accompanying note by the Chief Engineer recorded above

To
The S. E. III circle with enclos:
" Exar P. W. Accts
" Judicial Deptt

Cr

Coords
1.6.96.

740—4,000—2-11-95

H2/

OS 138

Estimate for a first class Police Station-house at Adoni, Bellary Dt.

1719W

Superseded

No 1719W, d/ 10 June 1896.

P.W.Department.

C.No.4400/96

6

Note by the Chief Engineer,
P.W.D.

3 P

The foundations should be laid to ground level with concrete --- throughout instead of partly concrete and partly rubble masonry as proposed. This deviation will reduce the estimate from Rs.3,010 to Rs.2,984 and the estimate, as thus reduced, is recommended for sanction

3/6/96

E.W.

3.6.96

May

No 1719W, dt 10th June 1896.

Public Works Department.

Current No. 4400

Letter No. 822

Dated 6th May 1896

From the Judicial Department.

NOTE BY TECHNICAL SECTION.

Name of Work Constructing a first class Police Station house at Adoni, Bellary Dist.

Amount of Estimate, Rs. 3,010.

PARTICULARS OF ESTIMATE.

Main Building	Rs.	2,704
Subsidiary Buildings	,,	--
Contingencies 5%	,,	126
Petty Supervision maistry for 4 month at Rs 20	,,	80
Land compensation	,,	--
Demolishing existing buildings & levelling site	,,	100
Total Rupees ...		3,010

PARTICULARS OF CONSTRUCTION.

Surface soil Stated to be: made earth to a depth of 2 feet

Sub soil Do. black cotton 4 ft. below above.

Foundations are proposed to be laid to a depth of 6 feet, the lower 2 feet to be of concrete & the upper 4 feet in two footings built of coursed rubble in mortar 2nd sort

Basement is to be raised 2 feet & built of coursed rubble in mortar 1st sort.

Walls are to be raised 10½ feet & built of coursed rubble in mortar 1st sort with stone lintels over doors and windows

Plastering or Pointing (the interior of the building is to be plastered with 2 coats of chunam & the exterior pointed with chunam & coal dust.

Flooring is to be of Cuddapah slabs laid over 4 inches of concrete & the joints pointed with asphalte.

Roofing is to be of Mangalore tiles laid over teak reepers, rafters &c. complete & ceiled with ½" pine planks.

Doors and Windows are to be of the descriptions noted in the estimate of teakwood & painted with 2 coats of oil paint

Roof timbers are to be of teakwood & wood oiled 2 coats

Scantlings are correct

Rates are fair except for roofing & coursed rubble (vide remarks below.

The plinth area of the main building is 1,006 square feet, and the cost per square foot will be Rs. 3-0-0

The plan~~s~~ and estimate~~s~~ have been countersigned by the Inspector General of Police and approved in the Judicial Dept. ~~Department~~.

Els

REMARKS.

The plan & estimate under review, amounting to Rs 3010, have been prepared with reference to G.O. No. 11 W dated 3d January 1895 & provide for constructing a new 1st Class Police Station house at Adoni in the Bellary District, as per type design approved of in G.O. No. 1828 W dated 2d August 1880, design No. 1a for tiled roofing.

The proposed station house is to be built on the site of the present one which is to be demolished & the debris utilized for levelling the site

The following rates are in excess of the Divisional schedule but data sheets have been submitted in support of them

Coursed rubble in mortar 2d sort Rs 14-8-0 against 12-0-0
Roofing with mangalore tiles — 28-4-0 do 25-0-0

Provision has been made for arm racks, pegs for accoutrements & shelf in Inspector's room.

Loop holes are shown on plan but not estimated; these loop holes have been disallowed in G.O. No. ~~1281~~ 2181 W dated 24th August 93.

The soil being of ~~partly~~ made earth & black cotton below, it is submitted that the foundations be laid to ground level with concrete throughout, instead of partly concrete & partly rubble masonry; by this deviation a saving of Rs 26 will be effected.

29.V.96.

Sanction with Estt of this effect.

CHM
1.6.96.

Dw

For orders.

A draft G.O. sanctioning the estimate is submitted. a note by S.W. may be added if considered necessary.

Cs
29.5.96

P. W. CURRENT No. 4400

[G/15]

ovt. of {1896} Madras.

Encls 7 (2 plans)

Recd: 12.5.96

To

The Public Works Deptt.

Proceedings, No. 822 dated 6-5- 1896.

Subject.

Approving & transferring to P.W.D. the plans & estimates amounting to Rs 3010 for the construction of a 1st class station house at Adoni, Bellary District.

No. 2181 W d/ 24-8-93
11 W d/ 3-1-95
3350 d/ 11-12-76
3265 d/ 1-12-76
2557 d/ 14-8-66
243 d/ 22-1-66

ots 138

[G./53]
3,000—26-3-96

Judicial *Department.*

Rec. the following paper:—
G.O. No 822, dated 6 May 1896

CHIEF SECRETARIAT, MADRAS.

PROCEEDINGS OF THE MADRAS GOVERNMENT.

READ the following paper :— 1P

From the Inspector-General of Police, Madras, dated 15th April 1896., No.1591.

I have the honor to submit, for the sanction of Government, a plan and estimates amounting to Rs3010/. for the construction by the Public Works Department of a 1st Class Station house at Adoni in the Bellary District.

2. This work was approved of in G.O.No.3096.Judicial dated 14th December 1894.

3. It is intended that the proposed Station house should be built on the site of the present one, pushing it back to the extreme southernmost point of the platform, keeping its frontage to the north. The buildings marked in the plan as empty room and "lock-up" will be demolished and the debris available therefrom utilized for levelling the platform. By erecting the Police Station house on the southern side, three sides of a square will be available as a parade ground, the want of which is much felt, and by the Station facing North, a good view of the bazzars will be obtained. A portion of the present Station house was occupied as a Village Choultry till March 1895.

4. A sum of Rs3000. is provided for this work in the preliminary issue of the Public works Department Budget for 1896-97.

——————E E E——————

ORDER.

O R D E R. No. 822. Dated 6th May 1896.

The plans and estimates are approved and will be transferred to the Public Works Department.

(True Extract)

Under Secretary P.W.D.,
for Chief Secretary.

TO

The Public Works Department, (with Enclosures).
" Inspector-General of Police, Madras.