

6477
Public Works (1896) Department.

G.O., No. 2369 W

DATED 17 August 1896

[Despatch Abstract.]

Office: Estimate of Rs. 8500 for Constructing
a Stationary Submarine Cable — at
Kulitalai in Trincomalee St.
Sanctioned with Rs. 8500.

9/6
Tel 10/5

BACK PAPERS.

FURTHER PAPERS.

BUILDINGS AND ROADS.
CIVIL WORKS.

Government {1896} of Madras.
PUBLIC WORKS.

Recd.

Regd.

} 1896.

Enclosures

Spare copies

G.O., No. 2369 W., 17th August 1896.

AUGUST.

Office

Estimate of Rs. 8,500 for constructing a Stationary Sub-Magistrate's — at Kulittalai in Trichinopoly district, sanctioned with remarks.

GOVERNMENT OF MADRAS.

PUBLIC WORKS DEPARTMENT.

Buildings and Roads.
Civil Works.

Read—the following papers :—

Proceedings of the Board of Revenue (Land Revenue), Mis. No. 3258, dated 16th July 1896.

Read—the following letter from J. ANDREW, Esq., Collector of Trichinopoly, to the Secretary to the Commissioners of Land Revenue, dated 6th July 1896, R.C. No. 1772/Rev. :—

I have the honour to submit an estimate for Rs. 8,500 with site plan (received from the Superintending Engineer, VI Circle, and countersigned by me) for constructing a new building for the Stationary Sub-Magistrate's Office at Kulittalai in this district, and to request that the Board may be pleased to move Government to sanction it at an early date, as the new building is rather urgently required.

2. The construction of this building was sanctioned by Government in G.O., Mis. No. 1858, dated 10th May 1895 (Revenue Department), read in Board's Proceedings, Mis. No. 2441 L.R., dated 15th May 1895.

Resolution—Mis. No. 3258, dated 16th July 1896.

Submitted to Government in the Public Works Department for sanction.

(True Copy and Extract.)

(Signed) R. C. C. CARR,
Acting Secretary.

Note by the Chief Engineer, Public Works Department.

The following rates, which are in excess of the divisional schedule, are stated to be due to the distance from which materials can be obtained, but no data lists have been furnished in support of them :—

	RS.	A.	P.		RS.	A.	P.
(1) Brick work	18	8	0	against	15	8	0
(2) Arch work	20	0	0	do.	18	12	0
(3) Teakwood work	4	0	0	do.	3	12	0
(4) Country wood work	2	10	0	do.	2	8	0
(5) Wood-oiling	2	8	0	do.	2	0	0

Lists should now be submitted.

2. The Collector should be asked to countersign the site plan before the work is commenced.

(Signed) D. McNEIL CAMPBELL, Colonel, R.E.,
Chief Engineer.

10th August 1896.

ORDER—No. 2369 W., dated 17th August 1896.

The estimate, amounting to Rs. 8,500, for constructing a Stationary Sub-Magistrate's office at Kulittalai in the Trichinopoly district, is sanctioned.

2. There is a budget provision of Rs. 2,500 for the work in the current official year, which will, if necessary, be augmented later in the year on application from the Superintending Engineer, VI Circle.

3. Attention is drawn to the Chief Engineer's note above recorded.

4. The sanction accorded in paragraph 1 has been registered as Provincial No 53 W. of 1896-97, and classified as Civil Buildings, Original Works.

(True Extract.)

Under Secretary to Government.

To the Superintending Engineer, VI Circle, with five enclosures.
" Examiner, Public Works Accounts.
" Revenue Department.

Ed. C. M. Thumbuswamy.

Proceedings of the Board of Revenue

(Land Revenue)

No. 3258 Mis., dated 16th July 1896.

Read the following letter from J. Andrew Esquire, Collector of Trichinopoly, to the Secretary to the Commissioners of Land Revenue, Madras, R.C. No. 1772/Rev. of '96, dated 6th July 1896.

I have the honor to submit an estimate for Rs. 8,500 with site plan (received from the Superintending Engineer VI Circle and countersigned by me) for constructing a new building for the Stationary Sub-Magistrate's office at Kulittalai in this district, and to request that the Board may be pleased to move Government to sanction it at an early date, as the new building is rather urgently required.

2. The construction of this building was sanctioned by Government in Government Order No. 1858 Mis., dated 10-5-95 (Rev. Dept.) read in Board's Proceedings No. 2441 Mis. L.R., dated 15-5-95.

Resolution Submitted to Government in the Public Works Department for sanction.

(True Copy & Extract).

W. C. M.

Acting Secretary.

To

The Secretary to Govt. ^{PW} Rev. Dept., with 3 enclosures.
The Collector of Trichinopoly.

1896.
Board of Revenue
(Land Revenue),
MADRAS.

Encls 5 (Klan)
Ans: 18.7.96

To

The Secretary to Govt.
P. W. D.

Pro. No. 3258 Mis.

Dated 16th July 1896.

Subject.

Submitting to Govt. in the P.W.D.
for sanction estimate for constructing a new building for the
Stationary Sub-Magistrate's office
at Kulitalai, Trichinopoly Dt.

Note by the Chief Engineer.

The following rates which
are in excess of the Divisional
schedule, are stated to be
due to the distance from which
materials ^{can} be obtained,
but no data lists have been
furnished in support of them:-

- (1) Brick work. Rs 8- against 15-8-
- (2) Arch work. 20- do 18-12-
- (3) Oakwood work. 4- do 3-12-
- (4) Country wood work. 2-10- do 2-8-
- (5) Woodriling. 2-8- do 2-0-

These lists should now be submitted.

2. The Collector should be
asked to countersign the site
plan before the work is
commenced.

Cutts
9.8.96.

Cutts
9.8.96.

Ans. 20.7.96

No. 1991 W. 76-7-96
- 18332, 7 4-4-96
- 1200 W. 720-5-96

Plastering or Pointing ^{The interior surface of walls are to be plastered with 2 coats of chunnam & the exterior pointed with chunnam.}
~~the~~ The plinth face & 3 feet above floor are to be coated 2 coats

Flooring ^{is to be of 3/4" cement concrete over 4" ordinary concrete throughout except the road worn which is to be of 3/4" asphalt}

Roofing ^{is to be of Mangalore tiles laid over teak rafters & ceiled with 1/2" white cedar planks.}

Doors and Windows ^{are to be of the descriptions noted in the estimate of teakwood & painted with 3 coats of silicate paint.}

Roof timbers ^{of trusses, bracing posts, ridge pices & bressumer are to be teak & the remaining of country wood (Ainse)}

Scantlings ^{are correct}

Rates ^{a few of the rates are high, vide remarks below.}

The plinth area of the main building is 3373 square feet, and the cost per square foot will be Rs. 2.8.7 less steps.

The plans and estimates have been countersigned by the Collector & with the site plan, they and approved in the home have been submitted Department to Govt. through this Dept.

REMARKS.

The plan & estimate under review amounting to Rs 8,500. have been framed with reference to G.O. No. 1206 W dated 20th May 1895, and provide for constructing an office for the Stationary Sub. Magistrate at Kullitalai in the Trichinopoly District, as per type design no. 1, calculated with G.O. No. 1948 W dated 6th August 1895 for tiled roofing.

The site has been selected in consultation with the Revenue authorities & is proposed to be located at the South west angle in the corner of the Taluk Office.

It is reported that the foundations proposed are the same in depth as the other two buildings in the vicinity & the S.E. considers the depth allowed

allowed is sufficient, he also thinks that the foundations to the depth proposed, viz. 7 feet can be put in economically with concrete alone, owing pro- bably to the loose nature of the soil, vide his letter attached to the estimate.

The following rates are in Rs.:
 : Cars of the Divisional schedule for which no data lists have been submitted but in the re- ports it is stated that they are due to the distances from which materials could be ob- tained.

Brick work	Rs 18.8..	against 15.8..
archwork	20.00	- do - 18.12..
Teakwood work.	4.00	- do - 3.12..
Country woodwork	2.10..	- do - 2.8..
wood lining	2.8..	- do - 2.00..

If schedule rates be adopted the saving will be Rs 290 includ- ing contingencies & 1/2% supervision.

Provision has been made for wooden ceiling racks & more: white ladders as per design, ai- calculated with G.O. No. 802 W dated 19. March 91.

on
 For order -
 Draft Pro.
 Submitted -
 King (Sanctioned)
 21/12/1895
 3. VIII. 96.
 4/12/96

Public Works Department.

Current No. 6897
 Letter No. 3258
 Dated 16th July 1896
 From the Revenue Department,

NOTE BY TECHNICAL SECTION.

Name of Work Constructing an office for the
Stationary Sub-Magistrate at Kulitalai.

Amount of Estimate, Rs. 8,500.

PARTICULARS OF ESTIMATE.

Main Building Rs. 9,030

Subsidiary Buildings " "

Contingencies 3% " 280

Petty Supervision 2 1/2% " 190

Land compensation " "

7569
 Total Rupees ... 8,500.

PARTICULARS OF CONSTRUCTION.

Surface soil reported the alluvial to a depth of 7 feet

Sub soil do - sandy with water.

Foundations are proposed to be laid to a depth
of 7 feet, the lower 2 feet to be of concrete
& the upper 5 feet built of brick in
masonry.

Basement is to be raised 3 feet & built of
brick in chumam.

Walls are to be raised as per dimensions
outlined on the upper design & built of
brick in chumam with archwork
over doors & windows.

PUBLIC WORKS DEPARTMENT.

N^o 2369 W- dated 17 August 1896

PROCEEDINGS OF THE MADRAS GOVERNMENT.

READ the following

Proceedings of the Board of Revenue (Land Revenue) N^o 3258 dated 16th July 1896
Note by the Chief Engineer dt 10th August 1896

The estimate, amounting
 to Rs 8,500, for constructing a
 stationary Sub-Magistrate's
 at Kulitalai in the Trichinopoly
 District is sanctioned.

2. There is a budget pro-
 vision of Rs 2,500 for the work
 in the current official year
 which will, if necessary, be
 augmented later in the
 year, on application from
 the Suptg. Engineer. Circle.

3. Attention is drawn to
 the Chief Engineer's note
 above recorded.

4. The sanction accorded
 in

in para 1 has been registered
as Provincial No 53 of
1896-97 and classified as
Civil Buildings, Original
Works.

Estimated for a Stationary
Sub-Magistrate's office
at Kulitalai, Madras
Dist.

CMAY
9/8/56

✓
10/8/96

MA 11.8.96

The Revenue Secretary
for papers of countermands.

T. H.
B. G.

10/27/96

To The S. R. Circle with 5 enclos.
" Esq. P. W. Accts.
" Revenue Dept.

CM