

Public Works (1896) ⁸⁹³⁷ Department.

G.O., No. 2451 W

DATED 24/August/96

[Despatch Abstract.]

Office: Estimate of Rs. 8500 for constructing
a Stationary Submagistrate's - at Dindigul
Madura S.C., sanctioned with remark.

INDEXED.

25/8

100/6
225/8

Estimate of Rs. 8,500 for constructing a Stationary Sub-Magistrate's — at Dindigul, Madura district, sanctioned with remark.

GOVERNMENT OF MADRAS.
PUBLIC WORKS DEPARTMENT.

Buildings and Roads.
Civil Works.

READ—the following papers :—

G.O., Mis. No. 2881, Revenue, dated 21st July 1896.

Read—again G.O., No. 1018 R., dated 15th May 1896, requesting the Board of Revenue to obtain and forward a plan of the proposed Stationary Sub-Magistrate's office at Dindigul.

Read—also the following Proceedings of the Board of Revenue (Land Revenue), Mis. No. 3002, dated 1st July 1896, on the above Government Order :—

The Board begs to invite the attention of Government to the instructions issued in G.O., No. 2312, Revenue, dated 20th April 1888, and to state that, as the estimate for the Stationary Sub-Magistrate's office at Dindigul, submitted to Government with Board's Proceedings, No. 1968, dated 30th April 1896, was in accordance with the standard specification, a separate plan was not forwarded therewith.

Order—Mis. No. 2881, Revenue, dated 21st July 1896.

The plans and estimate received with Board's Proceedings Mis. No. 1968, dated 30th April 1896, are approved and transferred to the Public Works Department for favour of issue of the necessary instructions.

(True Extract.)

(Signed) LIONEL DAVIDSON,
Ag. Under Secretary to Government.

Note by the Chief Engineer, Public Works Department.

The Chief Engineer considers it desirable to make the foundations entirely of concrete to ground level. The estimate is accordingly raised to Rs. 8,500 to provide for this deviation and recommended for sanction.

(Signed) D. McNEIL CAMPBELL, Col., R.E.,
Chief Engineer.

18th August 1896.

ORDER—No. 2451 W., dated 24th August 1896.

The estimate, amounting to Rs. 8,500, as altered by the Chief Engineer, Public Works Department, for constructing a Stationary Sub-Magistrate's office at Dindigul, Madura district, is sanctioned.

2. The current year's budget grant for the work is Rs. 5,000, and this will, if necessary, be augmented on application by the Superintending Engineer.

3. This sanction has been registered as Provincial No. 59 W. of 1896-97 and classified as Civil Buildings—Original works.

(True Extract.)

(Signed) D. McNEIL CAMPBELL, Colonel, R.E.,
Joint Secretary to Government.

To the Superintending Engineer, VI Circle, with seven enclosures.

” Examiner, Public Works Accounts.
” Revenue Department.

Exd. Md. Pahlvan.

No. 2451 W. dy 24th August 1896. PUBLIC WORKS DEPARTMENT.

PROCEEDINGS OF THE MADRAS GOVERNMENT.

Read the following

G.O.No.2881 Mis.Revenue,dated 21st July 1896.

Note by the Chief Engineer,P.W.D.,dated 18th August 1896.

The estimate amounting to Rs.
8,500,as altered by the Chief Engi-
neer,P.W.D.,for constructing a
Stationary Sub Magistrate's office
at Dindigul,Madura District,is sanc-
tioned.

2. The current year's budget grant
for the work is Rs.5000, and this
will,if necessary,be augmented on
application by the Superintending
Engineer.

3. This sanction has been register-
ed as Provincial No. 59 W of 1896
-97 and classified as Civil Build-
ings,Original Works.

The Suptg.Engineer VI Circle,
with 7 enclosures. ✓
,, Examiner,P.W.Accounts. ✓
,, Revenue Department. ✓

(40-4,000-2-11-95.)

18/8/96
Cmsd
18/8/96
Dy S. 4/9
Kraj

C. No. 6937

P. W. Secretariat.

Note by Budget Section.

Work *Constructing a Stationary Sub-Magistrate's office at Dindigul, Madura District.*

Fund	<i>Provincial</i>		
Service Head	<i>Civil Buildings</i>		
Departmental Head	<i>Original Works</i>		
Amount of Estimate	...	Rs.	<i>8,440</i>
Expenditure in previous year	...	"	"
Allotment in current year	...	"	<i>5,000</i>
Balance required to complete	...	"	<i>3,440</i>
Total Rs...			<i>8,440</i>

Item 51 of the final issue of the Provincial Budget for 1896-97.

Note of available Funds.

The balance at the credit of the Provincial Reserve is Rs 46,149. Rs 30,000 being reserved for works at Govt. Houses, Quindy and Madras, and the drain near the Fort, only a sum of Rs 16,149 is available for other works.

AMB
13.8.96

T Am
B AMB

Note by Budget Section.

Public Works Department.

Current No. 6937

Letter No. 2881

Dated 21st July 1896

From the Revenue Department.

TECHNICAL NOTE.

Name of Work Constructing a District Sub
Magistrate's Office at Hindigol, Madras Dis

Amount of Estimate, Rs. 8440

PARTICULARS OF ESTIMATE.

Main Building	Office	Rs.	7,342
	Record books ..		396
Subsidiary Buildings	Month's labour		16
Contingencies	5%		386
Petty Supervision	2 1/2%		200
Land compensation			nil
	Constructing culvert & diverting channel		100
Total Rupees ...			8,440.

PARTICULARS OF CONSTRUCTION.

Surface soil is reported to be ordinary earth
Sub soil is hard gravel.
Foundations are proposed to be laid to a depth
of 3 1/2 feet, the lower 2 feet to be laid
with concrete & the upper 1 1/2 feet built
of burnt stone in chumam.
Basement is to be raised 2 feet and built
of burnt stone in chumam.
Walls are to be raised as per heights indicated
on the type design & built of burnt
stone in chumam with archwork over
doors & windows of rock faced ashlar.

Estimate may be raised
to Rs 8500 & sanctioned with
a note as follows:-

The Chief Engineer considers
it desirable to make the
foundations entirely of
concrete to ground level.
The estimate is accordingly
raised to Rs 8500 to
provide for this deviation,
and recommended for sanction.

Attest
18. 8. 96

Plastering or Pointing

The interior of the building is to be plastered with 2 coats of chunam & the exterior pointed with chunam.

Flooring

is to be of 6" concrete & plastered with 3/4" cement throughout.

Roofing

is to be tiled with bricks on edge & iron tie rods & beams throughout.

Doors and Windows

are to be of teakwood of the descriptions noted in the estimate & painted with 3 coats of oil paint.

Roof timbers

are to be of teakwood & wood-oiled 2 coats.

Scantlings

are correct.

Rates

are fair.

The plinth area of the main building is 3468 square feet, and the cost per square foot will be Rs. 2-4-7 less dips.

The plans and estimates have been countersigned by the Collector of Madras and approved in the Revenue Department.

REMARKS.

The plans & estimate under review, amounting to Rs 8440, have been framed with reference to G.O. No. 287 W dated 6th Feb 1895 and provides for constructing a Stationary Sub Magistrate's Office at Vandagudi in the Madurai District. The estimate has been based on the design approved & issued, dated with G.O. No. 427 W dated 19th Feb 1895 for tiled roofing, except that the foundations have been altered to suit the nature of soil.

The site has been selected in consultation with the local Sub Magistrate & the proposed building is to be built to the South east.

of the Taluk Office & Sub Register Office, vide site plan.

A lump sum provision of Rs 100 has been made in the estimate for diverting the existing drainage channel & for constructing a new culvert at point G in line of the existing culvert at point D which is to be demolished. A level of this channel or plan of the culvert has been submitted.

The foundations are proposed to be partly of concrete & partly of stone masonry. If concrete be substituted to ground level with width 2 feet wider than the masonry above the cross will be Rs 70 only.

15.11.96

No. 24511, dt 24th August 1896.

Public Works Department.

C.No. 6937.

Note by the Chief Engineer, P.W.D.

The Chief Engineer considers it desirable to make the foundations entirely of concrete to --- ground level. The estimate is accordingly raised to Rs. 8,500 to provide for this deviation and recommended for sanction.

E.W.

Coverd
10.8.96

May

(The interior of the building is to be plastered with 2-3

1
I
E
S
R
T
T

#

ESTABLISHED

#

an
h
2
h
10
r
a
1
e
o
c
r

The ~~pm~~ plans and estimates received with Board Proceedings No. 1968 Mis., dated 30th April 1896 are approved and transferred to the Public Works Department for favour of issue of the necessary instructions.

(True Extract)

Ag. Under Secretary to Govt.

To the Public Works Department with Enclosures. ✓
Copy to the Board of Revenue, Land Revenue.

h.M. Note circulated to the Hon. Mr. Goss, C.S.E.
in 1870.

Gabt. of {1896} Madras.
REVENUE.

To

The Public Works Dept.

Dated

Reed.

Encl.

Mis.
R. G.O., 21" July 1896, No. 2881.

SUBJECT.

Approving and transferring to the Public Works Department plans and estimates for the construction of a Stationary Submagistrate's Office at Dindigul, Madura District.

No. 4276, 07 19-2-95

crossed
29.7.96

8284A.
13/8 R 24/8.

Reference on Current No 1755 of 1896.
Genl

Madura Collector's office

20th April 1896.

From

J. Twigg Esquire

Collector of
Madura.

7.

The Secretary to the Commissioners of

Land Revenue
Madras.

Sir,

In Submitting duly countersigned the plans and the estimate for Rs. 8440 received with the enclosed Superintending Engineer's letter No. 371 M.D. dated 10th Instant for the Construction of a Stationary Sub-Magistrate's office at Duidigul in the Compound of the Saluk Cutcherry, I have the honor to request that the Board will be pleased to obtain the necessary sanction of Government for the same.

2

2. The construction of the office was sanctioned in Government order Number 384

Revenue

Revenue dated 31st January 1895, communicated with
Board's Proceedings Number 498 Miscellaneous dated
4th February 1895.

I have the honor to be
Sir

Your most obedient servant.

Wm.
Collector

Chas
1894

6

7

3278 4812

No. 371 Ind.

Superintendent's Office, Madras
Peechiopoly. 13 April 1896.
8/14

GOVERNMENT OF INDIA
LAND REVENUE

From

W. Hughes Esquire
Superintending Engineer
Madras

To

The Collector of
Madras.

Sir,

Enclosures:—

1. Site Plan
1. Site Section
1. Chart of sections
of foundations
1. Estimate with report
etc.

In reference to the L.O. in
the Revenue Department No. 384 of
29 January 1895, communicated to
me with Public Works L.O. No. 287 of
dated 6 February 1895, I have the
honour to forward for your counter-
signature and submission to Govern-
ment for sanction an estimate ac-
mounting to Rs 8440 for constructing
a Stationary Sub Magistrate's office
at Diindigul in the Madras S.D.

2. The plan has been prepared
in accordance with the type design
with terraced roofing, circulated for

6537/96

To be returned
to Revenue Board
with reply.

To be returned
to Revenue Board
with reply.

adoption with G.O. No. 427 W dated
19 February 1895, except the foundation
which is altered to suit the locality.

3. No Compensation has been pro-
vided in the estimate as the build-
ing is to be within the compound
of the Takey Cutchery.

4. The channel that intercepts
the building will be diverted as shown
in red lines on the site survey, and
a small culvert built across the
road leading to the Takey Cutchery,
for which a lump sum of Rs 100 has
been provided.

5. The rates are fair and the
estimate is recommended for
sanction.

I have the honor to be
Sir,

Yours faithfully & Servant

W. Hughes

Superintending Engineer
M. K. K. K.

9/4

1755 of 1896
Cml
15-4-96

From
The Supty Engineer
M. Birch

To
The Collector of
Madura
15 APR 96
No. 371 ind.

Dt. 10th April 1896
D/14-

Factor: 4.

Stationary Sub Magis-
trates office at Dindigul
Forwarding for Comr's
signature & submission to
Govt. for sanction and
estimate of Rs. for
Constructing the —

On 6.2
6522/86
N-2021796

3278481

BUILDINGS AND ROADS.
CIVIL WORKS.

Government {1896} of Madras.
PUBLIC WORKS.

Recd. }
Regd. } 1896.
Enclosures
Spare copies

G.O., No. 2451 W., 24th August 1896.

AUGUST.

Office

Estimate of Rs. 8,500 for constructing a Stationary Sub-Magistrate's — at
Dindigul, Madura district, sanctioned with remark.

No. 2451 W., 24th August 1896.

GOVERNMENT OF MADRAS.
PUBLIC WORKS DEPARTMENT.

Buildings and Roads.
Civil Works.

Read—the following papers :—

G.O., Mis. No. 2881, Revenue, dated 21st July 1896.

Read—again G.O., No. 1018 R., dated 15th May 1896, requesting the Board of Revenue to obtain and forward a plan of the proposed Stationary Sub-Magistrate's office at Dindigul.

Read—also the following Proceedings of the Board of Revenue (Land Revenue), Mis. No. 3002, dated 1st July 1896, on the above Government Order :—

The Board begs to invite the attention of Government to the instructions issued in G.O., No. 2312, Revenue, dated 20th April 1888, and to state that, as the estimate for the Stationary Sub-Magistrate's office at Dindigul, submitted to Government with Board's Proceedings, No. 1968, dated 30th April 1896, was in accordance with the standard specification, a separate plan was not forwarded therewith.

Order—Mis. No. 2881, Revenue, dated 21st July 1896.

The plans and estimate received with Board's Proceedings Mis. No. 1968, dated 30th April 1896, are approved and transferred to the Public Works Department for favour of issue of the necessary instructions.

(True Extract.)

(Signed) LIONEL DAVIDSON,
Ag. Under Secretary to Government.

Note by the Chief Engineer, Public Works Department.

The Chief Engineer considers it desirable to make the foundations entirely of concrete to ground level. The estimate is accordingly raised to Rs. 8,500 to provide for this deviation and recommended for sanction.

(Signed) D. McNEIL CAMPBELL, Col., R.E.,
Chief Engineer.
18th August 1896.

ORDER—No. 2451 W., dated 24th August 1896.

The estimate, amounting to Rs. 8,500, as altered by the Chief Engineer, Public Works Department, for constructing a Stationary Sub-Magistrate's office at Dindigul, Madura district, is sanctioned.

2. The current year's budget grant for the work is Rs. 5,000, and this will, if necessary, be augmented on application by the Superintending Engineer.

3. This sanction has been registered as Provincial No. 59 W. of 1896-97 and classified as Civil Buildings—Original works.

(True Extract.)

Under Secretary to Government.

To the Superintending Engineer, VI Circle, with seven enclosures.
„ Examiner, Public Works Accounts.
„ Revenue Department.

Exd. Md. Pahilvan.