

Government { 1896 } of Madras.
PUBLIC WORKS.

Spare copies.

G.O., No. 2563 W., 3rd September 1896.

SEPTEMBER.

Estimate of Rs. 3,220 for additions to the Police Superintendent's office at Calicut, in Malabar district, sanctioned, and the amount appropriated from the Provincial reserve.

No. 2563 W., 3RD SEPTEMBER 1896.

GOVERNMENT OF MADRAS.
PUBLIC WORKS DEPARTMENT.

Buildings and Roads.
Civil Works.

READ—the following papers:—

G.O., No. 1110, Judicial, dated 4th July 1896.

Read—the following letter from the Inspector-General of Police, Madras, dated 8th June 1896, No. 2274:—

I have the honour to submit, duly countersigned, for the sanction of Government, a plan and an estimate, amounting to Rs. 3,180, for additions to the Police Superintendent's office at Calicut.

2. The order for the preparation of plan and estimate for the work was given in G.O., No. 2028, Judicial, dated 1st October 1895.

3. The estimate provides for extending the building on the northern side with a verandah in front. The additions to the building are required for records and stores, for which the present accommodation in the office is insufficient.

Order—No. 1110, Judicial, dated 4th July 1896.

The plan and estimate, aggregating Rs. 3,180, are approved and will be transferred to the Public Works Department.

(True Extract.)

(Signed) W. FRANCIS,
for Chief Secretary.

Note by the Chief Engineer, Public Works Department.

The foundations are proposed to be laid, to a depth of 4 feet, in sand mixed with earth, although they would have to be taken only 6 inches deeper to come to gravel. It is considered that they should be made 4 feet 6 inches deep, and to allow for this alteration the estimate is raised to Rs. 3,220.

(Signed) D. McNEIL CAMPBELL, Colonel, R.E.,
Chief Engineer.
28th August 1896.

ORDER—No. 2563 W., dated 3rd September 1896.

The estimate, amounting to Rs. 3,220, as altered by the Chief Engineer for additions to the Police Superintendent's office at Calicut, in the Malabar district, is sanctioned, and the amount is appropriated from the Provincial reserve.

No. 2563 W., 3RD SEPTEMBER 1896.

2. Attention is drawn to the Chief Engineer's note above recorded.
3. This sanction has been registered as Provincial No. 70 W. of 1896-97, and classified as Civil Buildings—Original Works.

(True Extract.)

Under Secretary to Government.

To the Superintending Engineer, IV Circle, with five enclosures.
 „ Examiner, Public Works Accounts.
 „ Judicial Department.

Ed. T. K. Narayana Aiyangar.

Estimate for additions to the
 Police Superintendents' office at Calicut, PUBLIC WORKS DEPARTMENT.

2563
 No. 2563 W., d. 3rd September 1896.

PROCEEDINGS OF THE MADRAS GOVERNMENT.

READ the following

Proceedings of Govt. in the Judicial Dept. No. 1110 d. 4 July 1896
 note by the Chief Engineer d. 78-8-96

The estimate amounting
 to Rs. ³²²⁰ 3200, as altered by the
 Chief Engineer, for additions
 to the Police Superintendents'
 office at Calicut in the
 Malabar District is sanctioned,
 and the amount is appropriated
 from the Provincial Reserve.

2. Attention is drawn to the
 Chief Engineer's note above
 recorded.

3. This sanction has been
 registered as Provincial No. 70
 W of 1896-97, and classified as

C. IV circle with 5 mchrs: Civil Buildings, Original Works.

or P.W. Accts.

Judicial Dept.

W. 40.
 10-6-96

Cu

CMS

28.8.96

P.W.D.

No. 2563W, d 3-9-96

Note by the Chief Engineer.

20

The foundations are proposed to be laid, partly with concrete and partly with latrite masonry. It is considered that they should be of concrete throughout to ground level. With this alteration, which will entail an excess of Rs 20, the estimate is recommended for sanction. to a depth of 4 feet, in sand mixed with earth, although they ^{have} have to be taken only 6 inches deeper to come to gravel. It is considered that they should be made 4' 6" deep, and to allow for this alteration the estimate is raised to Rs 3220.

C. W. D.

28/8/96

28/8/96.

CW

and

No. 2563W, dt 3-9-96

Public Works Department.

Current No. 6259

Letter No. 1110

Dated. 4 July 1896

From the

Judicial Department.

NOTE BY TECHNICAL SECTION.

Name of work.

Extending the Police Supt. Office at Calicut, Malabar Dist.

Amount of Estimate Rs 3,800.

The plan & estimate under review amounting to Rs 3,800, have been framed with reference to G.O. No. 2600 W dated 23 October 1895 & provide for extending the Police Supt. Office at Calicut in the Malabar District.

The extension will be at the northern end of the building and will consist of a room 26' x 21' with an upper room 26 1/2' x 21 1/2' and with a front verandah 7 1/2 feet to the basement floor above.

The soil is reported to be sand mixed with earth to a depth of 4 1/2 feet, below which gravel.

The foundations are proposed to be laid to a depth of 4 feet, the lower 3 feet will be of concrete to the upper one foot together with the basement raised 2 feet built with laterite stone in chunam. The superstructure walls of basement floor will be raised 12 1/2 feet to top of joists and the first floor raised.

The plan should be laid to a depth of 4 1/2 feet to meet level gravel. C.E.S. 28.8.96

curved 11 feet and will be built of
 latenti stone in masonry with flat &
 semicircular archwork over doors
 & windows. The walls will be plastered
 & both interior & exterior with two
 coats of Chumash.

The floor of the
 basement floor will be of 9" paving
 tiles laid over 4" of concrete & the first
 floor boarded with 1 1/2" of Karimar
 & adu plank laid over teak joists
 & beams. The roof of the upper
 floor will be of Mangalore tiles laid
 over teak rafters and Karimaradu
 rafters supported on teak trusses.
 The doors & windows will be of teak
 wood & painted with a coat of
 brilliant purple brown paint.

The rates are fair, high data
 lists submitted and the scant
 charge of work timber correct.
 Provision has been made for
 firing old & new roof & for open
 & a new doorway in first
 floor, vide plan.

The estimate is in order.
 21.8.96.

P.S. H. Concrete is substituted is
 ground level instead of partly
 concrete & partly latenti masonry
 the excess will be only about
 Rs 20, actual Rs 16 at estimated
 rates.

Thos.

[G.]
 53
 3,000-20-3-96

Judicial Department.



PROCEEDINGS OF THE MADRAS GOVERNMENT.

Read the following paper:—

From the Inspector-General of Police, Madras, dated 8th
 June 1896, No 2274:—

I have the honour to submit duly countersigned, for the
 sanction of Government, a plan and an estimate amounting to
 Rs 3180 for additions to the Police Superintendent's office at
 Calicut.

2. The order for the preparation of plan and estimate for
 the work was given in G.O., No 2028, Judicial, dated 1st October
 1895.

3. The estimate provides for extending the building on the
 northern side with a verandah in front. The additions to the
 building are required for records and stores, for which the
 present accommodation in the office is insufficient.

O R D E R :—No 110 dated 4th July 1896.

The plan and estimate aggregating Rs 3180 are approved
 and will be transferred to the Public Works Department.

(True Extract)

Francis

for Chief Secretary.

To

The Public Works Department
 --- Inspector-General of Police.

18/4

Gobt. of 1896 Madras.
J. M. L.

Encls 5 (1 plan)
Recd: 11.7.96

To The Public Works
Department.

Proceedings, No. 1110 dated 4th July 1896

Subject.

Approving and transferring
to P. W. D. the plans
and estimate amounting
to Rs 3,180 for additions
to the Police Supt's Office
at Calicut

No: 260815 23.10.95
2276 C 16-5-96

Public Works (1896) Department.

CURRENT No. 7696

No 2564 W, dated 3rd
September 1896.

Order

Recorded.

From

The Public Department

20/8/96

No. 849

curm
31.8.96.

Dated 10. 8. 96

Received 25. 8. 96

Enclosures -

Spare copies 105. c

SUBJECT.

Signing of papers:

Directing that, with effect
from next year, the Under
Secretaries, P. W. D and the
Asst Secretary & Mr. Deptt
shall remain at Madras for
the purpose of signing papers
instead of accompanying
travels to Bangalore.

Curm

INDEXED

[P. W. 20
1,000-5-8-90.]

27/8-10357-234-

25/9.