

7539 & 8100
Public Works (1896) Department.

G.O., No. 2684 W

DATED 21st September
1896.

22/9/96

[Despatch Abstract.]

Sub-Registrar's Office at Vadakke Viravanalloor.
Estimate of Rs. 3100 for constructing a —
in Simeevally DC, sanctioned with remarks.

==

80/6

De
20/9

P. W. DE.
1000-10-4-96.

INDEXED

4/5

Walls are the raised 14 feet to top of
= rise for the main rooms & 10' of
the front verandah & built of
in chambers with archwork in
voids

Plastering and pointing the interior & exterior surface of walls are to be plastered with 2 coats of common.

Flooring is to be of concrete, the lower 3/4" to be of concrete in lime mortar & the upper 1/2" in cement mortar, except the road worn which will be of 3/4" asphalt.

Roofing is to be tiled with bricks on edge & complete over tank joints, beams & complete.

Doors and Windows are to be of the description noted in the estimate & painted with 2 coats of dilute paint.

Roof timbers are to be of teakwood and stained with 2 coats of wood oil.

Scantlings are correct.

Rates are fair except for tiling & cut stone work.

The plinth area of the main building is 1,274 square feet, and the cost per square foot will be Rs. 2.6.0.

The plans and estimates have been countersigned by the Inspector General of Registration and approved in the Judicial Dept.

REMARKS.

The plans & estimate under review, amounting to Rs 3100, have been framed with reference to G.O. No 839 dated 4th April 1895 and provide for constructing a Sub-Registrars at Tadakkal Viravamallur in the Tirunelveli District, as per type design given & dated with G.O. No 1320 dated 13th May 1891, licensed roofing for large class of offices.

The site has been selected by the Registration Dept. in consultation with the Revenue Dept. It is private land on which a sum of Rs 38 is allowed in the estimate for compensation.

Provision has been made for providing the joints around the terrace Cuddalore slabs are not procurable

The following rates are in excess of the Divisional schedule
Dance - Rs 20.... against Rs 18....
Cut stone - 1.... do - ..8....
If schedule rates be adopted the saving will be Rs 45 only.

The estimate also provides for a lump sum of Rs 100 for demarcating the land to be taken up, forming & repairing mud compound wall & gate and a sum of Rs 30 for building a small road side Culvert in front of the gate.

The building is proposed to be laid out so as to face east & west.

[Signature]
11-9-96

CRTS
14-9-96

No 2684 W, dt 21-9-96 P.W.D

Note by the Chief Engineer

The following rates are in excess of the Divisional schedule:
Terrace - Rs 20 - .. against Rs 18....
Cut Stone - 1.... do - ..8....

If schedule rates be adopted there will be a saving of Rs 45. Data lists should be submitted in support of these items.

[Signature]
16/9/96

[Signature]
8.11

[Faint handwritten notes and signatures]

[Signature]

Public ^{Works} (1896) Department.

CURRENT No. 8106

30

From

The Judicial Department

Order

No. 1436

Dated 30th September 1896

Received 8. 9. 96

Registered — " —

Enclosures 3 (2 plans)

Spare copies.

SUBJECT.

Approving & transferring to the Public Works Department the plans and estimate amounting to Rs 3100 for the construction of a Sub-Registrar's office at Vadakku Viravandalur in the Simeenelly District.

Class A
Vim 149,

O.L.S. 401.
1221/9

BACK PAPERS.

G.O.	No.	Department.	Date.

FURTHER PAPERS.

G.O.	No.	Department.	Date.

[G.]
53
3,000-3-7-96.

Judicial

Department.



PROCEEDINGS OF THE MADRAS GOVERNMENT.

Read the following paper :—

From the Superintending Engineer, 6th Circle, Trichinopoly, dated 15th August 1896, No. 945. T. N. to the Inspector General of Registration.

In reference to your letter to the Chief Secretary to Government dated 11th March 1895, G No. 1132, communicating to me with G.O. Public Works, dated 4th April 1895, No. 839 W, I have the honour to forward for your countersignature and submission to Government for sanction an estimate of Rs3100 for the construction of a Sub-Registrar's office at Vadakku Viravanallur in the Ambasamudram Taluq, Tinnevely District.

The plan has been prepared in accordance with the type design with terraced roofing for the larger class of office circulated with G.O. No 1320 W, dated 13th May 1891 with alteration in the foundation, flooring and Cuddapah slab work &c, to suit the locality.

3. A sum of Rs 38 is provided in the estimate as compensation for land to be taken up for the erection of the building. The Executing Engineer reports that this site has been selected by the Registration Department in consultation with the Revenue Department and the Officers of both the Departments have countersigned the plan.

4. For rates above the ordinary data are submitted the estimate is recommended for sanction.

Endorsement of the Inspector General of Registratin dated 21st August 1896, No. G.5334.

Public Works (1896) Department.

CURRENT No. 7539

L.O. No 142

Order

From

The Supty. Engineers
VI Circle.

No. 946 J.N

Dated 15. 8. 96

Received 19. 8. 96

Enclosures

Spare copies -

SUBJECT.

Sub Registrar's office at
Vadakku Viravanallur
in the Trichinopoly Dh.
Informing that an estimate
for the construction of a -
has been forwarded to the
Inspector General of Registrar-
tion for countersignature.

Submitted for the sanction of Government.

2. The construction of an Office building for the
Sub- Registrar of Vadaku Viravanallur was sanctioned in
G.O. No. 659, Judicial dated 28th March 1895.

Hel
ORDER :- No. 1436, dated 3rd September 1896.

The plans and estimates aggregating Rs 3100 are
approved and will be transferred to the Public Works Depart-
ment.

(True Extract)

J. Hulm
for Chief Secretary.

To the Public Works Department.
To the Inspector General of Registration.
with enclosures in original

P. W. 20
1,000-5-8-96

12/9 R 21/9

BACK PAPERS.

FURTHER PAPERS.

OFFICE OF THE SUPERINTENDING INFER.

6TH CIRCLE,

No. 94672.

Trichinopoly, 15th August 1896.

From

W. Hughes Esquire
The Superintendent Engineer,
6th Circle,

To

The Chief Engineer,

 SIR_2

P. W. S.

ENCLOSURES.

In reference to G.O. No: 8397
of 4 April 1895, I have the honor to
inform you that the estimate called
for therein for the construction of a
Sub Registrar's office at Vadakku -
Vairavanallur in the Tirunelveli Dist.
has been forwarded to the Inspector
General of Registration for his counter-
signature and submission to Govt.
for sanction with this office No: 9457
of 15th August 1896

2. The amount of estimate as altered in this office is £ 3100.

Peace the hour the
his,
Yours Most obed^t. Servant.
J. S.

W. Hughes

Supr. Inquirer, or Clerk

P. W. D. 6th CIRCLE.

FROM

THE SUPERINTENDING ENGINEER,
6th CIRCLE,

TO

THE CHIEF ENGINEER,

P. W. D.

NO. 94672

Dated, 15th }
Received, 17 } August 1896.

Enclosure.

Sub. Registrar's office at
Vadaku Varamallur.

Informing that the
estimate of Rs 3100 for the
construction of a — has
been forwarded to the Ins-
pector General of Registration
for his counter signature
a submission to Govt for
sanction.

BUILDINGS AND ROADS.
CIVIL WORKS.

Government { 1896 } of Madras.
PUBLIC WORKS.

Recd.

Enclosures

1896.

Regd.

Spare copies

G.O., No. 2684 W., 21st September 1896.

SEPTEMBER.

Sub-Registrar's office at Vadakku Viravanallur

Estimate of Rs. 3,100 for constructing a —, in Tinnevely district, sanctioned
with remarks.

No. 2684 W., 21st SEPTEMBER 1896.

GOVERNMENT OF MADRAS.
PUBLIC WORKS DEPARTMENT.

Buildings and Roads,
Civil Works.

READ—the following papers :—

From W. HUGHES, Esq., Superintending Engineer, VI Circle, to the Chief Engineer, Public Works Department, dated Trichinopoly, 15th August 1896, No. 946 T.N.

In reference to G.O., No. 839 W., dated 4th April 1895, I have the honour to inform you that the estimate called for therein for the construction of a Sub-Registrar's office at Vadakku Viravanallur in the Tinnevely district has been forwarded to the Inspector-General of Registration for his countersignature and submission to Government for sanction with this office No. 945 T.N., dated 15th August 1896.

2. The amount of estimate, as altered in this office, is Rs. 3,100.

G.O., No. 1436, Judicial, dated 3rd September 1896.

Read—the following letter from the Superintending Engineer, VI Circle, to the Inspector-General of Registration, dated Trichinopoly, 15th August 1896, No. 945 T.N. :—

In reference to your letter to the Chief Secretary to Government, dated 11th March 1895, G. No. 1132, communicating to me with G.O., No. 839 W., dated 4th April 1895, I have the honour to forward, for your countersignature and submission to Government for sanction, an estimate of Rs. 3,100 for the construction of a Sub-Registrar's office at Vadakku Viravanallur in the Ambásamudram taluk, Tinnevely district.

2. The plan has been prepared in accordance with the type design with terraced roofing for the larger class of office circulated with G.O., No. 1320 W., dated 13th May 1891, with alteration in the foundation, flooring and Cuddapah slab work, &c., to suit the locality.

3. A sum of Rs. 33 is provided in the estimate as compensation for land to be taken up for the erection of the building. The Executive Engineer reports that the site has been selected by the Registration Department in consultation with the Revenue Department, and the officers of both the departments have countersigned the plan.

4. For rates above the ordinary, data are submitted; the estimate is recommended for sanction.

Endorsement of the Inspector-General of Registration, dated 2nd August 1896, No. G. 5334.

Submitted for the sanction of Government.

2. The construction of an office building for the Sub-Registrar of Vadakku Viravanallur was sanctioned in G.O., No. 659, Judicial, 28th March 1895.

8260

Public Works (1896) Department.

2

No. 2684 W., 21st SEPTEMBER 1896.

Order—No. 1436, Judicial, dated 3rd September 1896.

The plans and estimates, aggregating Rs. 3,100, are approved and will be transferred to the Public Works Department.

(True Extract.)

(Signed) F. J. WILSON,
for Chief Secretary.

Note by the Chief Engineer, Public Works Department.

The following rates are in excess of the divisional schedule:—

Terrace	...	...	...	...	...	...	Rs. 20 against Rs. 18.
Cut stone	...	...	...	...	...	...	Rs. 1 „ As. 8.

If schedule rates be adopted there will be a saving of Rs. 45. Data lists should be submitted in support of these items.

14th September 1896. (Signed) D. McNEIL CAMPBELL, Col., R.E.,
Chief Engineer.

ORDER—No. 2684 W., dated 21st September 1896.

The estimate, amounting to Rs. 3,100, for constructing a Sub-Registrar's office at Vadakku Viravanallur in the Tinnevely district, is sanctioned.

2. There is an allotment of Rs. 1,000 for the work in the current official year.
3. Attention is drawn to the Chief Engineer's note above recorded.
4. The sanction accorded in paragraph 1 has been registered as Provincial No. 81 W. of 1896-97, and classified as Civil Buildings—Original Works.

(True Extract.)

Under Secretary to Government.

To the Superintending Engineer, VI Circle, with seven enclosures,
Examiner, Public Works Accounts,
Judicial Department.