

6043, 9361, 9360

Public Works (1896) Department.

G.O., No. 3058-920

DATED 28th October 1896

7 miles

29/10/96

[Despatch Abstract.]

Telegraph Office: Estimate of Rs. 11,350 for constructing a — with outhouses at Vizagapatam, sanctioned with remarks and a sum of Rs. 9100 out of the budget grant for the work round to be replaced at the disposal of the Govt of India.

Telegraph Office: Reverting that a sum of Rs. 9100 or Rs. 11,330 inclusive of percentage charges may be resumed by the Govt of India from the budget grant for constructing a — with outhouses at Vizagapatam.

Estimate of Rs. 11,350 for constructing a — with out-houses at Vizagapatam, sanctioned with remarks, and a sum of Rs. 9,100 out of the budget grant for the work, ordered to be replaced at the disposal of the Government of India.

GOVERNMENT OF MADRAS.

PUBLIC WORKS DEPARTMENT.

Buildings and Roads.
Civil Works.

READ—the following papers:—

From the Superintending Engineer, I Circle, dated 1st July 1896, No. 251 V.Z.

From J. C. LARMINIE, Esq., M.I.C.E., Superintending Engineer, I Circle, to the Chief Engineer, Public Works Department, dated Cocanada, 14th October 1896, No. 529 V.Z.

In continuation of my No. 251 V.Z., dated 1st July 1896, I have the honour to submit herewith plans and estimates, amounting to Rs. 11,350, for constructing a Telegraph office with out-houses at Vizagapatam for your approval and sanction.

2. The plans and estimates have been countersigned by the Director-General of Telegraphs and returned to me through the Superintendent, East Coast Division, Vizagapatam, with a request that a battery-room on the upper floor may be added and submitted direct for the sanction of Government.

3. Early sanction to the estimate is solicited as the work is of an urgent nature.

4. Out of the existing grant of Rs. 12,100 for the work, the Executive Engineer states that only Rs. 3,000 will be spent during the current official year, and I request that the balance Rs. 9,100 may be resumed.

From the Director-General of Telegraphs, to the Secretary to the Government of Madras, Public Works Department, dated Ootacamund, 17th October 1896.

Your 17 words of 14th instant. Estimate, Vizagapatam office, is with Superintending Engineer who has been asked to expedite.

Note by the Chief Engineer, Public Works Department.

The undersigned has the honour to make the following observations:—

A teakwood beam $22\frac{1}{2} \times 10 \times 17\frac{1}{4}$, to cost Rs. 94, is provided in the estimate for signal room roof, but the Superintending Engineer notes on the plan that a rolled steel beam 10×5 , weighing 34.5 lb. per foot, should be used instead. As the load on the beam, however, will be over 19 tons; so small a section as 10×5 would be slight. A steel section 16×5 weighing 62 lb. per foot run would be necessary, but it would not cost more than about Rs. 50 in excess of a teak beam.

2. A sum of Rs. 802 is allowed for cornice-work for the upper and lower stories, the work to be done with Cuddapah slabs. As nearly Rs. 600 might be saved by substituting brick-in-mortar, the question of adopting these materials should receive the consideration of the Superintending Engineer.

3. As the two beams at the ends of the front verandah will have to carry joists they should be made 6×6 instead of 3×6 .

4. The foundations for the steps should be in footings, and not, as shown in the plan, vertically flush with the masonry above.

5. The foundations seem somewhat shallow; where there is an upper story 33' high above ground level to be carried. There they might, with advantage, be given an extra foot in depth.

(Signed) D. McNEIL CAMPBELL, Colonel, R.E.,
Chief Engineer.

24th October 1896.

ORDER—No. 3058 W., dated 28th October 1896.

The estimate, amounting to Rs. 11,350, for constructing a Telegraph office with out-houses at Vizagapatam, is sanctioned.

2. The Superintending Engineer reports that a sum of Rs. 3,000 only out of the budget grant of Rs. 12,100 can be spent on the work before the close of the current official year. The balance Rs. 9,100, or Rs. 11,330 inclusive of percentage charges will, therefore, be replaced at the disposal of the Government of India.

3. Attention is drawn to the Chief Engineer's note recorded above.

4. The sanction accorded in paragraph 1 has been registered as Imperial No. 4 W. of 1896-97, and classified as Civil Buildings—Original Works.

[Here enter No. 3059 W., dated 28th October 1896.]

(True Extract.)

Under Secretary to Government.

To the Superintending Engineer, I Circle, with twelve enclosures.
„ the Examiner, Public Works Accounts.
„ the Director-General of Telegraphs.

Estimate for Telegraph Office
at Vizagapatam

No. 3058 N. D. 28th October 1896

PROCEEDINGS OF THE MADRAS GOVERNMENT.

Buildings and Roads

Civil works

Read the following

From the Suptg. Engineer, I Circle, No. 25183 d/1st July 1896

No.

No. 52913 d/14th October 1896

Telegram from the Director General of Telegraphs d/17th October 1896

Note by the Chief Engineer d/24-10-96

The estimate, amounting to Rs 11,350, for constructing a Telegraph office with out-houses at Vizagapatam, is sanctioned.

2. The Suptg. Engineer reports that a sum of Rs 3000 only out of the budget grant of Rs 12,100 can be spent on the work before the close of the current official year. The balance Rs 9,100, or Rs 11,330 inclusive of percentage charges will, therefore, be placed at the disposal of the Govt. of India.

3. Attention is drawn to the Chief Engineer's note recorded above.

4. The sanction accorded in para 1 has been registered as

as Imperial No 4 W of 1896-97,
and classified as Civil Buildings
Original Works.

To the S. L. I Circle with 12 enclos.

" Secy P. W. Sects

" Director General of Telegraphs

H. B. No 3059 W d/ 28th October 1896.

To

The Secretary to the Govt.
of India P. W. D.

Sir,

In forwarding a copy of
Proceedings of this Govt. No 3058 W
dated 28th October 1896 sanctioning
an estimate of Rs 11,350 for constructing
a Telegraph office with out houses
at Vizagapatam, I am directed
to state that there is a provision of
Rs 12,100 for the work in the Imperial
Civil Works budget for 1896-97, and
that the year ^{being now} ~~having~~ very much
advanced, it is not practicable to
utilize more than Rs 3000. I am,
therefore, to request that the difference
Rs 9,100 or Rs 11,330 inclusive of Estab-
lishment and Tools and Plant
charges, may be resumed by the
Govt. of India.

J. S. H.
26.10.96

T. A.
B. C. M.

I have &c

On

24/10/96

20.10.96

P.W.D.
69

Note by the Chief Engineer

The undersigned has the honour to make the following observations:-

A teak-wood beam $22\frac{1}{2}'' \times 10'' \times 1\frac{1}{2}''$, to cost Rs 94, is provided in the estimate for signal room roof, but the Superintending Engineer notes on the plan that a rolled steel beam $10'' \times 5''$ weighing 34.5 lbs per foot, should be used instead. As the load on the beam, however, will be over 19 tons, so small a section as $10'' \times 5''$ would be slight. A steel section $16'' \times 5''$ weighing 62 lbs per foot run would be necessary, but it would not cost more than about Rs 50 in excess of a teak beam.

2. A sum of Rs 802 is allowed for cornice-work for the upper and lower stories, the work to be done with Cuddapah Slabs. As nearly Rs 600 might be saved by substituting brick-in-mortar, the question of adopting these materials should receive the consideration of the Superintending Engineer.

3. As the two beams at the ends of the front verandah will have to carry joists they should be made 6"x6" instead of 3"x6".

4. The foundations for the steps should be in footings, and not as shown in the plan, vertically flush with the masonry above.

5. The foundations seem somewhat shallow, since there is an upper story 33 feet high above ground level to be carried. Here they might with advantage be given an extra foot in depth. E. W.

corr

$\frac{23}{10}$ 56.

26/10/01

It is suggested that the honour to make the following observations:

A teak-wood beam $22\frac{1}{2} \times 10 \times 17\frac{1}{4}$, beam R⁹⁴, is provided in the estimate for signal room roof: but the Superintending Engineer notes in the plan that a rolled steel beam 10×8 , weighing 34.5 lbs per foot, should be used instead. As the load on the beam, however, will be over 19 tons so small a section as 10×8 would be slight. A steel section 16×8 weighing 62 lbs per foot-run would be necessary, ~~and~~ ^{but} it would not ~~be~~ ^{be} necessary ~~it~~ ^{it} cost more than about R⁸⁵⁰ in pieces of a teak beam.

2. A sum of R⁸⁰² is allowed for cornice work for the upper and lower stories. The work to be done with Cuddapa Slabs. As nearly R⁶⁰⁰ might be saved by substituting brick-in-mortar, the question of adopting these materials should receive the consideration of the Superintending Engineer.

3. As the two beams at the ends of the front verandah will have to carry joists they should be made 6×6 instead of 3×6 .
4. The foundations for the steps should be as shown in the plan, in footings, and not ^{as shown in the plan,} vertically flush with

the masonry above.

5. The foundations seem somewhat shallow when
there is an upper story 33 high above ground level & the
carried. There they might with advantage be put in
depth.

23.10.56.

The article may be continued.

23/10/56.

23/10/56.

Public Works Department.

Current No. 9361Letter No. 529 V.Z.Dated 14th October 1896.From the Superintending Engineer I Circle.

TECHNICAL NOTE.

Name of Work Constructing a Telegraph office with out houses at Vigagapatam.Amount of Estimate, Rs. 11,350Budget Grant Rs 12,100 =

PARTICULARS OF ESTIMATE.

Main Building _____ Rs 8,410Subsidiary Buildings Cust. & Lab., 2,940
Oil line & Stone shed -Contingencies Rs. 373 }Petty Supervision " 457 }Land Compensation Nil "Total Rupees ... 11,350

PARTICULARS OF CONSTRUCTION.

Surface soil Ordinary Earth 2 1/2 ft deepSub-soil Hard - do belowFoundations 4 ft in depth and will
be of concrete in mortar.Basement 2 ft. high & will be built of
Rough stone in mortar.Walls of the rooms & front verandah of the
lower story will be 15 ft high & that of back
Verandah 10'-9" to the top of joist. Walls of
the room in the upper story will be 14 ft high
& the top of joist & that of the verandah 9'-6"
all will be built of Rough stone in mortar
except the walls of the upper story which will
be built of brick in mortar.

The steps should
be plain footings.

Plastering or Pointing Walls in and out of the main building will be plastered with 2 coats of Chumaw.

Flooring will be laid with slab stones over a bed of 4" Concrete.

Roofing Main building will be terraced with brick on edge & the out-houses will be roofed with flat & pau tiles.

Doors and Windows Doors Panelled & Venetioned - Windows venetioned - For out-houses - Better doors & windows.

Roof timbers Teak wood.

Scantlings Correct according to Standard Specifications.

Rates Fair.

The plinth area of the main building is 3636 square feet, and the cost per square foot will be Rs. 2-5-0

The plans and estimates have been countersigned by the Director General of Telegraphs.
and

REMARKS.

The necessity for this work is that the existing telegraph office is in an unsafe condition & it is therefore proposed to demolish and to rebuild the same as per accompanying plan & estimate. Provision is also made in the estimate for reconstructing the Sub Dwg^g line & Store Shed which are also in an unsafe condition.

The cut stones under the beam in the Signal room are only 1 ft. in length each, as provided

If we substitute a solid beam 16" x 6" they need not be altered.

in

By formula $w = WL$

$$w = 19.69 \times 20$$

$$= 393.80.$$

The distributed load that
one foot must carry.

For this a girder $16" \times 6"$
will be suitable

vide Dorman & Long, page 58.

$10" \times 5"$ proposed by
Superintending Engineer

would be too slight. It's
depth, moreover, would be
 $\frac{1}{20}$ span.

Load on terrace.

Terrace $20' \times 10' \times \frac{3}{4}" = 150 \text{ cft} @ 120 \text{ lbs} = 18,000.$
Joists $20' \times 14' \times 10' \times 3' \times 6" = 19 \text{ cft} @ 46 \text{ lbs} = 874.$
Live load $20' \times 10' = 200 \text{ sqft} @ 120 \text{ lbs} = 24,000$
Weight of Girder $20' \times 62' (\text{Seal } 16' \times 6") = 1,240$

Total load = $44,114 \text{ lbs}.$

or $19.69 \text{ Tons}.$

in the estimate, but to distribute
the weight of the beam over a
larger area they should be not
less than 2 ft. long.

The two beams at the ends of the
front Verandah marked A & B
in pencil on the plan, should
be $6" \times 6"$ instead of $3" \times 6"$, which
scantling is insufficient to
carry the joists over them. The
extra cost of the above two items
is very trifling.

A sum of Rs. 802 is provided
in the estimate for cornice with
Cuddappa slabs for the lower
& upper stories. If the cornice
is to be done with brick in mortar,
it will cost only Rs. 212 at 6 annas
per sqft, which is the highest rate
in the Schedule for mouldings
& other ornamental work. The
total length of cornice is 566 ft.

A teak wood beam $22\frac{1}{2}" \times 10" \times 17\frac{1}{4}"$
at a cost of Rs. 94 is provided
in the estimate for the Signal
room, but in the plan the Supg.
Engineer remarks that Rolled
steel girder $10" \times 5"$ should be
provided in place of wood.

The load on the beam being
 19.69 Tons as per details in
the margin, the section proposed
by the Supg. Engr. will not suit
as the safe load it will carry
is only 8 tons. It will not also

suit

Public Works Department.

Current No. 9361
 Letter No. 529 V.V.
 Dated 14th October 1896.
 From the Superintending Engineer I Circle.

TECHNICAL NOTE.

Name of Work Constructing a Telegraph
office with out houses at Vizagapatam.

Amount of Estimate, Rs. 11,350
Budget Grant Rs 12,100 =

PARTICULARS OF ESTIMATE.

Main Building Rs. 8,410
 Subsidiary Buildings Const. a Sub., 2940
Oil line & Stone shed -
 Contingencies Rs. 373 }
 Petty Supervision 457 }
 Land Compensation Nil }

Total Rupees ... 11,350

PARTICULARS OF CONSTRUCTION.

Surface soil Ordinary Earth 2 1/2 ft deep
 Sub-soil Hard - do below same
 Foundations 4 ft in depth and will
be of Concrete in Mortar.

Basement 2 ft. high & will be built of
Rough stone in Mortar.

Walls of the rooms & front Verandah of the
lower story will be 15 ft high & that of back
Verandah 10'-9" to the top of joist. Walls of
the room in the upper story will be 14 ft high
& the top of joist & that of the Verandah 9'-6"
all will be built of Rough Stone in Mortar
except the walls of the upper story which will
be built of brick in mortar.

*The steps should
 be plain footings.*

suit the span of 20 ft, as its depth is less than $\frac{1}{20}$ th of the span -
Please see plate 69 G 10. Dorman Long's Hand book -

The girder 16x6", in plate 58 G 3 will suit for the ^{required} load nearly.

The cost of the girder is as follows: -

Price of 16x6" girder at	Cost for 1 Cut.
Messy & Co, Madras	Rs. 8-0-0
Cartage to Salt Cotars	" 0-1-0
Carriage by Rail from Madras to Vijayapattam at 13-61 pice per mile per ton. Distance, 77 $\frac{3}{4}$ miles	2-12-1
Loading & unloading	0-2-0
Cart hire from the Railway Station to the work spot	0-2-0
Hoisting & fitting charges	0-8-0
<u>Total Cost for 1 Cut: 11-9-1</u>	
<u>Says Rs. 11-10-0</u>	

Girder $22\frac{1}{2} \times 62 = 1395$ lbs. }
at Rs. 11-10-0 per Cut: } 145-0-0

Provision made in the Estimate for Teak beams } 94-0-0

Extra }
over estimate } Rs. 51

HC
21-10-96.

I have been informed that many of the so-called steel joists obtained in India are really Belgian iron. It would be more satisfactory in every way - except as regards delay - to order all iron for works of this kind, through the Indian Office. An approximate forecast of requirements might be made in this office, an indent sent to England, and the materials might on arrival be sent to the P.W. Works Madras, on which indents might be made by Superintending Engineers.

CCB
23/10/96

Public Works (1896) Department.

CURRENT No. 9360

Order

Telegram.

From

The Director General
of Telegraphs.

No.

Dated 17. 10. 96

Received 19. 10. 96

Enclosures

Spare copies

SUBJECT.

Telegraph office with out-
-houses at Vizagapatam:

Stating that the Suptg. Eng.
I circle has been asked to
expedite the submission of
the estimate for the constn.
of a —.

BACK PAPERS.

FURTHER PAPERS.

Code Class. *S.T.* INDIAN  TELEGRAPHS. Monthly Number.

To *madras.* (Office) From *Ca.* (Office)

Words.	Day.	Hour.	Minute.	Official Instructions.
<i>33/6.</i>	<i>17.</i>	<i>11.</i>	<i>33.</i>	<i>Spd Readd at</i>

To *madras. works* (Person) From *city.* (Person)
Chepauk *S. S. G.*
Teles.

Your 17 words of 14th inst estimate. vigagapatam office is with *Isupdtg* engr who has been asked to expedite.

64 Word Form.

F.C.2.

city.
Recd. from *18/18. Gillon* sent to *MADRAS* 17-10-96
At *18.* Hrs. *11.* Mts. by *11.* Telegraph Master.

U.P. No 372-27 11 91-60.0000

7 for same
soon
an
19.10.96.
City
DW

Public Works (189⁶) Department.

CURRENT No. 9361

Order

From J. C. Larmine Esq.
Supg. Engr. I Cile,
To The Chief Engineer P.W.D.

No. 529 U.Z. urgent

Dated 14.10.96

Received 19.10.96

Enclosures 4.12 (3 plans)

Spare copies

SUBJECT.

Telegraph Office with out houses
at Vizagapatam — Submit plans
and Estimates for Rs. 11350/- for
Constructing a — for sanction.

7 for sanction
soon

Copy
19.10.96.
DWS

BACK PAPERS.

FURTHER PAPERS.

hrg sub
No. 529 V.Z.

FROM

J. C. Lammie Esq. M. I. C. E.
SUPERINTENDING ENGINEER.

FIRST CIRCLE.

Enclosures. 9

TO

THE CHIEF ENGINEER

PUBLIC WORKS DEPARTMENT.

Cocanada. 8 Maoras. 1896.
WALTER. 14 October

SIR,

In continuation of my No. 251 V.3 dated 1st July 1896, I have the honor to submit herewith, plans and estimates amounting to Rs 11,350 for constructing a Telegraph office with out houses at Vizagapatam for your approval and sanction.

2. The plans and estimates have been countersigned by the Director General of Telegraphs and returned to me through the Superintendent East Coast Division Vizagapatam with a request that a Battery room on the upper floor may be added and submitted direct for the sanction of Government.

3. Early sanction to the estimate is solicited as the work is of an urgent nature.

4. Out of the existing grant of Rs 12,100 for the work, the Executive Engineer states

FROM
SUPERINTENDING ENGINEER,
FIRST CIRCLE.

TO
THE CHIEF ENGINEER

PUBLIC WORKS DEPARTMENT.

DATED
DESPATCHED
RECEIVED

189 .

No.

ENCLOSURES.

SUBJECT.

States that only Rs 3000 will
be spent during the current
official year and I request
that the balance Rs 9,100
may be resumed.

I have the honor to be

Sir,

Your most obedient Servant.

J C Paramee
Superintending Engineer
1st Circle

Lt
13/10

P. W. CURRY 6043

L.O. No 1104

Recd: 6.7.96

305857 W

In 3058-9 W

FROM W.C. De Morgan Esq
SUPERINTENDING ENGINEER
FIRST CIRCLE.

TO, THE CHIEF ENGINEER
PUBLIC WORKS DEPARTMENT.
MADRAS.

DATED 1st July 1896
DESPATCHED 3rd
RECEIVED.

No. 251 VZ.

ENCLOSURES. -

SUBJECT.

Constructing a Telegraph Office
with out-houses at Viragapattam -
Submits copy of letter to the
Telegraph Superintendent East
Coast Division, forwarding plans
and Estimates for Rs. 9040/- for
- for transmission through the
Director General of Telegraphs
for Sanction of Government.

- 3158-76 d/ 9. 1295
- 26 87C d/ 5995
- 1158N, d/ 2-4-96.
- 803W, d/ 6-3-96
- 144 W, d/ 14-1-96
- 2820 W, d/ 6-11-95
- 2528C, d/ 16-8-95
- 3336C, d/ 26-10-94
- 2357C, d/ 12-7-94
- 1514C, d/ 5-4-94
- 1311W, d/ 16-5-93
- 1145W, d/ 25-10-93

Amount received of
the plan estimate

8/7/96 W

237 Rm/7

Letter from the Superintend-
ing Engineer 1st Circle No. 250 dated 1st
July 1896 to the Telegraph Superintendent
East Coast Division Vizagapatam.

With reference to G. O No. 3156 W
dated the 9th December 1895 and the
Schedule of requirements therewith received,
I have the honor to forward herewith
plans and estimates amounting to Rs
9840 for constructing a Telegraph office
with out houses at Vizagapatam and to
request that the same may be transmitted
through the Director General Telegraphs
for the sanction of Government.

2. There is no sanctioned standard
design for Telegraph offices. The accommo-
-dation now proposed is, as will be seen
from the report which accompanies the
estimate, in accordance with the sketch
furnished by you to the Executive Engi-
-neer.

3. I may add for your information
that in the current year's Budget a sum
of Rs 12,100 has been provided for the work
in question and this cannot be exceeded
unless.

unless the Estimate receives Early Sanction.

True Copy.

No. 251 U.Z. dated 1st. July 1896.

Forwarded to the Chief Engineer
Public Works Department for in-
formation with reference to his
memo No. 2681 C dated 5.9.95.

W. Dehong An
2/7

Superintending Engineer
First Circle

Sh
1/7

Letter from the Superintendent.
-ing Engineer 1st Circle No. 250 dated 1st
July 1896 to the Telegraph Superintendent
East Coast Division Vizagapatam.

With reference to G. O. No. 3156 W
dated the 9th December 1895 and the
Schedule of requirements therewith received,
I have the honor to forward herewith
plans and estimates amounting to Rs
9840 for constructing a Telegraph office
with out houses at Vizagapatam and to
request that the same may be transmitted
through the Director General Telegraphs
for the sanction of Government.

2. There is no sanctioned standard
design for Telegraph offices. The accommo-
-dation now proposed is, as will be seen
from the report which accompanies the
estimate, in accordance with the sketch
furnished by you to the Executive Engi-
-neers.

3. I may add for your information
that in the current year's Budget a sum
of Rs 12,100 has been provided for the work
in question and this cannot be expended
unless.

V/

N^o. 3123 Cd/18. August 1896.

P. W. Department.

To
The Director General of
Telegraphs.

Sir,

The Superintending
Engineer, I Circle, having
reported that plans and
estimates, amounting to
Rs. 9,840, for constructing
a Telegraph Office with
outhouses at Vizagapatam
were forwarded to you
for approval, through
the Superintendent of
Telegraphs, East Coast
Division, on the 1 July 96.
I have the honour to
request that the trans-
mission of the same to
this Government for
execution may be ex-
pedited.

2. There is a grant of
Rs: 12,100 for the work in
the current year's Budget,
and it is desirable that
the amount required for
it should be utilised, and
that the balance should
be surrendered as early
as possible.

I have re

14/8/96
W

No 3123 Cd/18 August
1896

U.R.C.
W

~~18/8/96~~

1. Remuneration 23.9-96

No 1158 Wd/2-14-96

803 Wd/6-3-96

144 Wd/14-1-96

2820 Wd/6-11-95

2528 Cd/16-8-95

Cu

20/8

W

with fair for
info signature

0.2.5.324 12/8

GENERAL.
ACCOUNT.

Gobt. of {1895} Madras.

PUBLIC WORKS.

Dated December, 9th.

Recd.

Encl.

G.O. Nos. 3156, 3157 W., 9th Dec.
1895.

DECEMBER.

Imperial Civil Works

Forwarding Proceedings embodying the
schedule of requirements on account of —
for 1896-97.

No. 3156 W., 9TH DECEMBER 1895.

GOVERNMENT OF MADRAS.
PUBLIC WORKS DEPARTMENT.

General.
Account.

READ—the following papers :—

Procs. of the Board of Revenue (Separate Revenue), Mis. No. 4041, dated 22nd Sept. 1895.
From the Director-General of Telegraphs, dated 22nd October 1895, No. 3032.
G.O. Mis. No. 4266, Revenue, dated 29th October 1895.
From the Director-General of the Post Office of India, dated 9th Nov. 1895, No. 2700-IV.
" " " " 19th " " No. 2830-IV.

ORDER—No. 3156 W., dated 9th December 1895.

Ordered that the schedule of requirements for 1896-97 on account of Imperial Civil Works be forwarded to the Government of India, Public Works Department.
2. The officers concerned will lose no time in submitting plans and estimates for the unsanctioned works for which funds have been applied for in the schedule.
3. A sum of Rs. 20,000 has been entered under "Postal and Telegraph repairs," this being the amount provided in the current year's budget.
4. The revised list of Salt works called for from the Board of Revenue in the Proceedings of the Revenue Department, Mis. No. 4266, dated 29th October 1895, has not yet been received and cannot be waited for any longer, as the schedule has to reach the Government of India on the 15th December 1895. Any additional works that may be brought forward by the Board of Revenue will be incorporated in a supplemental schedule.

[Here enter No. 3157 W., dated 9th December 1895.]

(True Extract.)

(Signed) J. PENNYCUICK, Colonel, R.E.,
Secretary to Govt., P.W.D.

To Superintending Engineers.
" the Consulting Architect to Government.
" the Examiner, Public Works Accounts.
" the Director-General of the Post Office of India.
" the Director-General of Telegraphs.
" the Postmaster-General.
" the Chief Superintendent of Telegraphs, Madras Division.
" the Revenue Department.
" the Public Department.
" the Financial Department.

ENDORSEMENT—No. 3157 W., dated 9th December 1895.

Forwarded to the Government of India, Public Works Department.

(By order.)

(Signed) J. PENNYCUICK, Colonel, R.E.,
Secretary to Govt., P.W.D.

Exd. T. K. Narayana Aiyangar.
Spare Copies

IMPERIAL—CIVIL WORKS.

DETAIL schedule of requirements for Original Works and Repairs for 1896-97.

Requirements for 1896-97.																							
Head of classification.	Executive division and locality.		Item Number.	Projects and works.	Amount of estimate.	Outlay.		Major works.			Minor works.	Total Original works.	Repairs.	Total works and repairs.	Remarks.								
						To end of 1894-95.	Probable during 1895-96.	Works in progress.	New works.	Total.													
Postal	Architect .. Vizagapatam.	Madras .. Jeypore ..	1 2 3	Civil Buildings. New stables for the horses of the Madras General Post office. New Post office .. Minor works and repairs ..	RS.	RS. .. 1,000 ..	RS.	RS. .. 4,000 ..	RS. 13,497	RS.	RS.	RS. .. 14,000 ..	RS.		Estimate awaited. Do. Do. Do.								
																Total, Postal works ..	RS. ..	RS. ..	RS. ..	RS. ..	RS. ..	RS. ..	RS. ..
Telegraph	Vizagapatam.	Vizagapatam.	4 5	Constructing a Telegraph office. Minor works and repairs ..	RS.	RS.	RS.	RS.	RS.	RS.	RS.	RS.	RS.	Do. Do. Do.									
															Total, Telegraph works ..	RS. ..	RS. ..	RS. ..	RS. ..	RS. ..	RS. ..	RS. ..	
Meteorological.	Madura ..	Kodaikanal ..	6 7 8	Observatory building .. Residence for the Superintendent Quarters for the establishment .. Total, Meteorological works ..	RS.	RS.	RS.	RS. 20,000 15,000 ..	RS. .. 15,000 ..	RS.	RS.	RS.	RS.	RS.	Do. Do. Do. Do.								
																Total, Meteorological works ..	RS. ..	RS. ..	RS. ..	RS. ..	RS. ..	RS. ..	RS. ..
Salt	Chingleput ..	Chunampet ..	9	Restoring the cross road connecting the Chunampet-Maduranthakam road with the Merkanam-Tindivanam road. Grand Total ..	RS.	RS.	RS.	RS.	RS.	RS.	RS.	RS.	RS.	RS.	Do. Do. Do. Do.								
																Total, Civil Buildings ..	RS. ..	RS. ..	RS. ..	RS. ..	RS. ..	RS. ..	RS. ..

• Includes Mysore.

• Includes Mysore.

MADRAS PRESIDENCY.

Accompaniment to G.O. No. 3156 W., dated 9th December 1895.

IMPERIAL—CIVIL WORKS.

MADRAS PRESIDENCY.

ABSTRACT schedule of requirements for 1896-97.

ABSTRACT

Service heads.	Original Works.						Total works and repairs.
	Major Works.			Minor works.	Total.	Repairs.	
	In progress.	Not commenced.	Total.				
	RS.	RS.	RS.	RS.	RS.	RS.	RS.
	39,000	40,597	79,597	15,000	94,597	20,000	1,14,597
Civil Buildings	2,000	..	2,000	..	2,000	..	2,000
Communications	..	..	..	..	..	..	..
Miscellaneous Public Improvements ..	..	..	..	..	..	..	..
Total ..	41,000	40,597	81,597	15,000	96,597	20,000	1,16,597
Establishment	..	..	..	..	..	..	26,852
Tools and Plant	..	..	..	..	..	..	1,751
Suspense	..	..	..	..	..	..	..
Grand Total ..							1,45,200

No. 3156 W., 9TH DECEMBER 1895.

GOVERNMENT OF MADRAS.
PUBLIC WORKS DEPARTMENT.

General.
Account.

READ—the following papers :—

Procs. of the Board of Revenue (Separate Revenue), Mis. No. 4041, dated 22nd Sept. 1895.
From the Director-General of Telegraphs, dated 22nd October 1895, No. 3032.
G.O. Mis. No. 4266, Revenue, dated 29th October 1895.
From the Director-General of the Post Office of India, dated 9th Nov. 1895, No. 2700-IV.
" " " " 19th " " No. 2830-IV.

ORDER—No. 3156 W., dated 9th December 1895.

Ordered that the schedule of requirements for 1896-97 on account of Imperial Civil Works be forwarded to the Government of India, Public Works Department.

2. The officers concerned will lose no time in submitting plans and estimates for the unsanctioned works for which funds have been applied for in the schedule.

3. A sum of Rs. 20,000 has been entered under "Postal and Telegraph repairs," this being the amount provided in the current year's budget.

4. The revised list of Salt works called for from the Board of Revenue in the Proceedings of the Revenue Department, Mis. No. 4266, dated 29th October 1895, has not yet been received and cannot be waited for any longer, as the schedule has to reach the Government of India on the 15th December 1895. Any additional works that may be brought forward by the Board of Revenue will be incorporated in a supplemental schedule.

[Here enter No. 3157 W., dated 9th December 1895.]

(True Extract.)

(Signed) J. PENNYCUICK, Colonel, R.E.,
Secretary to Govt., P.W.D.

To Superintending Engineers.
" the Consulting Architect to Government.
" the Examiner, Public Works Accounts.
" the Director-General of the Post Office of India.
" the Director-General of Telegraphs.
" the Postmaster-General.
" the Chief Superintendent of Telegraphs, Madras Division.
" the Revenue Department.
" the Public Department.
" the Financial Department.

ENDORSEMENT—No. 3157 W., dated 9th December 1895.

Forwarded to the Government of India, Public Works Department.

(By order.)

(Signed) J. PENNYCUICK, Colonel, R.E.,
Secretary to Govt., P.W.D.

Exd. T. K. Narayana Aiyangar.
Spare Copies

GENERAL.
ACCOUNT.

Govt. of {1895} Madras.
PUBLIC WORKS.

Dated December, 9th.

Recd.

Encl.

G.O. Nos. 3156, 3157 W., 9th Dec.
1895.

DECEMBER.

Imperial Civil Works

Forwarding Proceedings embodying the
schedule of requirements on account of —
for 1896-97.