Public Works (1896) Department.

G.O., No. 429

Dated 14-5-96

[Despatch Abstract.]

Construction work: The execution by the P.W.D. of the — of extending the existing Malasapaka calingula, Vizagapatam &c., at an estimated cost of Rs 1230, sanctioned.

[P.W. 22. 1000-03-19-vol.]

IRRIGATION.

Govt. of {1896} Madras.

PUBLIC WORKS.

Dated May, 14th.

Read. *Encl.*

G.O. No. 429 I., 14th May 1896.

MAY.

Contribution Work

The execution by the Public Works Department of the — of extending the existing Mulagapaka calingula, Vizagapatam division, at an estimated cost of Rs. 1,230, sanctioned.

No. 429 I., 14TH MAY 1896.

GOVERNMENT OF MADRAS.

PUBLIC WORKS DEPARTMENT.

Irrigation.

READ—the following paper:—

From W. C. DEMORGAN, Esq., Executive Engineer in charge, I Circle, to the Chief Engineer for Irrigation, dated Dowlaishweram, 28th April 1896, No. 75 V.Z.

I have the honour to submit herewith plan and estimate, amounting to Rs. 1,230, including the percentage charges for establishment and tools and plant, for "extending the existing Mulagapaka calingula," received from the Executive Engineer, Vizagapatam division.

2. The necessity for the work is explained in the report accompanying the estimate.

3. The cost of the work is to be borne by the Anakápalle proprietor, who has expressed his willingness to pay the amount. I request that sanction of Government may be obtained under paragraph 79, chapter IX, Volume I of the Public Works Code, to the work being carried out by this department.

4. The work will not be commenced until the proprietor has paid the estimated amount into the treasury.

5. Prior to the work being put in hand, the ruling contained in paragraph 82 (iii), chapter IX, Volume I, will receive attention.

ENCLOSURE.

REPORT to accompany the estimate for extending the existing Mulagapaka calingula.

	RS.
Amount of estimate	1,230

The drainage area from the north and east of Anakápalle ava is nearly 42 square miles, and when the ava discharges into Krishnamarazu channel, the cross drainage is backed up by the ava water as the Mulagapaka and Chintamanu calingulas are not capable of discharging the whole drainage from the above basin. Consequently, the water spreads over the Poodimaraka road and country, besides endangering the Government supply-channel to Kondakorla ava.

From the above waterspread 1,580 acres of land have been submerged for a long time.

It is therefore proposed to extend the Mulagapaka calingula by 75 feet, so as to relieve the cultivation from submersion and reduce the risk of Government channel being breached.

The cost of this work is to be borne by the Anakápalle proprietor, who has expressed his willingness to pay the cost (*vide* his letter, dated 19th June 1895, addressed to the Collector of the district).

The whole work will be carried out in accordance with the standard specifications of the department.

(Signed) P. HAWKINS,
Asst. Engr. in charge of Vizagapatam Divn.

ORDER—No. 429 I., dated 14th May 1896.

The execution by the Public Works Department of the work referred to, at an estimated cost of Rs. 1,230, including the percentage charges for establishment and tools and plant, is sanctioned.

(True Extract.)

Under Secy. to Govt., P.W.D.,
Irrigation Branch.

To the Chief Engineer for Irrigation.
" Superintending Engineer, I Circle, with three enclosures.
" Examiner, Public Works Accounts.

Extd. T. K. Narayana Aiyangar.
Spare Copies

A file No. 429 dd 14-May 1896

PUBLIC WORKS DEPARTMENT,
IRRIGATION BRANCH.

PROCEEDINGS OF THE MADRAS GOVERNMENT.

3

UNDER date the

READ the following

From Supdg Engr, C Circl, No 7582 928.4.96

The execution by the P W Dept of the work referred to at an estimated cost of Rs 1230 including the percentage charges for establishment & tools & plant, is sanctioned.

7/5

Recd 9/5/96

DESPATCHED
29 MAY. 96

To The Chief Engr for Irrn
The S E I Circle with 3 enclos
The Examiner of Accts

1902

Report to accompany the Estimate for Extending the Existing Mulagapaka Caliugala.

2 SP

1230 Rs

Amount of Estimate Rs 1282.

The drainage area from the north and East of Anakapalli ava is nearly 42 square miles and when the ava discharges into Krishnamarazw channel, the cross drainage is backed up by the ava water as the Mulagapaka and Chintamanw Caliugalas are not capable of discharging the whole drainage from the above basin. Consequently the water spreads over the Poodimaraka road and country, besides endangering the Government supply channel to Kondakorla ava.

From the above water spread 1580 acres of land have been submerged for a long time, and destroys the fields.

It is therefore proposed to extend the mulagapaka Caliugala by 75 feet so as

I. L. Form No 1—1,000—27-11-96.

to relieve the Cultivation from
Submersion and reduce the risk of
Government Channel being breached.

The cost of this work is to be borne
by the Anakapalli Proprietor who has
expressed his willingness to pay the cost,
vide his letter dated 19th June 95 addressed
to the Collector of the District.

The whole work will be carried
out in accordance with the standard
specifications of the Department.

22 APR 96

Yours truly
Assistant Engineer
In charge of Vizagapatam
Division

W De Morgan 28/3

Rec'd 30th April 1896.

Encls-3.

Dated
No: 75 V.Z. Camp Dimbirhowa
Dy 28 4/96

From

W.C. De Morgan Esqr.
Exve Engineer incl
1st Circle

To

The Chief Engineer
for Irrigation

Sir,

I have the honour to
submit herewith plan and
estimate amounting to Rs
1230-0-0 including the per
centage charges for establish-
-ment and tools and plant
for Extending the existing
Mulagapaka Calingulah "re-
-ceived from the Exve Engr
Vizagapatam Division
2 The necessity for the
work is explained in the
report accompanying the
estimate
3. The cost of the work
is to be borne by the Anaka-
-palli Proprietor who has
expressed his willingness to
pay the amount. I request
that sanction of Government
may be obtained under para
79 Chapter IX Volume I of
the P.W. Code to the work being
carried out by this Department
4

The

4. The work will not be commenced until the Proprietor has paid the estimated amount into the Treasury.

5. Prior to the work being put in hand the ruling contained in para 82 III Chapter IX Volume I into receive attention.

I have the honor to be,

Sir,

Your Most obedt St

H Worrgan
28
4
Byrn Engineer mch 18 Civil

---

a
a
w
te
Re £.15
fo
te
Y

FROM W. Donithorne Esq
Executive
THE SUPERINTENDING ENGINEER
Trichinopoly FIRST CIRCLE.

C. W. CURREY

TO,
THE CHIEF ENGINEER
FOR IRRIGATION
MADRAS.

DATED 28 9
DESPATCHED 1/6 } April 1896
RECEIVED

No. 75 W2

ENCLOSURES. 3.

SUBJECT.

Melagiri Cauvery Channel — Submits
Plan and Estimate amounting to Rs 1239
for extending the — for favour of
Sanction the Sanction of Government
to the work being carried out by