Public Works (1896) Department.

G.O., No. 5519/552

Dated 2/7/96.

[Despatch Abstract.]

Pelandorai Anicut — The revised estmak for lowering the — & fitting it with 6 feet girder shutters Counterweighted and with suitable gearing, Sanctioned and a copy of these Pros forwarded to the Govt of India

[P.W. 25. 1,000—23-10-95.]

BACK PAPERS.

G.O.	No.	Department.	Date.	G.O.	No.	Department.	Date.

FURTHER PAPERS.

G.O.	No.	Department.	Date.	G.O.	No.	Department.	Date.

IRRIGATION.
ACCOUNT.

Govt. of {1896} Madras.

PUBLIC WORKS.

Dated July, 2nd.

Read. *Encl.*

G.O. Nos. 551, 552 I., 2nd July 1896.

JULY.

Pelandorai Anicut

Forwarding for information a copy of the Proceedings of this Government sanctioning a revised estimate of Rs. 74,800 for lowering the —, and fitting it with six feet girder shutters counterweighted and with suitable gearing.

GOVERNMENT OF MADRAS.

PUBLIC WORKS DEPARTMENT.

Irrigation.
Account.

READ—the following paper:—

From Lieutenant-Colonel C. C. RAWSON, R.E., Superintending Engineer, V Circle, to the Chief Engineer for Irrigation, dated Chepâk, 1st June 1896, No. 116 E.I.

I have the honour to point out what is apparently an error in the estimate for lowering the Pelandorai anicut and fitting it with 6 feet girder shutters sanctioned in G.O. No. 301 I., dated 31st March 1896.

2. In the details of brick-work the quantity deducted is the section of brick-work in the anicut by the whole length, instead of only by the thickness of the piers, multiplied by the number of piers.

3. The total amount of brick-work will therefore be 34,436 cubic feet against 13,135 as given in the estimate and the difference in cost Rs. 3,120.

4. The sanctioned plan and estimate are enclosed for information.

No. 129 I.

Submitted to Government. The error pointed out by the Superintending Engineer, V Circle, in the original estimate has been rectified. The estimate, as revised in this office, amounts to Rs. 60,800 and is recommended for sanction.

(Signed) R. R. E. DRAKE-BROCKMAN, Col., R.E.,
23rd June 1896. Chief Engineer for Irrigation.

ORDER—No. 551 I., dated 2nd July 1896.

The following revised estimate is sanctioned in supersession of the estimate of Rs. 71,100 sanctioned in G.O. No. 301 I., dated 31st March 1896:—

Irrigation.
43. Minor Works and Navigation.
Minor Works for which Capital and Revenue Accounts are kept.
Pelandorai Anicut System.
Open Capital Account.
1. Head Works.
3. Works.

Lowering the Pelandorai anicut and fitting it with six feet girder shutters, counterweighted and with suitable gearing —

	RS.
I. Works	60,800
II. Establishment	13,984
III. Tools and plant	16
Total ...	74,800

2. This sanction is registered as No. 78 I. of 1896-97, and will expire on 31st March 1898.

3. Ordered that a copy of these Proceedings be forwarded to the Government of India for information.

[Here enter No. 552 I., dated 2nd July 1896.]

(True Extract.)

(Signed) R. R. E. DRAKE-BROCKMAN, Colonel, R.E.,
Secretary to Govt., P.W.D.,
Irrigation Branch.

To the Chief Engineer for Irrigation.
" Superintending Engineer, V Circle, with four enclosures.
" " " on Special duty, Cauvery Completion Estimates.
" Examiner, Public Works Accounts.

ENDORSEMENT—No. 552 I., dated 2nd July 1896.

Forwarded.

(By order.)

Colonel, R.E.,
Secretary to Govt., P.W.D.,
Irrigation Branch.

Exd. Shaik Karim.
Spare Copies

No. 551 I., dy 2nd July 1896.

PUBLIC WORKS DEPARTMENT,
IRRIGATION BRANCH.

PROCEEDINGS OF THE MADRAS GOVERNMENT.

UNDER date the

READ the following

From Supg Engr, V Circle, No. 1162 I., dy 1st June 1896.
2012 I dy 23 Dec 96
Submitted to Govt. The errors pointed out by the Supg Engr, V Circle, in the original estimate has been rectified. The estimate as revised in this office amounts to Rs 60,800 & is recommended for sanction & order thereon

The following revised estimate is sanctioned in sup

session of the estimate of Rs 71,100 sanctioned in G.O. No 301. I, d/ 31st March 196:—

Irrigation.

43. Minor Works Maint. Minor works for which Capital & Rev. Accts are kept.

Irlandoram Anicut system.

Open Capital Account
1. Head Works.
3. Works.

Lowering the Irlandoram anicut & fitting it with 6 feet girder shutters, counter-weighted & with suitable gearing :—

I. Works . . .	60,800	
II. Establishment.	13,984	
III. Tools & Plant.	16	
Total	74,800	

This sanction is registered as No 781 of 1896-97

& will expire on 31st March 198. 3 Years

3. Ordered that a copy of these Proc. be forwarded to the Govt of India for information.

Endorsement — No 5529, dy 2nd July 1896.

Forwarded.

22/6/96

Recd 29/6/96

TELEGRAPH 13 JUL 96

To
The Chief Engr for I.
Supdg Engr V. with 4 enclos
Dr. & special Duty, Canvey Completion Estn.
Ex. Div 2.

Lcu 18/6

P. W. CURRENT No. 5902

Revised Estimate for lowering Pelandorai Anicut & fitting it with 6 feet girder shutters. Encls 5 (plans) Recd: 1.7.96

G.O. 3019 d/31.3.96

Issue Rheadk 25/6

E. I. Form No. 1—500—14-5-95

No. 1166 I

SUPERINTENDING ENGINEER'S OFFICE,
V CIRCLE, MADRAS,
Chepák, 1st June 1896.
Despd 3/6/96.

From Lieut.-Colonel C. C. Rawson R. E.

SUPERINTENDING ENGINEER, V CIRCLE,

To THE Chief Engineer for Irrigation

SIR,

I have the honour to point out what is apparently an error in the Estimate for lowering the Pelandorai anicut and fitting it with 6 feet girder shutters sanctioned in G.O. No: 301 I dy 31st March 1896.

2. In the details of brick work the quantity deducted is the section of brick work in the anicut by the whole length, instead of only by the thickness of the piers, multiplied by the number of piers.

3. The total amount of brick work will therefore be 34,436 cft: against 13,135 as given in

Enclosures. 3.
1 Tracing plan.
1 Detail Estimate.
1 abstract Estimate.
3

500—25-2-96.

P. W. CURRENT No. 5902

in the Estimate and the difference in cost Rs. 3,120.

The Sanctioned plan and Estimate are enclosed for information.

I have the honour to be
Sir
Your most obedt. Servt.

C. E. Lamme
1/6/96 Colonel R. E.
Supdg Engineer V Circle

1-6-96

From

THE SUPERINTENDING ENGINEER,
V CIRCLE,

CHIEF ENGINEER
FOR IRRIGATION.
4 JUN. 96
No. 110 L.A.

To

THE Chief Engineer
For Irrigation

Dated 1st
Rec'd. 3rd } June 1896.

ENCLOSURES. 3

OWC I
550/98

No. 1162.

Pelandorai Anicut

Points out what is apparently an error in the Estimate for lowering the