Public Works (1896) Department.

G.O., No. 5789

Dated 7/7/96

[Despatch Abstract.]

Ettalakodu drain Buck Canal
Godavri Eastern Delta — Estimate
for excavating — sanctioned

[P.W. 26
1,000—23-10-96.]

BACK PAPERS.

G.O.	No.	Department.	Date.	G.O.	No.	Department.	Date.

FURTHER PAPERS.

G.O.	No.	Department.	Date.	G.O.	No.	Department.	Date.

IRRIGATION.
ACCOUNT.

Govt. of {1896} Madras.

PUBLIC WORKS.

Dated July, 7th.

Recd. *Encl.*

G.O. No. 578 I., 7th July 1896.

JULY.

Drain

Estimate of Rs. 550 for excavating Ethalakodu drain, Bank canal, Gódávari Eastern delta, sanctioned.

GOVERNMENT OF MADRAS.

PUBLIC WORKS DEPARTMENT.

Irrigation.
Account.

READ—the following paper :—

From W. C. DEMORGAN, Esq., Executive Engineer in charge, I Circle, to the Chief Engineer for Irrigation, dated Waltair, 18th June 1896, No. 536 G.D.

I have the honour to submit the accompanying estimate of Rs. 545 * for excavating Ethalakodu drain in the Gódávari Eastern division and to request that sanction of Government may be obtained thereto.

* Increased to Rs. 550 in the office of the Chief Engineer for Irrigation.

2. The necessity for the work is explained in the report attached to the estimate.

3. A survey sheet and section accompany the estimate.

ENCLOSURE.

REPORT to accompany estimate for excavating Ethalakodu drain (between Kotipalli road and Sarlapudi drain).

1. Amount of estimate, Rs. 545.†

† Increased to Rs. 550 in the office of the Chief Engineer for Irrigation.

2. The proposed drain is to drain the low lands of three villages (about one square mile) east of Kotipalli-Ramachandrapúr road and between Gangaveram and Sundarapalli channels. It carries off the drainage into Gangaveram drain which is really the continuation of the Sarlapudi drain, and passes under the Kotipalli road through a Local Fund culvert.

3. The excavation of this drain is absolutely necessary, as at present the lands have no means of relief during the rainy season, and are usually flooded.

4. No extra earthwork for banking will be carried out up to cross section No. 8, as the spoil only will be used for banks.

5. There is no necessity to occupy or take up any ryot's land as the width of punta through which the proposed drain passes is ample.

(Signed) A. G. ROMILLY,
Asst. Engr., Gódávari Eastern Divn.

No. 578 I., 7TH JULY 1896.

ORDER—No. 578 I., dated 7th July 1896.

The following estimate is sanctioned :—

Irrigation.
42. Major Works (Working Expenses).
Gódávari Delta System.
Eastern Section.
1. Extensions and Improvements.
Bank Canal.
4. Drainage and Protective Works.
3. Earthwork.
Excavating Ethalakodu drain.

	RS.
Estimate	550

2. This sanction is registered as No. 82 I. of 1896–97.

(True Extract.)

Under Secy. to Govt., P.W.D.,
Irrigation Branch.

To the Chief Engineer for Irrigation.
" Superintending Engineer, I Circle,
" Examiner, Public Works Accounts.
with four enclosures.

Exd. T. K. Narayana Aiyangar,
Spare Copies

X

No. 578 I. dt 7-July 1896.

PUBLIC WORKS DEPARTMENT,
IRRIGATION BRANCH.

PROCEEDINGS OF THE MADRAS GOVERNMENT.

UNDER date the 30th April

READ the following

From Supdg Engr, 1st Circle No. 5366 D. dt 18 June/96

The following
estimate is sanctioned:—
Irrigation.
42 Major Works (Working
Expenses)
Godavari Delta System
Eastern Section.
1 Extensions & Improvements
Bank Canal
4. Drainage & Protective
Works.
3. Earthwork
Excavating Ethalakodu
drain. Estimate Rs 550
2. This sanction
is registered as No.
82 I of 1896-97.

DESPATCHED
22 JUL. 96

To the Chief Engr for I
Supdg Engr 1st Circle with 4 enclos
Ex Engr.

Rnedk 27/6/96.

~~152~~ 5

Estimate for excavating Khalakoda drain in the Godavari Eastern Dn

—

Issue

Recd 4/7

A. 4/7

4/7/26

F.C.9.

Recd

E. I. Form No 1—1,000—27-11-25.

Report to accompany Estimate for excavating Eathalakoda Drain (between Kotipalli road and Karlapudi Drain.

1 Amount of Estimate Rupees ~~550~~ 545 ~~-~~ 500-0-0.

2 The proposed drain is to drain the low lands of 3 villages (about 1 sq. mile) east of Kotipalli - Ramachendrapuram road and between Gangaraam and Sundarapalli channels. It carries off the drainage into Gangaraam Drain which is really the continuation of the Karlapudi drain, and passes under the Kotipalli road through a Local Fund Culvert.

3 The excavation of this drain is absolutely necessary, as at present the lands have no means of relief during the rainy season, and are usually flooded.

4 No extra Earthwork for banking will be carried out up to cross section No 8, as the spoil only will be used for banks.

5 There is no necessity to occupy or take up any ryots' land as the width of Puntas through which the proposed drain passes is ample.

A. Bonnikka

Asst. Engr. E. Dn. G.

A. A.

Jr.

CHIEF ENGINEER
FOR IRRIGATION.
22 JUN. 96
No.

SUPERINTENDING ENGINEER.
2201
16 MAY. 96
FIRST CIRCLE.

No. 536 Gd

1 Pur.

FROM

W. L. D'E Morgan Esqr.
Executive
~~SUPERINTENDING~~ ENGINEER, in charge
FIRST CIRCLE.

Enclosures. four-TO

THE CHIEF ENGINEER
FOR IRRIGATION. Madras

WALTAIR, 18th June 1896.

Dpo. 19.6.96

one Report
one Estimate
one Survey Sheet
one Section.

SIR,

I have the honor to submit the accompanying Estimate of Rs 550 (~~545~~) for Excavating Ehalakodu drain in the Godavari Eastern Division and to request that sanction of Government may be obtained thereto.

2. The necessity for the work is Explained in the report attached to the Estimate.

3. A Survey Sheet and Section accompany the Estimate.

I have the honor to be
Sir,
Your most obedient Servant
p Dellorgan
19/6
Executive Engineer
in Charge I Circle.

× attended in the office of the Chief Engr for disposal.

CH 18-6-96.

Gl 83
6085/96

CHIEF ENGINEER
FOR IRRIGATION.
22 JUN. 96
No. 1082

S. E. 1.
1 500—29-2-96.

P. W. CURRENT No. 6085

FROM

SUPERINTENDING ENGINEER,

FIRST CIRCLE.

Rec'd 5 (2 Plans)
Ans: 7.7.96

TO

THE CHIEF ENGINEER

FOR IRRIGATION.

DATED 18..
DESPATCHED 19 } June 1896.
RECEIVED

No. 5360 G0

ENCLOSURES. From—

SUBJECT.

Submits an estimate for
Rs. 545 viz: Running Shuk Section
& requests
to obtain the sanction of Govt.