Public Works (1898) Department.

G.O., No. 1284 W

DATED 19 May 98

Communicated 23/5/98

29/5/98

[Despatch Abstract.]

Reformatory School at Chingleput: Estimates aggregating Rs. 5,210 for works connected with the — sanctioned and the amount appropriated from the Provincial reserve.

110/6

[P. W. M. 1,000—12-2-95.]

Indexed 20/5

19-5-98

BACK PAPERS

G.O.	No.	Department.	Date.	G.O.	No.	Department.	Date.
1358 22.4.98							

FURTHER PAPERS.

G.O.	No.	Department.	Date.	G.O.	No.	Department.	Date.

BUILDINGS AND ROADS.
CIVIL WORKS.

Government {1898} of Madras.

PUBLIC WORKS.

Recd. } 1898. Enclosures
Regd. } Spare copies

G.O., No. 1284 W., 19th May 1898.

MAY.

Reformatory School at Chingleput

Estimates, aggregating Rs. 5,210, for works connected with the —, sanctioned and the amount appropriated from the Provincial reserve.

GOVERNMENT OF MADRAS.

PUBLIC WORKS DEPARTMENT.

Buildings and Roads.
Civil Works.

Read—the following papers :—

G.O., No. 727, Educational, dated 20th November 1896.

From the Director of Public Instruction, Madras, No. 5447, dated 16th May 1896.

From the Public Works Department, No. 3534 C., dated 7th October 1896.

From the Director of Public Instruction, Madras, No. 11032, dated 10th October 1896.

Order—No. 727, Educational, dated 20th November 1896.

The plans and estimates received with the Director of Public Instruction's letter No. 11032, dated 10th October 1896, are approved and will be transferred to the Public Works Department.

(True Extract.)

(Signed) W. FRANCIS,
for Cnief Secretary.

From the Superintending Engineer, V Circle, dated 11th March 1897, No. 89 W.
Endorsement from the Educational Department, No. 1610, dated 30th July 1897.
Memorandum from the Chief Engineer, P. W. Dept., No. 4202 C., dated 16th October 1897.

From Colonel C. C. RAWSON, R.E., Superintending Engineer, V Circle, to the Chief Engineer, Public Works Department, dated Chepâk, 17th March 1898, No. 187 W.

With reference to paragraph 11 of your memorandum No. 4202 C., dated 19th October 1897, I have the honour to re-submit for sanction the enclosed revised plan and estimate amounting to Rs. 5,280, for constructing kitchens and godown to the Reformatory at Chingleput [marked (*f*) and (*m*) in the memorandum under reply].

2. The other plans and estimates are under revision in my office and will be submitted shortly.

From the Superintending Engineer, V Circle, dated 29th March 1898, No. 217 W.

Letter from the Inspector-General of Prisons, dated 6th May 1898, No. 2090.

Note by the Chief Engineer, Public Works Department.

With his letter No. 187 W., dated 17th March 1898, the Superintending Engineer, V Circle, submits, for sanction, the following estimates in connection with the Reformatory School at Chingleput :—

	RS.
(*a*) Constructing a circular kitchen	3,640
(*b*) Constructing a kitchen and godown with covered way for the Deputy Superintendent's quarters	1,640

These estimates which have been reduced to Rs. 3,620 and Rs. 1,590, respectively, by the correction of certain errors in calculation, are recommended for sanction.

(Signed) W. B. DEWINTON,
Chief Engineer.

17th May 1898.

Order—No. 1284 W., dated 19th May 1898.

The undermentioned estimates, aggregating Rs. 5,210, as altered by the Chief Engineer, Public Works Department, for works connected with the Reformatory School at Chingleput, are sanctioned, and the amount is appropriated from the Provincial reserve :—

	RS.
(*a*) Constructing a circular kitchen	3,620
(*b*) Do. a kitchen and godown	1,590

2. This sanction has been registered as Provincial No. 13 W. of 1898–99 and classified as Civil Buildings—Original Works.

(True Extract.)

Under Secretary to Government.

To the Superintending Engineer, V Circle, with plans and estimates.
„ Examiner, Public Works Accounts.
„ Educational Department.

Exd. C. M. Thumbusawmy.

[40/500]

Public Works DEPARTMENT.

Proof

Papers to be read in proceedings :—

Again G.O., dated 189 , No.

Again G.O., dated 189 , No.

Quote Current No. 2653, of 1897, dated 13th March , from S.E.V Circle.
Quote ,, 7628 of 1897 ,, 2nd August ,, Educational Dept.
Print ,, 10720 ,, 1897 ,, 25th November, ,, -Do-
~~Print~~ ,, Chief Engineer's Memo No. 4202 C, dated 19th October 1897.
5- Quote Current No. 2951 ,, 1898, ,, 31st March ,, S.E.V Circle.
Print ,, 2547 ,, 1898 18th March ,, -Do-
Quote Letter from the I.G. of Prisons, No. 2090, dated 6th May 1898. 12 quot.
Print Note by the Chief Engineer, P.W.D., dated 17th May 1898.

ORDER.

N-1284 W 19.5.98

The undermentioned estimates aggregating Rs.5,210, as altered by the Chief Engineer, P.W. Department, for works connected with the Reformatory School at Chingleput are sanctioned, and the amount is appropriated from the Provincial reserve.

(a) Constructing a circular kitchen Rs. 3,620.

(b) Constructing a kitchen and godown. Rs. 1,590.

2. This sanction has been registered as Provincial No. 13 W of 1898-99, and classified as Civil Buildings, Original Works.

B & C Works

KUP

ASK
16.5.98.

I/B

17.5.98

P. T. O.

The Suptg. Engineer V Circle, with plans and estimates.

,, Examiner, P.W. Accounts.

,, Educational Department.

P 11.6.98

Public Works DEPARTMENT.

~~O. No.~~ Letter from the I. G. of Prisons
No: 2090 d/6-5-98.

SUBJECT.

Constructing kitchens and godowns to the Reformatory School at Chingleput.

HIS EXCELLENCY THE GOVERNOR.
~~THE HON'BLE SIR HENRY BLISS, K.C.I.E.~~
~~THE HON'BLE MR. GROSE, C.I.E.~~

FOR ORDERS.

Fifteen estimates aggregating Rs 64,929 for alterations and additions to the Reformatory at Chingleput were approved in the Educational Department and transferred to this Department for disposal. These estimates were reviewed in the technical note d/ 15th September 1897 + and returned for revision with the + Chief Engineer's Memo: No: 4202 C d/ 19th October 1897. Two of the more urgent of these estimates shown in the margin × came back revised with reference to paras 1 & 5 of the above memorandum and were recommended for sanction in the × Note for Orders d/ 4th April 1898, on which His Excellency remarked as follows:—

"I am

+ Flagged I

+ Flagged H

×
(1) Constructing a circular kitchen Rs 3,620
(2) Constructing a kitchen with godown .. 1,590
Total Rs. 5,210

× Flagged G

H.E. 11.5 [P. W. 45. / 900—27-1-98.] 14/5/98

"I saw one of these circular kitchens at the Lunatic Asylum at Vizagapatam. I was told it consumed a great deal of fuel. Has this type of kitchens been tried elsewhere? If so, has the trial resulted in practical success?"

In Memo: No: 139† D/29 April 1898, the Inspector General of Prisons was accordingly requested to report whether the circular kitchens constructed in the Vellore and Rajahmundry Jails have proved satisfactory in every respect. That officer now reports vide his letter No: 2090× d/6 May 1898, that the central kitchens built at the Vellore and Rajahmundry Central Jails are generally satisfactory, and that they do not consume a great quantity of fuel, the allowance per head per diem being only 13 oz and 12 oz respectively for cooking three hot meals, which is below the limit prescribed in the Jail Code.

† Flagged K

× Flagged M

In the above circumstances, orders are requested as to whether the two estimates for the kitchens in the Reformatory at Chingleput may be sanctioned.

These two Estimates are sanctioned.

ASH
13.5.98

ASR
11.5.98.

11.5.

May

P.W. DEPARTMENT.

His Excellency the Governor.

READ the following :—

FOR ORDERS.

Fifteen estimates, aggregating Rs 64,929, for alterations and additions to the Reformatory at Chingleput were dealt with in technical note dated 15th September 1897 and returned for revision with Chief Engineer's memorandum No 4202 dated 19th October 1897

Flag L.

Flag H.

Two of the more urgent of these estimates have now come back revised with reference to paras 1 and 5 of the above memorandum, and are as follow:—

(1)	Constructing a circular kitchen	Rs 3620.
(2)	Constructing a kitchen with go-down - - - - - - - -	1590.
		Rs 5210

They are dealt with in the accompanying technical note and may be sanctioned.

CHWS
4/4/98.

I saw one of these circular ~~hot~~ kitchens at the Lunatic Asylum at Vizagapatam. I was told it consumed a great deal of fuel. Has this type of kitchen been tried elsewhere? If so has the trial resulted in practical success?

A.S.H
5.4.98

SAW
5/4/98

43—500—22-4-97.

FOR ORDERS.

Public Works Department.

Note by the Chief Engineer.

With his letter No. 187 W dated 17th March 1898, the Superintending Engineer V Circle submits for sanction the following estimates in connection with the Reformatory School at Chingleput.

(a) Constructing a circular kitchen Rs. 3, 640.

(b) Constructing a kitchen and godown with covered way for the Deputy Superintendent's quarters Rs. 1, 640.

These estimates, which have been reduced to Rs. 3, 620 and Rs. 1, 590 respectively by the correction of certain errors in calculation, are recommended for sanction.

ASR
16.5.98.

E.W. 17.5.98

Maj

The following estimates in connection with work of the Reformatory School at Chingleput are sanctioned:-

(1) Constructing a circular kitchen - Rs 3640 reduced in this office to Rs 3620 owing to errors in calculation.

(2) Constructing a kitchen and go-down, with covered way, for the Deputy Superintendent's Quarters - Rs 1640 reduced to Rs 1590 for reasons similar to the above.

C.H.S.

4/4/98.

[P. W. 60 / 250—30-9-97.]

Public Works Department.

Current No. 2547
Letter No. 187 W
Dated 17th March 1898
From the Superintending Engineer 5th Cir

NOTE BY TECHNICAL SECTION.

Name of work Constructing a circular Kitchen to the Reformatory at Chinglep

Amount of Estimate as received Rs 364
" as altered Rs. 36

In G.O. No 1004 W dated the 20th March 18 the preparation of designs and estimates for alterations and additions to the Reform at Chingleput was ordered.- According designs and estimates prepared by the Consulting Architect to Govt were rece with the approval of the Director of Public Instruction, dealt with in this cen note dated 15-9-97 by Technical Sect and returned to S.E. V with Memoran No 4202 C of 19th October 1897 for a revision and resubmission.-

This estimate for kitchen with Cir Cooking range referred to in para of the Memorandum is based on th type design circulated with G.O. of 15th June 1893 with a slight mod tion since ordered.

e deviations from the printed Schedule which
lls for remark are as below.-

	Quantity as per Schedule cft	Qty of estimate now ref. cft	
xcavation for foundatn	2244	4812	Excess is due to greater breadth & depth with ref to nature of soil.
ncrete with broken ricks in Chunam	1002	1778	The excess is due to deviation with ref to nature of soil which is said to be Ordinary earth 6.-
rick in Chunam for undations	767	1752	
Fire brick in fire clay	111	86	Decrease is due to a slight deviation in thickness.-
eakwood wrot & put up	114	105	Decrease is due to Substitution of iron tie rods 1¼" diamr. for the beams.
rot Ironwork	117	315	Increase is due to substition of tie rods for tie beams.
oors and Windows	70	83	Outside measurements are now taken.
e. Damp proof Course.	Asphalte ½" is an extra item.		

Particulars of Construction

foundation will be laid with Concrete de & 2' deep and brick in Chunam for pth of 4 feet as shewn on the tracing.- ls will be built as per dimensions on the design with stock bricks in except at the fire place where f fire bricks in fire clay.-

The inner faces of walls will be plastered with 2 Coats of Chunam and the outer pointed bla with tar and Sand.

The floor will be of stone slabs set in Concre and pointed with cement and the roof laid with Mangalore tiles over teak reepers and diagonal Couples.-

The Scantlings of roof timbers are correct as per printed Schedule & the timbers painted with 3 Coats of Oak Color.-

The Plinth area is 734 Sft. and the cost per Sq foot = Rs 4-

Estimate for Kitchen and godown with Covered way for Dy Superintendent's qrs.

Rs 16240 reduced to Rs 159

This estimate is ~~also~~ referred to in para 11 of Memorandum No. 4202C / 19-10-97.

Particulars of Construction

Surface Soil .. 6½' made earth with stones
Sub soil ..... Hard Moramboo.

Foundations will be laid with concrete (bro bricks in Chunam) 5' x 2' below brick in chunam as shewn in Section.-

Walls will be as per dimensions shewn the tracing and built of stock bricks chunam, the inner faces of the struc plastered with 2 Coats of Chunam an outer pointed with tar and Sand.-

The floor will be of Cuddapah laid on a bed of 4" of Concrete an pointed with asphalte and the roo with pan tiles over teak reepers.

The Scantlings of roof timbers are as standard Specification & the timbe

True

ainted with Oak Color 3 Coats.

he plinth Area of this Kitchen and godowns
s 469 Sft. and the cost per Sq foot = Rs 3-6-3

n Current No. 7628 the Educational
Department urges the early Construction
f the Kitchens for the Reformatory school
nd for the H/ Supdts qrs.

he two estimates (amounting to Rs 3620 + 1590)
ave been checked and Submitted for Sanction
e rates being as given in the schedule.

W. ho.
S. D
30-3-98

The plans & estimates are in order.

30/3/98.

The two estimates may be
Sanctioned

CWS
4/4/98.

Office of the Director of
Public Instruction.

No. 4732.

Madras, 3rd May 1897.

CONSULTING ARCHITECT TO THE GOVERNMENT OF MADRAS
R. No. ....
15 JUN. 97

From

The Honourable Mr. D. Duncan, M.A., D.Sc.,
LL.D.

Director of Public Instruction,
Madras.

To

The Executive Engineer,
Chingleput Division.

Sir,

I have the honour to request that the erection of a wall to separate the play-grounds of the junior and senior divisions of the Reformatory School, Chingleput as per enclosed plan and estimate countersigned, may be undertaken by the Public Works Department and its cost included in the estimate for additions to the buildings recently sanctioned.

I have &c
(Sd) D. Duncan
Director of Public Instructio

No. 482 14-5-97

Copy forwarded to the Superintending Engineer, V Circle, with a request that the cost of the wall referred to by the Director of Public Instruction may be included in the Estimate for the Reformatory School under preparation by the Consulting Architect to Government. Vide para 2, of your letter No. 77 C. R of 4-3-96.

(Sd) J. P. Davidson,
Executive Engineer
Chingleput Divis

True

(True Copy)

"By Order"

O. Keeley

~~Lt. Colonel~~ Major R.E.

Office of the Superintending Engineer,

V Circle.

11.6.97

P.W. E.5 / 5893/97

H. O. Form No. (1)—2,000—October 1897.

OFFICE OF THE INSPECTOR-GENERAL OF PRISONS, MADRAS,

No. 2090.

dated Ootacamund, the 6th May 1898.

It is requested that any reply to this letter may be addressed to Ootacamund.

From

A. G. CARDEW, Esq., M.A.,

INSPECTOR-GENERAL OF PRISONS, MADRAS,

To

THE Under Secretary to Government,

Public Works Department, ~~Madras~~ Ootacamund

SIR,

Enclosures.

In reply to Public Works Memorandum No. 139/D, dated 29th April 1898, I have the honour to state that the central Kitchens built at the Vellore and Rajahmundry Central Jails are generally satisfactory. It is not the case that they consume a great quantity of fuel, the allowance per head per diem being reported to be only 13 ozs and 12 ozs respectively for cooking three hot meals. This amount is below that prescribed in Rule 445 of the Jail Code and is, in fact, extremely low.

I have the honour to be,

Sir,

Your most obedient servant,

A G Cardew.

Insptr: Genl of Prisons.

JAIL (1898) DEPARTMENT.

P.W.D. Ch. 433
&
Rd 7.5.98
Regr: 15-5-98

From

THE INSPECTOR-GENERAL OF PRISONS,
Madras,

To

THE Under Secretary to Govt:
P.W.D. Madras.

Dated 6th
Despatched } May 1898.
Received

No. 2090.

ENCLOSURES.

Subject.

States that the Central Kitchen built at the Vellore & Rajahmundry C.J. are generally satisfactory.

Public Works (1898) Department.

CURRENT No. 2547

Order

From The Supg Engineer
5th Circle.

No. 187 W.

Dated 17th March 1898.

Received 18.3.98

Enclosures 7 (3 plans)

Spare copies

SUBJECT.

Reformatory at Chingleput

Resubmitting for sanction the revised plan & Estimate of Rs 5280 for constructing kitchens & Godown to the —

For very early scrutiny

Comms
22/3/98.

AL. 4.4.98
R. 5.4.98

BACK PAPERS.

No.	Date.
4202C	19-10-97
3419C	24-9-96
3306C	11-9-96
1004W	20-3-96
3534C	7-10-96

FURTHER PAP

No.	Da

No. 187 W. 11P

SUPERINTENDING ENGINEER'S OFFICE,
V CIRCLE, MADRAS,
Chepâk, 17th March 1898

From Colonel C.C. Rawson R.E.
SUPERINTENDING ENGINEER,
V CIRCLE,

To
THE Chief Engineer
P.W. Department.

SIR,

With reference to para 11 of your memorandum No. 4202 C. dated 19th October 1897, I have the honour to resubmit for sanction the enclosed revised plan and estimate amounting to Rs 5,280/. for constructing kitchens and godown to the Reformatory at Chingleput (marked F and M in the memo under reply).

Enclosures. 7
1 Site plan
2 Plans
1 Report
2 detailed estimates
1 General abstract estimate

2 The other plans and estimates are under revision in my office and will be submitted shortly.

I have the honour to be,
Sir,
Your most obedt. Servant

C.C. Rawson
17.3.98
Colonel R.E.
Supg. Engineer 5th Circle

500—31-3-97.

15.3.98

Public Works (1898) Department.

CURRENT No. 2951

Order

From The Supg Engineer
5th Circle

No. 217 W.

Dated 29th March 1898.
Received 31. 3. 98
Enclosures
Spare copies

+ Sent H.R. on 4.4.98

SUBJECT.

Reformatory School at Chingleput.

Informing that the soil at site where the Kitchen & Godowns of the — are to be built is of a very variable nature.

Await return of the estimate from + H.R.

Cwd 5/4/98

Dpr

Rev C. No. 2547 — just returned from H.R. 5/4/98

2547/98

BACK PAPERS.

No.	Date.

FURTHER PAPERS.

No.	Date.

No. 217 W.

SUPERINTENDING ENGINEER'S OFFICE,
V CIRCLE, MADRAS,
Chepâk, 29th March 1898.

From
Colonel C. C. Rawson R.E.
SUPERINTENDING ENGINEER,
V CIRCLE,

10 grade

9 grade

To
THE Chief Engineer,
P. W. Department.

SIR,

× CWO 2547
sent to SAW by J.
on 30/3

Enclosures

In continuation of this office No. 187 W., 17th Instant, I have the honour to inform you that as the soil at the site where the Kitchen and godown of the Reformatory School at Chingleput are to be built is of a very variable nature, full depth of foundation has been allowed, but that when work is being executed the foundation may be reduced if the made-earth in places is found to be of less depth than that shown.

I have the honour to be
Sir,
Your most obedt. Servant

29.3.98 Colonel
Supg Engineer 5 Circ

200—12 1.98.

No. 4202 C

Government of Madras.

PUBLIC WORKS DEPARTMENT.

1' Reminder issued 3-2-98
2. Do. 5-3-98

Memorandum.

Dated, 19th October 1897.

Further papers
cd 25-10-97

The undersigned has the honour to return the marginally noted estimates, aggregating to Rs. 64,929, for alterations and additions to the Reformatory at Chingleput with reference to the following observations:-

(a)	Providing windows to Sub-Jail to convert it into a hospital.	Rs. 680.
(b)	Erecting a workshop and Dormitory over rampart.	17,735.
(c)	Erecting a weaving shed.	6,880.
(d)	Converting Police guard in Sub-Jail into a tailors' shed.	535.
(e)	Constructing a School house	8,129.
× (f)	- do - kitchen with range.	3,272.
(g)	- do - Compound wall and roadway.	7,034.
(h)	Erecting 107 new cubicles.	9,463.
(i)	Constructing a latrine for 20 seats.	852.
(j)	- do - latrine for 16 seats.	728.
(k)	Constructing quarantine shed.	3,032.
(l)	Latrine for Deputy Superintendent.	387.
× (m)	Kitchen and godown for - do -	1,150.
(n)	Stables and coach house - do -	915.
(o)	Constructing Blacksmiths shop.	4,137.
	Total estimate	64,929.

1. The depths, as well as the nature, of surface-soil and sub-soil should be entered on the plans where omitted.

2. Estimate (b). Provision should be made for wall-plates under the joists in the lower floor.

3. Estimate (c). Eight wooden trusses each of 24 feet span are provided, but, apparently because it would be difficult to obtain tie-beams of sufficient length, it is proposed to scarf two lengths of timber in the middle where there is no support. It is considered preferable to provide, instead,

iron

27/10/97

88

iron trusses with screw tie rods thus:-



The same remark applied to estimate (b) where the span is 22' 10".

4. Estimate (e). The steps seem unnecessarily long. 30' should be ample.

5. Estimate (f). The type design is considered faulty as regards the thickness of the circular dwarf wall at flue where it is only 9" thick, viz, 4½" firebrick in clay and 4½" brick in chunam. The latter thickness should be increased to 9" making the total 13½". This alteration will necessitate either a reduction from 15" to 10½" in the tread of the steps round the centre wall or the shifting of the steps 4½" towards the outer wall of the work: the latter alternative is considered the preferable of the two.

6. Estimate (g). No longitudinal or cross sections of the proposed road have been received. They are wanted to check the 105825 cubic feet of earthwork estimate, or fuller explanations should be given as to why this road should cost so much. Data for the high rate of Rs. 10 should also be given.

7. Estimate (h). This estimate which amounts to Rs. 9,643 cannot be sanctioned without a plan, and no plan has been received. Moreover experience of Chingleput Reformatory cubicles has shown wire netting to be objectionable, as the holes drilled to receive the netting harbour bugs. The proposals should be reconsidered and fully detailed when resubmitting.

8. Estimates (i) and (j). For the sake of privacy it would be well to provide a longitudinal partition between the seats.

9. Estimate (n). Ridge ventilators should be provided for stables.

10. Estimate (o).

91

10. __Estimate (o)__. It is doubtful whether wooden purlins will prove satisfactory for a Blacksmith's shop. Angle-iron purlins ~~which~~ 3"×3"×½" would, it is considered, be preferable.

11. Since the Superintendent requests that, in the event of funds not being avaialble for all the improvements contemplated, the kitchens - estimates (f) and (m) - at least may be constructed at once, ~~it~~ it is desired that the estimates for these works may be resubmitted, revised as necessary, as soon as possible with a view to funds being allatted for their immediate execution. The other estimates may follow in due course.

(By Order)

(~~7 by~~ initials)

Deputy Chief Engineer.

16.10.97.

T Xha.
/B 7/ks

16.10.97

To

The Suptg. Engineer, V Circle.

ult 50 ontos

21/10/97

C24.7.97

Public Works (1896) Department

CURRENT No. 10720

Order

From
The Educational Dept

No. 727

Dated 20 November 1896.
Received 25.11.96
Enclosures 46 (14 plans)
Spare copies

SUBJECT.

Approving the plans & Estimat
for the adoption of the
existing buildings in
Chingleput to the purpose
of the Reformatory Schoo

J / For scrutiny in DW
15/1

o L S 477
R 18/10

BACK PAPERS.

G.O.	No.	Department.	Date.
	3534C	PW	7-10-96
	3419C	"	24-9-96
	3306C	"	11-9-96

FURTHER PAPERS.

G.O.	No.	Department.	Date.

Educational Department.

PROCEEDINGS OF THE MADRAS GOVERNMENT.

(1) Print as r.s

Read the following papers:-

From the Director of Public Instruction, Madras, No. 5447, dated 16th May 1896.

From the Public Works Department, No. 3534 C, dated 7th October 1896.

From the Director of Public Instruction, Madras, No. 11032, dated 10th October 1896.

O R D E R:-No. 727, dated 20th November 1896.

fp

The plans and estimates received with the Director of Public Instruction's letter No. 11032, dated 10th October 1896 are approved and will be transferred to the Public Works Department.

(True Extract)

Francis

for Chief Secretary.

To
The Director of Public Instruction
,, Public Works Department. (with plans & estimates.) ✓

R26.7-97

P.W.

~~Educational~~ (189 7) Department.

CURRENT No. ~~837~~ 7628

727/96 Papers

Rd 30-7-97

(3)
Rusts

From
The Dir. of Pub. Instruction,
Madras.

~~**Order.**~~ **End.** No. 1610 d/30 July 1897.

H.M. J.G.
26/7/97

No. 7696.

Transferred to the Public Works Department with the request that the kitchens referred to may be constructed as early as possible.

E. Baker
Secretary to Govt.

Dated 16th July 1897.

Received ~~19 JUL. 1897~~

Registered ~~19-7-97~~ 2-8-97

Enclosures ~~one~~ 2

Spare copies 10720

J.G.
21/7/97

SUBJECT.

Requesting that the Public Works Department may be instructed to construct the new kitchens required for the Reformatory School, Chingleput and for the Deputy Superintendent's quarters.

Fwd

Refer P.W.D budget - & the P.W.D. G.O. sanctioning the plans & estimates

J.G.
21/7/97

DESPATCHED

SKW

BACK PAPERS.

G.O.	No.	Department.	Date.

FURTHER PAPERS.

G.O.	No.	Department.	Date.

No 6

To

The Director of Public Instruction,
Madras.

Sir,

I have the honour to state that the present kitchen attached to the school has been more than once condemned by the Sanitary Commissioner. It is defective from various points of view. As a plan and estimate for an improved kitchen are amongst those approved by Government in its order No 727 dated 30th November 1896, I request you will be so good as to address the Public Works Department with a view to the construction of the new kitchen being treated as an urgent matter. If funds are not immediately available for all the improvements contemplated, I trust that they will be available at least for the new kitchen which will be built at the site of the present one.

I have &c

(Sd) H.A.F.Nailer M.B.
Surg.Lt.Col.
Superintendent.

26th May 1897.

No 943.

To

The Director of Public Instruction,
Madras.

Sir,

I have the honour to request you will be so good as to let me know what action has been taken on this office letter dated 22nd February 1897 No 503, requesting that steps be taken for the early construction of the kitchen and out-houses required for the Deputy Superintendent's quarters.

2. The above quarters will be fit for re-occupation by the end of next month; and it will be great pity if Mr. Lewis is compelled again to convert one of the rooms in the house itself into a kitchen. The house is now having a new roof and ceiling put on. Apart from the great inconvenience which Mr. Lewis' family will be subjected to by having to cook in one of the rooms of the house itself, I consider it very objectionable that any room in the

building which is a public one should be converted into a kitchen and thus rendered unfit for its original purpose.

3. The room which was used as a kitchen is properly a bath room. If this room is again to be used as a kitchen, Mr Lewis will be left with only one bath room for the whole house; and as he has a large family with grown up daughters the inconvenience he will be put to by such an arrangement will be great.

4. If funds are not now available for constructing all the outhouses, I would strongly recommend that the kitchen at least should be built now so that the construction of that outhouse may be put on hand while the other repairs are in progress. I request you will be so good as to treat this recommendation as one of great urgency and importance.

I have &c.

(Sd) H.A.F.Nailer, M.B.Surg.Lt.Col.

Superintendent.

/True Copies

J. B. Bilderbeck

Ag. Director of Public Instruction.

Ouv. 1
7628/97

Enclos. to Lr. No. 837 Edl 10/8/97

C No 837 Edl

5 yarks

OFFICE OF THE DIRECTOR OF
PUBLIC INSTRUCTION,
Madras, 16th July 1897.

No. 7696.

~~Dated~~

From J.B.Bilderbeck Esq. M.A.
~~THE HONOURABLE MR. D. DUNCAN, M.A., D.Sc.,~~
Ag. DIRECTOR OF PUBLIC INSTRUCTION,
Madras,

To

The Secretary to Government.
Local and Municipal Department
Fort St. George.

× Cur 10720
Encl to G on
30/11

SIR,

With reference to G.O. No. 727 Educational, dated 20th November 1896, I have the honour to submit copies of letters from the Superintendent, Reformatory school, Chingleput, Nos. 645 and 948 of the 8th April and 26th May last, pointing out the necessity for the early construction of new kitchens for the school, and for the Deputy Superintendent's quarters, and to request ~~taht~~ that the Public Works Department may be instructed to proceed with the work at an early date.

I have the honour to be,

Sir,

Your most obedient servant,

J. B. Bilderbeck

Ag. Director of Public Instruction.

Ed. Cor. 22 1,000—21-5-95.

Pwc. 2
7625/97
7.

Cur 10720

From
The Educl Dept.

Reformatory school at Chingleput: approving plans and estimates for certain additions and alterations to the –

I

This makes the disposal of the plans & estimate an urgent matter –

Please dispose of them with the least possible delay –

Cz
5/8/97

Public Works (1897) Department.

CURRENT No. 2653

10720

Order

From The Supdg: Engineer
5 Circle

No. 89 W.

Dated 11 March 1897.
Received 13-3-97
Recd by S Aed on 30-3-97
Enclosures 2.
Spare copies

SUBJECT.

Deputy Supdts Quarters Reformatory school Chingleput – Request that plans and estimates may be sanctioned for the kitchen and outhouses for the ——— as requested in the copy of letters enclosed from the Director of Public Instruction and the Dy: Supdt.

BACK PAPERS.

G.O.	No.	Department.	Date.

FURTHER PAPERS.

G.O.	No.	Department.	Date.

No. 302

Reformatory School Chingleput
22nd February 1897

From

J D Lewis Esquire
Dy. Supdt in charge
Reformatory School
Chingleput

1 quot

To The Director of Public Instruction
Madras

Sir,

I have the honour to state that I have already brought to your notice that there is no kitchen nor a single out house attached to my quarters, and that my family has been put to considerable inconvenience thereby. I had to convert one of the bath rooms into a kitchen and this has been the source of considerable inconvenience to my people. As the house is now being re-roofed and repaired, it would be a great pity to cook again in the bath room referred to, as cooking in it will render it and the surrounding rooms dingy and dinginess is a stain which does not easily yield to whitewashing. Moreover, the bath room is needed as such for the requirements of my family.

2. In the plans and estimates for the extension of the school as sanctioned by

Government and transferred to the Public works Department, there is a plan and estimate for a kitchen and other necessary outhouses for my quarters. If these improvements are put on hand at once they could be conveniently executed together with the other repairs that are going on now. And when I shift back into the house it will be sufficiently comfortable and I shall be saved the trouble of vacating the house again for further improvements. I request you will be so good as to treat this matter as one of urgency and to address the Superintending Engineer with a view to the kitchen and outhouses referred to being put on hand at once as a special case.

3. I am writing this letter with the knowledge and approval of the Superintendent.

I have etc.

(Signed) J. P. Lewis
Dy Supdt in charge

P.W. E.1 / 2653/97

(True copy)

11/3/97
Lt Col R.E.
Superintending Engineer 5 Circle

No. 2331

Office of the Director of
Public Instruction
Madras, 6 March 1897

From
The Honourable Mr D. Duncan, M.A., D.Sc., LL.D.
Director of Public Instruction,
Madras

2 genl

To The Superintending Engineer
Fifth Circle

Sir,

I have the honour to enclose copy of a letter from the Deputy Superintendent Reformatory School, Chingleput, No. 302 dated 22nd ultimo, and to request that you will be good enough to arrange for the construction of the kitchen and outhouses referred to by him.

I have etc.

(Signed) D. Duncan
Director of Public Instruction

(True copy)

11/3/97
Lt Col R.E.
Superintending Engineer
5 Circle

11.3.97

P.W. E.2
2653/97

SUPERINTENDING ENGINEER'S O.
V CIRCLE, MADRAS,

No. 89 W

Chepák, 12th March 1897.

3 quire

From

Lieut-Colonel C.C. Rawson R.E.
SUPERINTENDING ENGINEER,
V CIRCLE,

To

THE Chief Engineer,
P.W. Department

(2) Quote:

SIR,

Enclosures.

I have the honour to forward copy letter no. 2331 dated 6th March 1897 from th Director of Public Instruction, with copy o Deputy Superintendent's letter referred to in i and to request that the plans and esti for the Kitchen and out-houses for the De Superintendent's quarters, Reformatory S Chingleput may be sanctioned as soon possible.

I have the honou
Sir,
Your most obedient

11/3/97

Superintending

11.3.97

1,000—25-2-96.

From

THE SUPERINTENDING ENGINEER,

V CIRCLE,

To

THE

Dated
Recd. } 189 .

LOSURES.

No.

15

P. W.
1,000—