C.F. 73.

Date taken out.	For what purpose.			Initials of clerk taking the paper or of attender.	Date returned.	Initials of attender.
	Department.	C. No.	Year.			

Public Works (1898) Department.

✓

G.O., No. 1409 W

DATED 6th June '98

[Despatch Abstract.]

District Munsifs' Court House at Villipuram. An Estimate of Rs 17250 for the Construction of a —— in the S. Ar Dt; Sanctioned

120/6

9/13

[P. W. 26. 1,000—12-2-98.]

Indexed. 1/6

BACK PAPERS.

G.O.	No.	Department.	Date.	G.O.	No.	Department.	Date.

FURTHER PAPERS.

G.O.	No.	Department.	Date.	G.O.	No.	Department.	Date.

BUILDINGS AND ROADS.
CIVIL WORKS.

Government {1898} of Madras.
PUBLIC WORKS.

Recd. } 1898. *Enclosures*
Regd. } *Spare copies*

G.O., No. 1409 W., 6th June 1898.

JUNE.

District Munsif's Court-house at Villupuram

An estimate of Rs. 17,250 for the construction of a —, in the South Arcot district, sanctioned.

GOVERNMENT OF MADRAS.

PUBLIC WORKS DEPARTMENT.

Buildings and Roads.
Civil Works.

Read—the following papers:—

G.O., No. 1566, Judicial, dated 30th September 1896.

Read—the following letter from the Registrar of the High Court, Madras, dated 8th September 1896, No. 473:—

With reference to G.O., No. 1814, dated 6th September 1893, I am directed to forward herewith plans and estimates for the construction of a new District Munsif's Court-house at Villupuram and to request that His Excellency the Governor in Council may be pleased to sanction the estimates and provide funds for the same.

Order—No. 1566, Judicial, dated 30th September 1896.

Subject to the remarks in endorsement No. 1925, dated 23rd September 1896, the plan and estimate received with the foregoing letter are approved and will be transferred to the Public Works Department.

(True Extract.)

(Signed) F. J. WILSON,
for Chief Secretary.

From the Superintending Engineer, V Circle, No. 323 W., dated 9th May 1898.

Abstract.—Submitting the estimate for a District Munsif's Court-house at Villupuram.

Order—No. 1409 W., dated 6th June 1898.

The estimate amounting to Rs. 17,250, for the construction of a District Munsif's Court-house at Villupuram, in the South Arcot district, is sanctioned.

2. A sum of Rs. 10,000 is appropriated for the work from the Provincial reserve.

3. The sanction accorded in paragraph 1 has been registered as Provincial No. 20 W. of 1898-99, and classified as "Civil Buildings Original—Works."

(True Extract.)

Under Secretary to Government.

To the Superintending Engineer, V Circle, with five enclosures.
" Examiner, Public Works Accounts.
" Judicial Department.

Exd. C. M. Thumbusawmy

P.W. DEPARTMENT.

Papers to be read in Proceedings:—

Again G.O., dated 189 , No.
Again G.O., dated 189 , No.
Current No. 8957 of 1896, dated 30th Septr 1896, from The Judicial Dept.
" " 4105 1898, " 9th May 1898, " The S.E. V circle No 323 W
" " 189 , " (abstract , submitting the estimate for a district munsifs court at Villupuram.

ORDER. No. 1409 W d/ 6.6.98.

To

The Chief Secretary, Judicial Dept
for favour of counter-signature

The estimate, amounting to Rs 17.250, for the construction of a District Munsifs Courthouse at Villupuram, in the South Arcot District, is sanctioned.

2 A sum of Rs 10.000 is appropriated for the work from the Provincial reserve

3 The sanction accorded in para 1 has been registered as Provincial No 20 W of 1898-99, and classified as "civil Buildings, Original Works".

A.J.H
3.6.98

T
B. PKs

AcR
27.5.98

P.K.S

2.6.98

W.S.V
W

Note.

An expenditure of Rs 718 has been incurred on the work during 1896-97, and the S.E reports that unless the estimate be

To

The S.E. V circle with 5 enclos.
" Exar P.W. Accts
" Judicial Dept

[P. W. 4.
500-24-3-98.]

J.D. recd 1.6.98 R 2/6/98 H.C. 2/6/98 R 4/6/98 be sanctioned soon. the materials collected will deteriorate so much as to become useless. It is therefore proposed to provide a sum of Rs 10.000 for the work.

2 The technical details of the estimate are dealt with in the accompanying note.

A.C.R
27.5.98.

P.K.S

W

28-5-98

Sen.
A.S.H
3.6.98

10094 W

W

Dw

On orders. draft is submitted.

25/5/98

Public Works Department.

Current No. 4105

Letter No. 323 W

Dated 9th May 1898

From the Supt. Engineer V Circle.

TECHNICAL NOTE.

Name of Work Constructing a District Munsiff's Court at Villapuram South Arcot District.

Amount of Estimate, Rs. 17,250

PARTICULARS OF ESTIMATE.

Main Building Rs 16,047

Subsidiary Buildings ,,

Contingencies 2½ per cent ,, 401

Petty Supervision 5 per cent ,, 802

Land Compensation ,,

Total Rupees ... 17,250

PARTICULARS OF CONSTRUCTION.

Surface soil Clay & Sand alternating for 7¾ ft.

Sub-soil Stiff Clay

Foundations Concrete 7 ft. deep to 9" below Ground Level.

Basement Brick in Mortar 2' 9" deep.
(Stock Bricks)

Walls Brick in Mortar to heights given in Estimate & Standard design. with damp course of asphalt ½" thick.

P. W. 58
250—5-8-96.

Plastering or Pointing Plastering inside 2 coats of Chunam and outside pointed with tar and asphalt. Plinth plastered ½" cement.

Flooring Court & Office rooms floored with 6" square pressed tiles from Govt. Brick-field on a bed of 6" brick concrete. Tiles to be set & pointed with Portland Cement. Record & property rooms & Verandahs on 6" concrete Cuddapah slabs.

Roofing Mangalore Pattern tiles from Govt brick fields - Valleys protected with $\frac{3}{32}$" lead sheets

Doors and Windows Teak battened & framed, $\frac{1}{3}$ panel & $\frac{2}{3}$ Venetian - Windows - Venetian with frames & glass heads & stained 2 coats wood oil.

Roof timbers Teak wood. all exposed woodwork to be painted 2 coats chocolate.

Scantlings Correct to Standard Plan

Rates Fair.

The plinth area of the main building is 5409 square feet, and the cost per square foot will be Rs. 3-3-0

The ~~plans and~~ estimate~~s~~ ha~~ve~~s been countersigned by the District Judge.
~~and~~

REMARKS.

This Estimate was called for in G.O. No 1491 W dated 16th June 1894 and also in item No 12 part 1 Class B works of the preliminary issue of the Provincial Civil works Budget for 1898-99 communicated with G.O. No 486 W dated 25th Feby 1898.

The proposed building will be constructed 200 feet east of the existing Taluq Office as shown on the site plan approved by the District Judge & Collector South Arcot District.

The court is to be built in accordance with the revised type design - Tiled roof - circulated with G.O. No 748 W dated 15th March 1897 -

The soil is very bad and in consequence the foundations have been allowed 7½' deep

A.C.R.
27.5.98

23.5.98

W

The cost of the building per sq. ft is high, but the rates are normal.

2. The foundations are very costly, and I am not clear that it is necessary to take them down to so great a depth, but perhaps it is advisable. The E. E. has allowed for taking them down to the depth at which sand is met.

3. The former building (Flag S) failed from insufficient foundations, 4'. 4½", & possibly, owing to bad concrete. See para 5 of E. E.'s letter (Flag S) Such soil as is there described is very untrustworthy

4. The building is an incomplete work of 1896-97, and it is said that materials collected (Flag Z) will become useless unless early sanction to the estimate is given.

A.C.R.
27.5.98.

Yes the only thing to be done is to get down to the sand.

28.5.98

Public Works (1898) Department.

CURRENT No. 4105

Order

From The Supg Engineer 5th Circle

No. 323 W.

Dated 9th May 1898.

Received 10.5.98

Enclosures 6 ~~5~~ (2 plans)

Spare copies

SUBJECT.

District Munsiffs' Court at Villupuram.

—

Submitting the Estimate for — on the new type design signed by the District Judge & requests that the Estimate may be sanctioned as early as possible —

14472

I
For sanction
CM
16/5/98

O.L.S. 134 R 6/6

BACK PAPERS.

No.	Date.
1447C	9-3-98
486-7W	25-2-98
748W	15-3-97
3502C	3-10-96
2794W	29-9-96
3456C	29-9-96
1386-7W	1-5-96
764W	3-3-96
179W	17-1-96
2434W	21-9-93

FURTHER PAPERS.

No.	Date.

200-19-1-98.

No. 323 W.

SUPERINTENDING ENGINEER'S OFFICE,
V CIRCLE, MADRAS,
Chepâk, 9th May 1898.

From
Colonel A. W. Smart R.E.
SUPERINTENDING ENGINEER,
V CIRCLE,

To
THE Chief Engineer,
Public Works Department.

Enclosures 5

1 Site Plan
1 Sketch of foundations
1 Report.
1 Detailed Estt.
1 Abstract do
1 G.O. No 1566 publ d/ 30.9.96

SIR,

With reference to your No. 1447.C. dated 9th March 1898 I have the honour to resubmit the estimate for the District Munsiff's Court at Villupuram on the new type design signed by the District Judge.

2. The soil is very bad and in consequence the foundations have been allowed very deep in order to get to sand - see letter from Executive Engineer South Arcot No 301 dated 30th May 1893 published with G. O. No 2434 W. dated 21st September 1893.

3. I request that the estimate may be sanctioned as soon as possible and funds given for the work which is really an incomplete work of 96-97 see G. O No 764 W dated

dated 3rd March 1896 on my letter No. 6 W/C dated 26th February 1896 sanctioning the burning of bricks for the work.

4. An expenditure of Rupees 718 was incurred in the collection of bricks during 96-97 and unless the estimate be sanctioned soon this will be lost as the materials will deteriorate so much as to be useless.

I have the honour to be,
Sir,
Your most obedient servant,
Colonel R.E.
Superintending Engineer 5th Circle

7.5.98

Public Works (1896) Department.

CURRENT No. 8957/ + 9728

1 Remembrance 4.5.98

No. 1447C, d. 9-3-98 Endt to Pub

From
The Judicial Department

C/
Endt
~~Order~~

Forwarded to the Supdg: Engineer, V Circle, with the request that he will revise the estimate in accordance with the type design & schedule issued with G.O. No. 768W, d. 15th March 1897, & return the same at an early date. The countersignature of the Dt. Judge should be obtained to the revised estimate.

2. The return of the Judicial Dept. G.O. herewith sent is requested.

(By Order)
(Sd) S.B.M.
D.E.W.
D. 10/3/98

No. 1506

Dated 30-9-96
Received 5-10-96
Registered
Enclosures 4 (1 plan)
Spare copies

SUBJECT.

New Dt. Munsif's Court house at Villupuram

Approving, with remarks, and transferring to the P.W.D. the plan & estimates for the construction of a new Dt. Munsif's Court-house at Villupuram, S. Arcot Dt.

I/B (after issue) vide SAW's note in red pencil

11/3/98

P. W. 29.
1,000—7-12-97.

BACK PAPERS.

No.	Date.
748W	15-3-97
C. No. 9728/96	
2794W	29-9-96
2434W	21-9-93
1386-87W	1-5-96
3502C	3-10-96
3456C	[illegible]
179W	17-1-96

FURTHER PAPERS.

No.	Date.

[G. / 5?]
3,000-3-7-96.

Judicial *Department.*

Superintending Engineer's Office, V Circle, P.W.D., Madras.
No. 4/a 2248W
11 MAR 1898

Read

PROCEEDINGS OF THE MADRAS GOVERNMENT.

Read the following paper :—

From the Registrar of the High Court, Madras, dated 8th September 1896, No. 473.

× GoO. 2434W & 21.9.93

With reference to G.O. No. 1814, dated 6th September 1893, I am directed to forward herewith plans and estimates for the construction of a new District Munsif's Court house at Villupuram and to request that His Excellency the Governor-in-Council may be pleased to sanction the estimates and provide funds for the same.

ORDER:- No. 1566, dated 30th September 1896.

× N. 3502 C & 3.10.96

Subject to the remarks in endorsement No. 1925, dated 23rd September 1896, the plan and estimate received with the foregoing letter are approved and will be transferred to the Public Works Department.

(True Extract)

For Chief Secretary.

To
The Hon. the Chief Justice (with C.L.)
,, Public Works Department (with pland and estimate in origl.)

Enclosure No. 4, to letter from the High Court of Judicature, Appellate Side, Madras, dated 8' September 1896, No. 473.

CHIEF SECRETARY
10 SEP. 1896
GOVERNMENT OF MADRAS

300—3-4-95.

Ch. No. 4605 13/4

No. 4470

5 files 9-3

Osd

These files contain a number of estimates for District Munsifs Court Houses, all of which require revision according to the latest type designs –

They have been lying over for ~~a~~ longer or shorter periods until I could find time to draw up the revised estimates, but up to this no progress has been made with them, I having had ~~so~~ so many more emergent matters to attend to –

I would propose now to send the esti: mates to the Executive Engineers concerned for revision – The

work of drawing up
revised estimates of the
kind should not
properly fall on the
Chief Engr's Office, &
seems a pity that
these estimates were
not sent away to
Supdg Engrs long ago,
as received –

8/3/98

Endorsements sub=
mitted for signature.

Yes – it is a great pity
these were not sent back
long ago – There is a
tendency wh. should be
rigorously suppressed to
do work in our Office wh.
should by rights be done
by E.E.s & S.E.s

8/3/98

we are a checking
Office –

[illegible]

Public Works (1896) Department.

CURRENT No. 9728

Order

Await receipt
of the revised type
design.

5/11/96

Copy
3-11-96.

From

The Consulting Architect
to the Government
of Madras

No. 3888

Dated 28" October 1896

Received 29.10.96

Enclosures

Spare copies

SUBJECT.

Reporting date when
the revised type plans
& Estimates for District
Munsifs Court houses
will be submitted to
the Chief Engineer
P. W. D.

BACK PAPERS.

G.O.	No.	Department.	Date.

FURTHER PAPERS.

G.O.	No.	Department.	Date.

CONSULTING ARCHITECT TO THE GOVERNMENT OF MADRAS
R. No.
28 OCT. 96

No. 3737 C

Government of Madras.

PUBLIC WORKS DEPARTMENT.

Madras, 27 October 1896.

OFFICE NOTE.

From

W

To

C.A.

Please report the date within which this office may expect to receive the revised type plans & estimates for District Munsifs' Court houses, called for in No. 3502C dated 3rd Oct 1896.

26/10/96

DW

No. 3888. CWM 24.10.96

In a fortnight's time

28/10 96.
C.A. 6 ... 10

(48—1,000—17-12-95.)

Office copy

No. 3737 C

Government of Madras.

PUBLIC WORKS DEPARTMENT.

Madras, 27-October 1896.

OFFICE NOTE.

From

W

To

C.A

Please report the date within which this office may expect to receive the revised type plans and estimates for District Munsifs' Court houses, called for in No. 3502 C dated 3rd October 1896.

(Sd) D. M. C

W

D 27/10/96. (Sd) CHBB

27/10

(48—1,000—17-12-95.)

Clr. 7728

T.

Kindly see note attached to C. No 8957 (within) and keep these papers with you.

6-11-26

3