Public Works (1898) Department.

G.O., No. 1469 W

Dated 13 June 98

[Despatch Abstract.]

Ryots' Sheds: Estimate Amounting to Rs 2000 Rs 2180 as per Memo for Constructing —— in the Compounds of the Coonoor & Gudalur D.C.'s Tahsildars' offices, Nilgiris, Approved & returned to the S.E. Wynaad, for Sanction thereto when funds are available.

110/6

Indexed.

[P. W. D. 1,000—12-2-98.]

BACK PAPERS.

G.O.	No.	Department.	Date.	G.O.	No.	Department.	Date.

FURTHER PAPERS.

G.O.	No.	Department.	Date.	G.O.	No.	Department.	Date.

BUILDINGS AND ROADS.
CIVIL WORKS.

Government {1898} of Madras.

PUBLIC WORKS.

Recd. } 1898. *Enclosures*

Regd. *Spare copies*

G.O., No. 1469 W., 13th June 1898.

JUNE.

Ryots' Sheds

Estimates amounting to Rs. 2,000 and Rs. 2,180, respectively, for constructing — in the compounds of the Coonoor and Gúdalúr Deputy Tahsildars' offices, Nilgiri district, approved and returned to the Superintending Engineer, IV Circle, for sanction and execution when funds are available.

GOVERNMENT OF MADRAS.

PUBLIC WORKS DEPARTMENT.

Buildings and Roads.
Civil Works.

READ—the following paper:—

Endorsement of the Revenue Department, dated 16th May 1898, Mis. No. 2105.

Read—the following papers:—

From H. A. STUART, Esq., Acting Collector of Nilgiris, to the Secretary to the Commissioners of Land Revenue, dated 14th February 1898, Ref. on Cur. No. 203.

In forwarding herewith two plans and estimates for the construction of ryots' sheds for Coonoor and Gúdalúr Deputy Tahsildars' offices, I have the honour to request that the Board will be pleased to accord its sanction for carrying out the work when funds are available. The estimated cost is Rs. 2,000 for the Coonoor shed and Rs. 2,180 for Gúdalúr, and I am satisfied the construction of these sheds is necessary. A sum of Rs. 1,000 has been provided for the Coonoor shed in the revised list of original works costing more than Rs. 500 submitted to the Board with this office Dis. No. 2478, dated 22nd September 1897.

2. I request that the plans and estimates may be returned when no longer required.

Ref. No. 305, dated 17th March 1898.

The estimates amounting to Rs. 2,000 and 2,180, respectively, for constructing ryots' sheds in the compounds of the Coonoor and Gúdalúr Deputy Tahsildars' offices, are submitted for the sanction of Government with reference to G.O., No. 3356 W., dated 23rd November 1896, communicated with G.O., No. 5135, Revenue, dated 12th December 1896. The works may be taken in hand when funds are available.

(Signed) R. C. C. CARR,
Secretary.

Official memorandum from the Acting Under Secretary to Government, Revenue Department, dated 31st March 1898, No. 82.

Ref. No. 407, dated 6th April 1898.

Forwarded to the Collector of Nilgiris for early attention.

From the Collector of Nilgiris, dated 15th April 1898, Ref. on Cur. No. 203, resubmitting the plans and estimates relating to the ryots' sheds at Coonoor and Gúdalúr after countersignature.

Ref. No. 487, dated 2nd May 1898.

The plans and estimates returned with Government memo., No. 82, dated 31st March 1898, have been duly countersigned by the Collector and are herewith resubmitted for the orders of Government.

(Signed) LIONEL DAVIDSON,
Ag. Secretary.

Mis. No. 2105, Revenue.

Approved and transferred to the Public Works Department for the issue of the necessary orders.

(By order.)

OOTACAMUND,
16th May 1898.

(Signed) N. E. MARJORIBANKS,
Ag. Under Secretary to Government.

ORDER—No. 1469 W., dated 13th June 1898.

The estimates, amounting to Rs. 2,000 and 2,180, respectively, for constructing ryots' sheds in the compounds of the Coonoor and Gúdalúr Deputy Tahsildars' offices, Nilgiri district, are approved and returned to the Superintending Engineer, IV Circle, for sanction and execution when funds are available.

(True Extract.)

Under Secretary to Government.

To the Superintending Engineer, IV Circle, with nine enclosures.
" Examiner, Public Works Accounts.
" Revenue Department.

Exd. T. K. Narayana Aiyangar.

P.W. DEPARTMENT.

Papers to be read in Proceedings :—

Again G.O., dated 189 , No.

Again G.O., dated 189 , No.

Current No. 4396 of 1898, dated 16th May 1898, from The Revenue Dept

" " " 189 , " , "

" " " 189 , " , "

ORDER.

No. 1469 W dy 13.6.98.

The estimates, amounting to Rs 2.000 and 2.180 respectively, for Constructing ryots' sheds in the compounds of the Coonoor and Gudalur Deputy Tahsildars' Offices, Nilgiri District, are approved and returned to the Suptg Engineer, IV circle, for sanction and execution when funds are available.

AcK 2-6-98

P.K.S.

J. 6. W

Note.

The estimates have been dealt with in the accompanying technical note. They are within the Suptg Engrs powers to sanction.

AcK 2-6-98

J. 6. W

To
The S.E. IV circle with 9 enclosures
Escar. P.W. Accts
Revenue Dept

[P. W. 4. 500—24-3-98.]

1669N

Public Works Department.

Current No. 4396

Letter No. 487

Dated 2nd May 1898

From the Board of Revenue
Land Revenue

NOTE BY TECHNICAL SECTION.

Name of work Constructing Ryots' Sheds in the compounds of the Coonoor and Gudalur Deputy Tahsildars' Offices, Nilgiri District.

Est Amts Rs 4,180

The acting Collector of Nilgiri with reference to G.O No 3356 W dated 23rd Novr 1896, communicated with G.O. No 5735 Rev dated 12th Decr 1896 forwards, through the Secretary to the Commissioner of Land Revenue, Madras, the undermentioned Estimates for the sanction of Govt:-

(a) Estimate for constructing a Ryots' Shed in the compound of the Deputy Tahsildar's Office Coonoor, Nilgiris.

Amount of Est Rs 2,000

(b) Estimate for constructing a Ryots' Shed in the compound of the Gudalur Deputy Tahsildar's Office. South East Wynaad.

Amount of Est Rs 2,180

Dr
Dr on abstract
Draft G.O.
enclosed

CR
10/5/98

A.S.H

[P. W. 60
250- 30-9-97.]

Estimate (a) provides for the construction of a Shed for Europeans and Natives - measuring 21'10½" × 14'6" for Natives, and 14'6" × 11'6" for Europeans. The North, East, & South sides will be built up to Eaves. The wall on the West side only being left partly open at top. The foundations will be of Concrete in Chunam 3'9" × 2' deep - basement of brick in mortar 2'9" × 2' high, and the walls Brick in mortar 1½" bond and 8 ft. high.
Roofing will be of corrugated iron sheets covered with hot. tiles.
Woodwork Teak wood, wood-oiled 2 coats.
Plastering 2 coats Chunam.
Flooring 6" concrete, upper 2½" of Portland Cement with surface well floated.
Doors. Teakwood battens, painted 2 coats.
Scantlings. correct.
Rates. Fair - Data, in detail, has been submitted for the principal items.
The plinth area of the building is 800 square feet and the cost per square foot will be Rs. 2-8-0.
The Plan and Estimate has been countersigned by the Collector of the Nilgiris

Estimate (b) provides for the construction of a Shed similar in dimensions to the one at Coonoor in the Gudalur Taluq Office compound South East Wynaad

Amount of Est. Rs. 2,180

The soil is said to be Easy Grass. The side walls to be built to the full height to roof on South and West sides, and to the one 5 ft. high in North and part of East sides.
Foundations will be of concrete in Chunam 3'9" × 2' deep - Basement. Brick in mortar 2'9" × 2' high.
Walls - Brick in mortar 8' high.
Roofing. Corrugated iron sheets covered with hot. tiles.
Woodwork. Vungay, painted 2 coats wood oil.
Plastering. 2 coats chunam with 2 coats whitewashing.
Flooring. 6" concrete, upper 2" of Portland Cement.
Doors. Batten, painted 2 coats wood oil.
Scantlings. Correct.
Rates. Fair. Data, in detail, has been furnished for the principal items.
The plinth area is 800 square feet and the cost per square foot will be Rs. 2-11-7.
The sites selected for both the buildings belong to Govt.
The Plan & Estimate has been Countersigned by the Collector of the Nilgiris.

A&R
2-6-98.

D.C.C.
25-5-98

O
18 4,000—19-7-97.

P. W. D

Revenue (1898) Department.

4396

CURRENT No. ~~3902~~

Rd 18-5-98

Read also Cir. 2256.

From

The Board of Revenue,
Land Revenue.

Ex 56.

Order Bid. No. 2105.

Approved and transferred to the P.W. Dept for the issue of the necessary orders.

(By order)

Under Secy to Govt.

Of No. 487

Dated 2nd May 1898.

Received 4th 20. 5. 98

Registered 4th

Enclosures 8 11 (2 plans)

Spare copies.

or Lacamined 16th may 98.

To

The P.W. Dept with enclosures.

SUBJECT.

Resubmitting to Govt. plans and estimates for constructing ayoli sheds in the Compounds of the Coonoor and Gudalur Deputy Tahsildar's offices, Nilgiri dt., duly countersigned by the Collr.

T for awaiting
ADK
18.5.98
Dwl.

P.P.K
17.5.98.

OS/31

O/2616/98 R 15/6

BACK PAPERS.

G.O.	No.	Department.	Date.

FURTHER PAPERS.

G.O.	No.	Department.	Date.

$\frac{O}{18}$ 4,004—19-7-97.

Revenue (1898) Department.

CURRENT No. 2256

From

The Board of Revenue,
Land Revenue.

Order

Ref No. 305.

Dated 17th March 1898.

Received 19th —"—

Registered 21st —"—

Enclosures 7

Spare copies.

SUBJECT.

Submitting for the Sanction of Govt. estimates for constructing ryots' sheds in the Compounds of the Coonoor and Gudalur Deputy Tahsildars' offices, Nilgiri Dt.

BACK PAPERS.

G.O.	No.	Department.	Date.

FURTHER PAPERS.

G.O.	No.	Department.	Date.

Reference on *No.* *of* 1898.

In replying the above should be quoted.

(LAND REVENUE.)

REVENUE BOARD OFFICE. MADRAS.

Read the following letter from H.A.Stuart,Esquire, Acting Collector of Nilgiris,to the Secretary to the Commissioners of Land Revenue,Madras,Ref.on No.205/cur. of 1898, dated 14th February 1898.

In forwarding herewith 2 plans and Estimates for the construction of Ryots' sheds for Coonoor and Gudalur Deputy Tahsildars offices,I have the honor to request that the Board will be pleased to accord its sanction for carrying out the work when ~~the~~ funds are available.The estimated cost is Rs.2000 for the Coonoor Shed & Rs.2180 for Gudalur and ~~and~~ I am satisfied the construction of these sheds is necessary.A sum of Rs.1000 has been provided for the Coonoor Shed in the revised list of Original Works costing more than Rs.500 submitted to the Board with this Office disposal No.2478, dated 22-9-97.

2. I request that the plans and estimates may be returned when no longer required.

-------:0:-------

Reference No.305,dated 17th March 1898

The estimates amounting to Rs.2000 & 2180 respectively for constructing ryots' sheds in the compounds of the Coonoor and Gudalur Deputy Tahsildars' offices,are submitted for the sanction of Government with reference to

Government Order No.3356 W,dated 23rd November 1896 communicated with Government Order No.5135 Rev.,dated 12th December 1896.The works may be taken in hand when funds are available .

Secretary

To

The Secretary to Govt.R.D.,with plan and estimates.

Md.R.H.

Reference on *No.* *of* 1898.

In replying the above should be quoted.

(LAND REVENUE.)

REVENUE BOARD OFFICE. MADRAS.

3P

Read letter from the Collector of Nilgiris, dated 14th February 1898, Ref. on. No. 203/Cur of 98, and Reference No. 305 dated 17.3.1898.

Also Official Memorandum from the Ag. Under Secretary to Government, Revenue Department dated 31st March 1898 No. 82 and the following Reference No. 407 dated 6.4.98.

Forwarded to the Collector of Nilgiris for early attention.

Also letter from the Collector of Nilgiris, dated 15th April 1898, Ref. on Cur. No. 203 of 98 resubmitting the plans and estimates relating to the ryots' Sheds at Coonoor & Gudalur after Counter signature.

Reference No. 487 dated 2nd May 1898.

The plans and estimates, returned with Government Memorandum,

Nº. 82, dated 31·3·1892, have been duly counter-signed by the Collector and are herewith resubmitted for the orders of Government.

Dowel Daniel

A/g Secretary.

To The Secy. to Govt. R.D.
with plans & Estimates.

Ed 84

Ow 4.0
4.3.1892