Public Works (1898) Department.

G.O., No. 324865

Dated 22 Dec 98

[Despatch Abstract.]

Town Police Station Housed at Madura.

Constructing a Housed Station at ——— Rs. 3180 for Remarks. ———, Sanctioned with

I/C.S.

Indexed 2/1

[P. W. 93. 1,000—13-4-98.]

BACK PAPERS.

G.O.	No.	Department.	Date.	G.O.	No.	Department.	Date.

FURTHER PAPERS.

G.O.	No.	Department.	Date.	G.O.	No.	Department.	Date.

BUILDINGS AND ROADS.
CIVIL WORKS.

Government {1898} of Madras.

PUBLIC WORKS.

Recd. / *Regd.* } 1898. *Enclosures* / *Spare copies*

G.O., No. 3248 W., 22nd December 1898.

DECEMBER.

Town Police Station-house at Madura

Revised estimate of Rs. 3,180 for constructing a —, sanctioned with remarks.

GOVERNMENT OF MADRAS.

PUBLIC WORKS DEPARTMENT.

Buildings and Roads.
Civil Works.

READ—the following paper:—

From Lieutenant-Colonel O. V. BODDY, R.E., Superintending Engineer, VI Circle, to the Chief Engineer, Public Works Department, dated Trichinopoly, 25th November 1898, No. 1605 M.D.

I have the honour to submit, for sanction of Government, a revised estimate, amounting to Rs. 3,180 in supersession of that for Rs. 2,940 sanctioned in G.O., No. 3303 W., dated 18th November 1896, for constructing a Town Police station at Madura.

2. The original estimate provided for an existing wall on the south side being incorporated into the building. On the work being put in hand, it was found that this wall was composed of unsuitable material and that it was not strong enough to carry the proposed terracing. It is therefore necessary to take down this wall and build a new wall together with the other walls of the building.

3. This extra work, together with the extra cost of the work ordered in Chief Engineer's note printed with the above-mentioned Government Order, has entailed an excess of Rs. 240, and a revised estimate is therefore submitted for sanction.

ORDER—No. 3248 W., dated 22nd December 1898.

The revised estimate, amounting to Rs. 3,180, for constructing a Town Police station-house at Madura, is sanctioned, in supersession of the estimate of Rs. 2,940 sanctioned in G.O., No. 3303 W., dated 18th November 1896.

2. A sum of Rs. 2,940 has been provided for the work in the current year's budget.

3. This sanction has been registered as Provincial No. 94 W. of 1898–99, and classified as Civil Buildings—Original Works.

(True Extract.)

Under Secretary to Government.

To the Superintending Engineer, VI Circle, with eight enclosures.
" Examiner, Public Works Accounts.
" Judicial Department.

Exd. A. Rungasawmy Aiyangar.

P.W. DEPARTMENT.

READ the following:—

Print

Letter from the Supdtg Engineer, VI circle, No 1605 M.D dy 25th November 1898

Circulated to the Secretary for Comments

W-3248 W & 22 Dec '98

ORDER.

The revised estimate amounting to Rs 3.180 for constructing a Town Police station house at Madura is sanctioned in supersession of the estimate of Rs 2.940 — sanctioned in G.O No 3303 W dated 18th November 1896

2. A sum of Rs 2.940 has been provided for the work in the current years budget

3. This sanction has been registered as Provincial No 94 W of 1898-99 and classified as Civil buildings. Original Works.

Note. The causes of the excess are explained in the accompanying technical note

To the Judicial Dept for favour of information

P.W. For perusal. ACH 12.12.98

To the S.E. VI circle with 8 encls
" Exam. P.W. Accts
" Judicial Dept

[P. W. 4 — 1,000—14-11-98.]

3248 W.

Public Works Department.

Current No. 9539

Letter No 1605 M. D.

Dated 25th November 1898

From the Supt Engineer III Circle

NOTE BY TECHNICAL SECTION.

Name of work. Constructing a Town Police Station at Madura

Revised Estimate - Rs 3,180.

An Estimate amounting to Rs 2,940 was sanctioned for this work in G. O. No 3303 W dated 18th November 1896 - It is now found that the present South wall marked A. B. in the accompanying sanctioned plan, which it was proposed to retain, is unsafe and too weak to carry a terrace being built of brick bats and rubbish.

It is proposed to re-build that portion of the wall which is to carry a terrace.

The increase viz Rs 240 is due to the following causes.

(a) Increase in quantity due to re-building South wall as explained above, and increased Scantling to Timbers (Joists) from 6" x

W

The excess of Rs 240. being due to wall being found necessary to the duty of carrying a terrace, & to alterations agreed in sanctioning G. O. can be passed.

A. R.

2-12-98.

12-12-98

Sanctioned works. This might perhaps be ~~if not~~ supported into if the wall was built completely recently.

In fine the E. P's record report that the wall is an old one built originally to same main by as a compound wall

S.E. for C.E. 12.12.98 16.12.98

to b 2/4" vide Chief Engineer's note printed with G.O. according sanction to Estimate ——— Rs 218

(b) Increase in amount for dismantling existing building Rs 22
and Supervision & Contingencies
Total Rs 240

A.E.K
3.12.98.

Excess can be passed

Dr
3-12-98

Public Works (1898.) Department.

CURRENT No. 9839

Order

From The Supdg Engineer
N. Circle

No. 1605. P.D.

Dated 25th November '98

Received 28-11-98

Enclosures 2 x 8 (1 plan)

Spare copies

SUBJECT.

Town Police Station at Thatha
Forwards for Sanction a
Govt a revised estimate
of Rs 3180 for Constructing

I
Just early receipt
of Rs 2 940 for
year's budget.

A.E.K
30-11-98.
DW

BACK PAPERS.

No.	Date.
4914	19-2-97
3303W	18-11-96
3450C	23-4-98
8414	7-3-96

FURTHER PAPERS.

No.	Date.

No. 1605. 2nd D.

OFFICE OF THE SUPERINTENDING ENGINEER,
6TH CIRCLE,
Trichinopoly, 25th November 1898.

D 26.

From

Lt-Col. C. V. Boady R.E
Superintending Engineer,
6th Circle.

To

The Chief Engineer,
P. W. D

SIR,

3. ENCLOSURES.

1. Orig. Estt
1. Revd Estimate with Comp: Statt & Sea Complete
1 Sanction's plan

3

I have the honor to submit for sanction of Government a revised estimate amounting to Rs 3,180 in supersession of that for Rs 2940 sanctioned in Go. No: 3303 W dated 18 November 1896, for constructing a Town Police Station at Madura.

2. The original estimate provided for an existing wall on the south side being incorporated into the building. On the work being put in hand it was found that this wall was composed of unsuitable material and that it was not strong enough to carry the proposed terracing. It is therefore necessary to take down this wall and build a new

wall together with the other wall of the
Guard Room

3. The extra work for the with the extra cost of the work ordered in Chief Engineers note marked with the above mentioned No. has entailed an ex- -cess of £ 240 and a revised estimate is therefore submitted for sanction.

I have the honor to be
Sir
Your Most obedient Servant
J. Donnelly Lieut RE
Supt Engineer, 4th Circle

3/11