Public Works (1898) Department.

G.O., No. 325 1. W.

DATED 27 December 1898.

3/1/99

[Despatch Abstract.]

Light keepers' Quarters

Sanctioning, with certain Estimate attached, the Construction of Light keepers' Quarters at Melpi, Hanger Kotha.

100/3 7/15 7/B/98.

Indexed.

[P. W. 196. 1,000—12-2-98.]

BACK PAPERS.

G.O.	No.	Department.	Date.	G.O.	No.	Department.	Date.

4865 ⎫ 5.11.98
895 ⎭ c 27.7.98
3457 c 3.6.98
1670 W 5.7.98

FURTHER PAPERS.

G.O.	No.	Department.	Date.	G.O.	No.	Department.	Date.

BUILDINGS AND ROADS.
CIVIL WORKS.

Government {1898} of Madras.

PUBLIC WORKS.

Recd. } 1898. *Enclosures*

Regd. *Spare copies*

G.O., No. 3251 W., 27th December 1898.

DECEMBER.

Lightkeepers' Quarters

Sanctioning, with remarks, certain estimates for constructing — at Malpi, Coondapoor and Hangerkotta.

Public Works (1898 &

Public Works Department.

Public Works. DEPARTMENT.

READ the following:—

Print { Letter from the Supdt of Works. L. H. Dr. No. 1448. dy 3rd December 1898.
Endorsement thereon by the Presidency Port Officer. No. 1271/261-PW dy 5th December 1898.

Light keepers' Quarters

Circulated to Secy to Govt & Secy to the Governor.

3251. W.

ORDER. No. ~~1059 Marine~~ dy 27-12-98.

The undermentioned estimates are sanctioned.

Light house Division

Excluded Local Port Funds

Civil Buildings. Original Works

		Amount. Rs	
(a) Constructing Light keeper's quarters at Malpi		3,620.	No 28 W of 1898-99
(b) — Do —	at Coondapur —	3,470	No 29 W of 1898-99
(c) — Do —	Hangerkotta —	3,460	No 30 W of 1898-99

2. A sum of Rs 3,000 has been provided for item (a) in the current year's Excluded Local Fund Budget. The provision of Rs 2,000 made for each of the items (b) and (c) is transferred from the head "Miscellaneous Public Improvements, Minor Works" to "Civil Buildings, Major Works."

P. T. 6

A.SH 25.12.98

22-12-98

note. The estimate is dealt with in the accompanying technical note.

2. The Supdt of Works has been permitted to collect materials in anticipation of sanction, in order that the working season of 1899 may not be lost, vide Memo. No. 5600 C dated 12th December 1898.

ASK
22-12-98

Maj

22.12.98

W

To

(28)

The S. W. Z H Dr with enclos. MS
" S.E. IV circle
- Examiner P W Accounts
x Marine Dept

2/1/99

x Hag G.

from A.G.M.

3251 W

Public Works Department.

Current No. 10137

Letter No 1271/261

Dated 5th Decr. 1898

From the Presidency Port Officer Madras.

NOTE BY TECHNICAL SECTION.

Name of work. Constructing Lt Ho Keepers quarters &c at Malpi Kundapur, & Hungarikotta. Estimates aggregating Rs. 10,550

W

The estimates may be sanctioned. The quarters are of the same type as others already sanctioned, & ~~are~~ data are given in the sketch

ASK
13-12-98.

The Superintendent of Works Lt Ho Division submits for sanction the undermentioned estimates.

Malpi Rs.
1 Lt Ho Lantern ——— 640
1 Lt Ho Keepers Quarters —— 2980

Kundapur.
1 Lt Ho Keepers Quarters ——— 3050
Compensation for land ——— 420

Hungarikotta
1 Lt Ho Keepers Quarters ——— 2910
Establishing Cabin Guard Lt Ho —— 50
Rs 10,550

The general provisions for the works are clearly set forth in the Report accompanying each Estimate.

Malpi. At this Station it is proposed to erect a Lt Ho Lantern resting on a Wooden Concrete 2 but in debris in

DW

13-12-98

[P.W. 60.]

of Latrite in Suki mortar, floored with Mangalore tiles in Cement and pointed with cement, and plastered with cement on the outside; also for the erection of a Lipt Kuppai Quarters and oil store.

The Soil is Lipt Loam 2' deep with Red clay & gravel below.

Foundations. Concrete in Suki Mortar 1 foot deep and Latrite in Suki Mortar 2 feet deep.

Basement. Latrite in Suki Mortar 2 feet in height.

Walls. Latrite in Suki mortar of heights allowed in Plan & archwork of the same material.

Plastering. outside ½" Cement and ordinary Mortar 2 coats on the inside.

Flooring. Basic Mission Square Tiles on 4" concrete.

Roofing timbers. Country wood wrought & put up & wood oiled.

Doors & Windows. Country wood, battens, with iron fittings reabbt painted 3 coats.

Roofing. Mangalore Tiles on Country wood Rafters

Scantlings. Correct.

Rates. Data furnished in Schedule of rates.

is 1437 Square feet and the cost per Square foot will be Rs 2-1-2. The Land is Government property. Kundapur. The Estimate No 3050 for quarters for Lipt. Kuppus and oil and general Store room on the same scale as at Malpi, as the Establishment and the conditions are similar, except that compensation for land to the extent of Rs 420 has been provided, and the Soil, Sand. The cost per square foot of the building will be Rs 2.2.0.

Hangarikotta. The Estimate submitted provides for quarters for Lipt. Kuppus and an oil and general Store on the same type as at Malpi & Kundapur, the conditions being similar, for Rs 2 9 10; The cost per square foot being Rs 2.0-4. and for Establishing the cabin and mark now at Malpi Rs 550 including Rs 400 for compensation for Land. The Lipt will be established on Sand Spit but no Survey is submitted as the

P. W. 20.
1,000—5-9-08.

C.No. 10137 22nd 12-98

Data sheet for this estimate has been returned by me to Supt of Works. at his special request.

A.K.P

22. 12. 98.

Public Works (1898) ent.

For the W&K. Works (1898) Department.

CURRENT No. 10137

C.No. 5600 C dy 12-12-98

Memo

The Supdt. of Works, Light House Division, is permitted to proceed with the collection of the materials required in anticipation of sanction.

A.K.P
7.12.98.

E.W. 9.12.98

From The Presidency Port Officer

No. 1271/261.

Dated 5-12-98

Received

Registered 7-12-98

Enclosures 23 (6 plans)

Spare copies

Rec'd.

To The Supdt. of Works. L.H. Divn.

SUBJECT Transferring with remarks plans & estimates for certain lights & lightkeepers quarters

T/ for necessary action A.K.P 12-12-98

[P. W. 29. 1,000—5-9-98.]

Rates. Data furnished in

BACK PAPERS.

G.O.	No.	Department.	Date.
	1885C	P.W.	5.11.98
	3457C	"	9.9.98
	3457C	"	6.8.98
	1670W	"	4.7.98

FURTHER PAPERS.

G.O.	No.	Department.	Date.

Public Work... nt.

Urgent

Office of the Supt. of Works, Light-house Divn.,
Egmore, Madras,
Dated 3rd December 1898.

No. 1448

From
F. W. ASHPITEL, Esq.,
Superintendent of Works,
Light-house Division,
Madras,

To
The Chief Engineer,
Public Works Department.
Thro' the Presidency Post Office. Madras.

Sir,

I have the honor to submit herewith plans & estimates as noted below and to request that you will grant permission for the collection of materials in anticipation of sanction in order that the working season of 1899 may not be lost.

Funds are available.

(?)

I have the honor to be,
Sir,
Your most obed.t servant,

F W Ashpitel

Superintendent of Works
Light-House Dp.

Enclosures.

Malpe.
1 Light house Location plan
1 Survey plan & 1 Estimate Rs 640.
1 Light Keepers quarters plan & 1 estimate " 2980 Rs 3620.

Kundapur.
1 Light Keepers quarters plan & 1 Estimate Rs 3050 Rs 3050
1 Survey plan.
1 Estimate for compensation plots ..... " 420

Hungarikatta.
1 Light Keepers quarters plan
1 Estimate ..... Rs 2910
1 Estimate for establishing a Cairn & mast light ... " 550 Rs 3460

1 Original data sheet for Malpe, Kundapur & Hungarikatta.

Kalis. Data

No. 1271/264 I.M.

Forwarded for the sanction required, observing that the work in each case is necessary for the efficiency of the lights specified.

H. A. Street
Commander, R.I.M.
Superintendent: Port Officer

Madras.
5th December 1898.