9593

Public Works (1898) Department.

G.O., No. 924-5 I

DATED 30 Nov 1898

[Despatch Abstract.]

Drainage Sluice in the Kistna River Bank

Estimate of Rs 1400 for Reconstructing the ——— at Vellatur Lock, Sanctioned, with Remark; and a Copy of the Proc: ordered to be forwarded to the Govt of India.

Drainage Sluice in the Kistna River Bank

Forwarding Copy of Proc: Sanctioning, with Remark, an Estimate of Rs 1400 for Reconstructing the ——— at Vellatur lock.

[P. W. 26. 7,000—12-9-98.]

Indexed 3/IV

7.12.98

BACK PAPERS.

G.O.	No.	Department.	Date.	G.O.	No.	Department.	Date.

FURTHER PAPERS.

G.O.	No.	Department.	Date.	G.O.	No.	Department.	Date.

Public Works (1898) Department.

CURRENT No. 9573

From the Chief Engr for Irrigation

Order

No. 290-I.

Dated 16-11-98

Received

Registered 19.11.98

Enclosures 5 (1 Plan)

Spare copies

SUBJECT.

Reconstructing the drainage sluice in the Kistna river bank at Vellatur lock — Note recommending that the estimate of Rs 1120 for — may be sanctioned

W.L. A.-B. note please
Sir Bruce
Sir Evan
15.11.98

A. submitted
Grace noted
20/11/98

BACK PAPERS.

No.	Date.

FURTHER PAPERS.

No.	Date.

H E

PUBLIC WORKS DEPARTMENT,

IRRIGATION BRANCH.

PROCEEDINGS OF THE MADRAS GOVERNMENT.

Note recommending for sanction Estt
of Rs 1400 for recondy the drainage
Sluice in the Kistna River bank at Vellatur lock"

UNDER date the

From the Supdg: Engineer II Circle — No. 3187 K.W. dated 12th October 1898

READ the following

No 2905 dy 16.11.98

Note by the Chief Engineer for Irrigation

The accompanying estimate of Rs 1120 submitted by the Supdg: Engineer II Circle provides for re-constructing the drainage sluice in the Kistna River bank at Vellatur lock, which is reported to be so badly cracked as not to admit of satisfactory repairs or improvement.

2. The work is classed as unremunerative and will probably be completed by the 31st March 1900.

3. The estimate may be ~~recommended for~~ sanctioned.

Order

Order thereon No: 924 I 30th Nov 98

The following estimate is sanctioned:—

Capital Expenditure not charged to Revenue.

49. Irrigation.

Kistna Delta System.

Western Section.

Open Capital Account.

I. Head works.

2. Main Canals & Branches

8. Escapes.

Unremunerative work.

Reconstructing the drainage sluice in the Kistna River bank at Vellatur lock.

	Rs.
I. Works	1120.
II Establishment	258.
III Tools & plant	22
Total estimate	1400.

2. This sanction is registered as No. 97. I of 1898-99 and will expire on the 31st March 1900.

3. The cost of the original sluice, viz. Rs. 208, will be written back by the Examiner of P.W. Accounts from the "capital" to the "Revenue Account" of the Kistna Delta System in accordance with paragraph 37, Chapter V, Volume II, P.W.D. Code.

4. Ordered that a copy of these Proceedings be forwarded to the Government of India for information.

Endorsement No 925 I 30 Nov 98

Forwarded.

16/11/98

16.11.98

Signed copy 5/12/98

4/12/98

To,
The Chief Engineer for Irrigation.
" Supdg. Engineer II Circle
" Examiner P.W. Accounts
Editors' Table

14.11.98 15/12/98

9/12/98

Reinstate ... [illegible]

Con 9593.

Chf. 18/10/98

Public Works (1898) Department.

CURRENT No. 2478

From The Superintending Engineer
II Circle

Order

No. 3187 KW.

Dated 12 · 10 · 98.

Received } 14 — do —
Registered }

Enclosures two.

Spare copies

SUBJECT.

Reconstructing drainage Sluice in Nehru Canal to Lee Water Lock — Forwards for Approval and Sanction plan and Estimate for Rs 1 for orders.

Lee 14/10/98

To Superintending Engineer

B/4-10

E. I. Form No. 1 (a)—500—21-4-98.

16-11-98 Rec'd 15-11-98

BACK PAPERS.

No.	Date.

FURTHER PAPERS.

No.	Date.

211

Report to accompany the Estimate for reconstructing a Drainage Sluice in the River bank at Vellatur Lock. Estimate Rs. 1170

1. The sluice is intended to discharge the drainage of the Vellatur Village which lies between the Kistna Right flood bank and Ring bund, into the Bank canal below Vellatur Lock. The area of the village is about 50 acres. The Sluice is ~~discharged~~ designed with sufficient vent to discharge the rain fall of one inch over this area in one hour.

2. The level of the lowest land is 16.25 and the F.S.L below Vellatur Lock is 17.44. As the Bank canal water will flow into the Village when it is full, a Screw gearing shutter has been provided. At times of rain fall this sluice will be opened & the lands drained. During the rainy season the water level below Vellatur Lock is generally ~~16.44~~ 15.44 Rm.

3. As the river bank in which the sluice was built has, recently, been ordered to be raised to five feet above the maximum flood level of 1896 with 10' top width, the Existing sluice requires to be improved to suit the new bank. But it is so badly cracked that no satisfactory repairs or improvements can be carried out. It is, therefore, proposed to rebuild it as per plan & Estimate herewith

The Estimate for raising right bank of the Kistna River received from SE has been returned for further ation.

sent up.

4. The estimate for the existing work was sanctioned in Superintending Engineer's No. 2451 K.S of 21.1.85 and was built at a cost of Rs 208 in 1885-86 from the provision for contingencies in the Vellatur Lock estimate. As the cost of reconstruction is more than that of the existing work, the Estimate will have to be sanctioned under open capital Kistna Delta System & the cost of the old work written back to Revenue. The work is non remunerative but required for the safety of the River bank and the Bank canal. It is, therefore, recommended to be sanctioned under "open capital Kistna Delta System"

R. a. Srinivasa Ayyangar
20.9.98
Executive Engineer.
Kistna Western Division.

Encls: 2

No. 3187 KW. Superintending Engr's Office
2nd Circle. Dated 12th October 1898

From

W. C. Lewis Esquire.
Offg: Superintending Engr.
2nd Circle

To

The Chief Engineer.
For Irrigation.

Sir.

I have the honor to forward herewith plan and estimate amounting to Rs 1120/- for reconstructing a drainage sluice in river bank below Vellatur Lock, for your approval and Sanction of Government.

2. The report accompanying explains the necessity for the work.

3. The estimate is recommended for Sanction under "open Capital" and the work is non-remunerative.

I have the honor to be
Sir,
Your most obt Servt
for: AO Campbell 12/10/98
Offg: Superintending Engr
2nd Circle

12/10/98

CHIEF ENGINEER
FOR IRRIGATION.
14 OCT. 1898
No. R247 K4