Public Works (1899) Department.

G.O., No. 1750 W

DATED 8th July 1899.

[Despatch Abstract.]

Famine Roads

Sanctioning, with remarks, certain estimates for ——— in the Bellary District, under 33 Famine Relief.

11/7

~~T.R.C.~~

17/7

P. W. 31.
250—27-4-99.

BACK PAPERS.

G.O.	No.	Department.	Date.	G.O.	No.	Department.	Date.

FURTHER PAPERS.

G.O.	No.	Department.	Date.	G.O.	No.	Department.	Date.

BUILDINGS AND ROADS.
CIVIL WORKS.

Government (1899) of Madras.

PUBLIC WORKS.

Recd. } 1899.
Regd. } 1899.

Enclosures
Spare copies

G.O., No. 1750 W., 8th July 1899.

JULY.

Famine Roads

Sanctioning, with remarks, certain estimates for — in the Bellary district, under 33. Famine relief.

GOVERNMENT OF MADRAS.

PUBLIC WORKS DEPARTMENT.

Buildings and Roads.
Civil Works.

Read—the following papers :—

Proceedings of the District Board, Bellary, dated 11th February 1899.

Present.

* * * * *

Resolution—No. 6.

Read footnote No. 1612, dated 7th February 1899, from the Local Fund Engineer, Bellary, submitting for sanction estimates for the construction of the following roads as famine-relief works for the year 1899–1900 :—

* * * * *

New Works.

	RS.
Adoni Taluk.	
1. Constructing a road from the Tungabhadra railway station on the Madras Railway to Sidaragadda *viâ* the village on the bank of the Tungabhadra river, 30 miles	1,43,510
2. Constructing a road from Adoni to Vallur *viâ* Isivi, Kaditota, Badanchalu, Kowtalam, Bhanta kunta, Sulikera, Peddakunta and Halir, 24 miles	1,19,800
3. Completing the road from Yemmiganuru to Kosigi, 1st to 20th mile	10,760
4. Constructing a road from Rowdur to Hotshalli *viâ* Biravalli ...	31,320
Alur Taluk.	
5. Constructing a road from Yerur to Belladona, 5 miles ...	19,620
6. „ „ from Halaharivi to Guliem *viâ* Bapuram, 6 miles	26,120
7. „ „ from Yerur to Bantanahal railway station.	12,650
8. „ „ from Guliem to Hollalagundi *viâ* Siddapuram and Kogiltota, 11 miles ...	45,900
9. „ „ from Arekera to Hollalagundi *viâ* Virapuram, 13 miles	44,040
10. „ „ from Molagavalli to Alur, 8 miles ...	36,330
Hospet Taluk.	
11. Constructing a railway feeder road from the Tornagallu-Yettinahatti road to Tornagallu railway station	9,820

* * * * *

(Signed) R. H. CAMPBELL,
President.

Dis. No. 151.

Submitted with the estimates to the Secretary to Government, Local and Municipal Department, Madras, for favour of sanction through the Superintending Engineer, Public Works Department, Bellary.

(Signed) S. GOPALACHARI,
for President.

23rd March 1899.

No. 1998 W.

Submitted to the Chief Engineer, Public Works Department, with a request that he will be good enough to obtain the sanction of Government in the Local and Municipal Department.

(Signed) W. L. C. BADDELEY, Lt.- Col., R.E.,
Superintending Engineer, III Circle.

29th May 1899.

Order—No. 1750 W., dated 8th July 1899.

The undermentioned estimates for famine roads in the Bellary district are sanctioned under 33. Famine relief :—

LOCAL.

Name of work.	Amount of estimate.	Register number.
Adoni Taluk.	RS.	
(1) Constructing a road from the Tungabhadra railway station on the Madras Railway to Sidaragadda *viâ* the villages on the bank of the Tungabhadra river, 30 miles	1,43,510	No. 1 W. of 1899–1900.
(2) Constructing a road from Adoni to Vallur *viâ* Isivi, Kaditota, Badanchalu, Kowtalam, Bhanta kunta, Sulikera, Peddakunta and Halir, 24 miles ...	1,19,800	No. 2 W. of 1899–1900.
(3) Completing the road from Yemmiganuru to Kosigi, 1st to 20th mile	10,760	No. 3 W. of 1899–1900.
(4) Constructing a road from Rowdur to Hotshalli *viâ* Biravalli	31,320	No. 4 W. of 1899–1900.
Alur Taluk.		
(5) Constructing a road from Yerur to Belladona, 5 miles.	19,620	No. 5 W. of 1899–1900.
(6) „ „ from Halaharivi to Guliem *viâ* Bapuram, 6 miles	26,120	No. 6 W. of 1899–1900.
(7) „ „ from Yerur to Bantanahal railway station	12,650	No. 7 W. of 1899–1900.
(8) „ „ from Guliem to Hollalagundi *viâ* Siddapuram and Kogiltota, 11 miles	45,900	No. 8 W. of 1899–1900.
(9) „ „ from Arekera to Hollalagundi *viâ* Virapuram, 13 miles	44,040	No. 9 W. of 1899–1900.
(10) „ „ from Molagavalli to Alur, 8 miles.	36,330	No. 10 W. of 1899–1900.
Hospet Taluk.		
(11) Constructing a railway feeder road from the Tornagallu-Yettinahatti road to Tornagallu railway station ...	9,820	No. 11 W. of 1899–1900.

2. The works should be put in hand only in the event of famine relief, and even then they should not be taken up for execution with the exception of No. 3 until other available works are exhausted, as it will be found beyond the powers of the District Board to maintain them when finished.

(True Extract.)

Under Secretary to Government.

To the Superintending Engineer, III Circle.
„ Examiner, Public Works Accounts.
„ Local and Municipal Department, with enclosures.

Exd. T. K. Narayana Aiyangar.

P.W. DEPARTMENT.

Send print

Print [illegible]

READ the following :—

Print

From the President, District Board, Bellary, Dis No 151 dy 23.3.99

From the Supty Engineer, III circle No 1998W dy 29th May 1899.

Circulated to H. E. the Engineer

M 6th [illegible]

To The Secretary to Govt. [illegible] Dept for favour of C.I.

4P

F.2.H. 3.7.99

ORDER. No 1750 W dy 8-7-99

The undermentioned estimates for Famine roads in the Bellary District are sanctioned under 33. Famine Relief :—

Local

Name of Work	Amount of estimate Rs	Register number
Adoni Taluk		
(1) Consty a road from the Tungabhadra Railway station on the Madras Railway to Sidaragadda (via) the villages on the bank of the Tungabhadra river — 30 miles	1.43.510.	No 1 W of 1899-1900
(2) Consty a road from Adoni to Valluir (via) Isivi, Kaditola, Badanchala, Kowtalam, Bhantakunta, Suli, Kera, Peddakunta and Halir — 24 miles	1.19.800.	No 2 W of 1899-1900
(3) Completing the road from Yemmiganur to Kosigi. 1st to 20th mile —	10.760	No 3 W of 1899-1900
(4) Consty a road from Rowdur to Hotshalli via Biravalli —	31.320.	No 4 W of 1899-1900
Alur Taluk		
(5) Consty a road from Yemmi to Belladona, 5 miles —	19.620	No 5 W of 1899-1900
(6) — do — from ~~Halaharvi~~ Halaharivi to Gulum via Bapuram, 6 miles —	26.120	No 6 W of 1899-1900

(7) Consty

[P. W. 42-A. / 1,000—2-3-99.]

to Rev Dept for C.I. 16/6. [illegible] 20/6 [illegible] 20/6 R 5/7

T

B

C S

Alur Taluk continued

	Amount of estimate Rs	Register No
(7) Constg a road from Terur to Bantanahal Railway station.	12.650.	No 7 W of 1899-1900.
(8) — do — from Gulhem to Hollalagundi [via] Siddapuram and Kugiltota — 11 miles	45.900.	No 8 W of 1899-1900
(9) — do — from Arekera to Hollalagundi [via] Virapuram. 13 miles	44.040.	No 9 W of 1899-1900.
(10) — do — from Molagavalli to Alur - 8 miles -	36.330.	No 10 W of 1899-1900.
Hospet Taluk		
(11) Constg a Railway feeder road from the Tornagallu Yettinahatti Road to Tornagallu Railway station —	9.820.	No 11 W of 1899-1900.

2. The works should be put in hand only in the event of Famine Relief ~~but~~ and even then they should not be taken up for execution with the exception of No 3 until other available works are exhausted, as it will be found beyond the powers of the District Board to maintain them when finished.

16.6.99
W.

P.K.S.

Note. The estimates are dealt with in the accompanying technical note

16.6.99
W.

P.K.S.

To
The S.E. III Circle
" Exe. P.W.A.
" L + M Dept with enclosures. ✓

Dees
7/5/99

6 & 10
19.6

Note for office
Before sending to Press care should be taken to see that all the names are correct

---

Public Works Department.

Current No. 4303
Letter No 1998 W
Dated 29 May 1899
From the S.E. III Circle

NOTE BY TECHNICAL SECTION.

17504 ✓

Name of work Famine Relief Roads in the Bellary District.

seen by DW

The S.E. III Circle with his Lr. 1998 W of 29 May 1899, submits 11 Estimates for Famine Relief Roads in the Bellary Dist. as follows.

(1) Constructing roads from the Tungabhadra Station on the Madras Railway to Sidaragada via villages on the bank of the Tungabhadra - Adoni Taluq.

Length . . . . 30 miles
Top width of road . . . 18' . . slopes 1½ to 1
Metalling . . . . width 15' thickness 6"
gravelling . . . . " — 18' — " — 3"
Estimate Rs: 143510

(2) Constructing a road from Adoni to Valleir via Isvi, Kasitota, Badanahal, Kontalkum, Bhantakunta, Salkari, Peddakunta & Halvi - Adoni Taluq.

Length . . . . 24 miles
Top width of road — 18' — slopes 1½ to 1.
Metalling — — width 15' thickness 6"
gravelling — " — 18' — " — 3"
Estimate Rs: 119800

(3) Completing a road from Kosigi to Yemmiganur via Mantapalley. Adoni Taluq.

This is a useful road & shd be completed

P. W. 60.
250—5-9-98.

p width - - - 18' - Slopes 1½ to 1.
Length ——— 10 miles
no metal
gravelling — — width 15' thickness 6".
Estimate Rs. 10760

(4) Constructing a road from Kowsur to Holshalli via Bora-valli - Adoni Taluq.
Length - - - 7 miles
Top width - - - 18' - side slopes 1½ to 1
Metalling - - width 15' thickness 6"
gravelling - " - 18' - " - 3"
Estimate Rs 31320

(5) Constructing a road from Yerur to Bellatona - Alur Taluq.
Length - - - - 5 Miles
Top width of road - - 18' slopes 1½ to 1.
Metalling - width 12' thickness 6"
gravelling — " - 15' — " — 3"
Estimate Rs: 19620.

(6) Constructing a road from Halaharvi to Gulyam via Bapuram - Alur Taluq.
Length ——— 6 miles
Top width of road 18' slopes 1½ to 1.
Metalling width 12' - thickness 6"
gravelling — " — 15' — " — 3"
Estimate Rs: 26210

(7) Constructing a road from Yerur to Bantanahal Railway Station - Alur Taluq.
Length — — 3 miles
Top width of road 18' slopes 1½ to 1.
Metalling width 12' thickness 6"
gravelling — " - 15' — " — 3"
Estimate Rs. 12650

(8) Constructing a road from Golyam to Holagundi via Siddapuram and Kogilathota - Alur Taluq.
Length - - - 11 miles
Top width - — 18' - slopes 1½ to 1.
Metalling - 12' width - thickness 6"
gravelling - 15' — " — " — 3"
Estimate Rs: 45900

(9) Constructing a road Arikera to Hollagoondi via Virupapuram Alur Taluq.
Length - - - - - 13 miles
Top width - - - 18' - - Slopes 1½ to 1
Metalling - - width 12' thickness 6"
gravelling — " - 15' — " — 3"
Estimate Rs 44040.

(10) Constructing a road from Molagavally to Alur - Alur Taluq.
Length ——— 8 miles
Top width - - - 18' - - Slopes 1½ to 1.
Metalling - width 12' - thickness 6"
Gravelling — " - 15' — " - 3"
Estimate Rs: 36330.

(11.) Constructing a Railway Feeder from the Tornagal - Yettinahatti Road to Tornagal Ry: Station Hospet Taluq.
Length ——— 2 miles
Top width - - - 18' — slopes 1½ to 1.
Metalling - width 15' - thickness 6"
gravelling - - " - 18 — " — 3"
Estimate Rs: 9820

Rates. The rates it is stated have been checked and are in accordance with the L.F. schedule for 1899/1900 in the Circle Office.

The Estimates have been countersigned by the President District Board – and considered in Board's Proceedings dated 11th Feby: 1899.

Am. 12-VI-99

The Estimates may be sanctioned for famine relief purposes, but they should not be ~~put in hand~~ taken up for execution until other available works are exhausted as it will be found beyond the powers of the District Board to maintain them when finished.

H.L. 14/6

approval

14-6-99

Public Works (1899) Department.

CURRENT No. 4303

From The Superintg. Engineer 3 Circle Bellary

Order

No. 1998 W

Dated 29 May 1899

Received
Registered 31-5-99

Enclosures 11 Estimates & letter

Spare copies

SUBJECT.

Roads in Bellary Dt

Forwards, for sanction 11 Estimates for constructing as Famine Relief works for the year 1899–1900

T/ For sanction

31/5/99 HC

oLS 2021717

BACK PAPERS.

No.	Date.

FURTHER PAPERS.

No.	Date.

Local & Munl. (1899) Department.

CURRENT No.

SUPERINTENDING ENGINEER, III. CIRCLE, BELLARY, P.W.D.
Regr. No. 92
24 MAR 99

From The President
District Board.
Bellary.

Order

Dis No. 151

3 P

Enclosures
11 Estimates

Dated 23rd March 1899

No. 1998 W dated 29 May 1899.

Received

Registered

Enclosures 11

Spare copies

Submitted to the Chief Engineer, P. W. Department with a request that he will be good enough to obtain the sanction of Government in the Local & Municipal Department.

Lieut.-Col. R.E.
Supdg: Engineer, III Circle.

SUBJECT.

Famine Relief

Submitting for sanction of Government certain estimates for the construction of roads to be carried out as —— works for the year 1899-1900

S.D

BACK PAPERS.

G.O.	No.	Department.	Date.

FURTHER PAPERS.

G.O.	No.	Department.	Date.

PROCEEDINGS OF THE DISTRICT BOARD BELLARY.

Dated 11th February 1899.

18

Present

R. H. Campbell Esqr., President

Official Members

1. M. R. Ry. Rao Bahadur P. Rama Rao Garu, Tahsildar of Hospet
2 – do – Rao Bahadur P. Subbraya Mudaliar Avl., Tahsildar of Adoni
3 – do V. Subbraya Mudaliar Avl., Tahsildar of Rayadrug
4 – do K. Ramakrishnabrahmam Pantulu Garu, Tahsildar of Hadagalli
5 – do – S. Swami Aiyar Averghal, Assistant Inspector of Schools, Bellary
6 – do S. V. Melagiri Rao Garu, Sub Assistant Inspector of Schools, Hospet Range
7 – do J. Vittal Pant Garu. Sub Assistant Inspector of Schools, Bellary Range

Non-Official Members

8 – do J. Seenambhat Garu
9 – do A. Bhima Rao Garu.
10 – do P. Rama Rao Garu.
11 – do G. Venkoba Rao Garu.
12 – do S. Venkappayya Garu.
13 – do H. Rungana Gowd Garu.
14 – do C. Hanumantha Gowd Garu.
15 – do D. Krishnamacharlu Garu.
16 – do J. P. Kotilingam Averghal, M.A.
17 – do – B. Virupaksha Reddi Garu.
18 – do – A. Virupaksha Gowd Garu.
19. Mahammad Shah Saheb.

Resolution No. 6

Read footnote No. 1612 dated 7.2.99 from the Local

Local Fund Engineer Bellary Submitting for Sanction estimates for the construction of the following roads ~~works~~ as Famine Relief Works for the year 1899-1900.

New works

Adoni Taluk

1. Constructing a road from the Tungabhadra Railway Station on the Madras Railway to Sidaragadda (via) the village on the bank of the Tungabhadra river 30 miles - Rs 1,43,510.

2. Constructing a road from Adoni to Vallur (via) Isivi Kaditota, Badanchalu, Kowtalam, Bhanta Kunta, Sulikera Peddakunta and Halvi. 24 miles - - - - - - - - Rs 1,19,800

3. Completing the road from Yemmiganur to Kosigi - - - - Rs 10760.

4. Constructing a road from Rowdur to Hoshalli (via) Biravalli 1st to 20th mile } " 31320

Alur Taluk

5. Constructing a road from Yerur to Belladona, 5 miles Rs 19,620

6. - do - do - from Halaharivi to Gulium (via) Bapuram 6 miles - " 26120.

7. - do - do - from Yerur to Bantanahal Railway Station } " 12650.

8. - do - do. from Gulium to Hollalagundi (via) Siddapuram and Kogiltota 11 miles } " 45,900

9. - do - do - from Arekera to Holalagundi (via) Virapuram, 13 miles - - - - - - - - } " 44040.

10. - do - do - from Molagavalli to Alur. 8 miles - " 36330.

Hospet Taluk

11. Constructing a Railway feeder Road from the Toranagal-Yettinahatti Road to Toranagal Railway Station Rs 9820 15,230

× × ×

2P

(Sd) R. H. Campbell
President

Dis 151
23-3-59

(True Copy)

Submitted with the estimates to the Secretary to Government Local and Municipal Department Madras for favour of Sanction through the Superintending Engineer P. W. D. Bellary.

Vice President
for President

20/5.