Public Works (189) Department.

G.O., No. 2427 W

DATED 15 September 89

16/9/89

[Despatch Abstract.]

Subordinate Judge's Court at Kottakara

Tinnevelly Dt.

The estimate, amounting to Rs 4280

remodelling and terracing the roof

The _____ sanctioned for very ea

execution.

100/4

T

B

C.S.

[P. W. 56.
500—19-7-89.]

BACK PAPERS.

G.O.	No.	Department.	Date.	G.O.	No.	Department.	Date.

FURTHER PAPERS.

G.O.	No.	Department.	Date.	G.O.	No.	Department.	Date.

BUILDINGS AND ROADS.
CIVIL WORKS.

Government {1899} of Madras.

PUBLIC WORKS.

Recd. } 1899. *Enclosures*

Regd. } *Spare copies*

G.O., No. 2427 W., 15th September 1899.

SEPTEMBER.

Subordinate Judge's Court at Kokkarakulam, Tinnevelly District

The estimate, amounting to Rs. 4,280, for remodelling and terracing the roof of the —, sanctioned for very early execution.

GOVERNMENT OF MADRAS.

PUBLIC WORKS DEPARTMENT.

Buildings and Roads.
Civil Works.

READ—the following papers:—

From A. L. HANNAY, Esq., I.C.S., Registrar of the High Court of Judicature, Madras, to the Chief Secretary to the Government of Madras, dated 25th July 1899, Ref. on Cur. No. 1770.

With reference to G.O., No. 2677 W., dated 14th October 1898, read in G.O., No. 1660, dated 26th idem, I am directed to forward, for the sanction of His Excellency the Governor in Council, an estimate, amounting to Rs. 4,330, and a plan for remodelling and terracing the roof of the Subordinate Judge's Court of Tinnevelly at Kokkarakulam, prepared by the Superintending Engineer, VI Circle.

No. 2005, Judicial.

Transferred to the Public Works Department.

8th August 1899. (Signed) A. R. KNAPP, Under Secretary.

Note by the Chief Engineer, Public Works Department.

Submitted for the sanction of Government with the remark that the provision of bamboo tatties to keep out rain from beating into clerks' rooms is opposed to the orders contained in paragraph 4, chapter X, Volume I of the Public Works Code, and has therefore been struck out, the amount of the estimate being reduced from Rs. 4,330 to Rs. 4,280.

4th September 1899. (Signed) W. B. DEWINTON, Chief Engineer.

ORDER—No. 2427 W., dated 15th September 1899.

The estimate, amounting to Rs. 4,280, as altered by the Chief Engineer for remodelling and terracing the roof of the Subordinate Judge's Court at Kokkarakulam, Tinnevelly district, is sanctioned for very early execution, and an allotment of Rs. 4,280 has been made for the work in G.O., No. 2399 W., dated 13th September 1899.

2. Attention is drawn to the Chief Engineer's note read above.

3. This sanction has been registered as Provincial No. 62 W. of 1899–1900 and classified as Civil Buildings—Original Works.

(True Extract.)

Under Secretary to Government.

To the Superintending Engineer, VI Circle, with nine enclosures.
" Examiner, Public Works Accounts.
" Judicial Department.

Exd. S. J. Pereira.

Very Urgent

P.W. DEPARTMENT.

READ the following:—

Letter from the Registrar, High Court of Judicature, Madras, Ref on current No 1770 dy 25.7.99

Endorsement thereon from the Judicial Dept No 2005 dy 8.8.99

Note by the Chief Engineer P.W.D. dy 4.9.99.

Circulated to

ORDER.

No: 2427 W dy 15.9.99

The estimate, amounting to Rs 4.280, as altered by the Chief Engineer, for remodelling and terracing the roof of the Subordinate Judge's Court at Kokkarakulam, Tinnevelly District, is sanctioned for very early execution; and an allotment of Rs 4.280 has been made for the work in G.O. No 2399 W dated 13th Sept 1899.

2. Attention is drawn to the Chief Engineer's note read above.

3. This sanction has been registered as Provincial No 62 W of 1899-1900, and classified as Civil Buildings Original Works.

Note The estimate is dealt with in the accompanying technical note and in C.E's note read above.

2. The building is unsafe in its present condition.

To the S.E. VI circle with spare
.. Exam P.W. A
.. Judicial Dept

[P. W. 42-A. 1,000—2-3-99.]

P. W. D

Note by the Chief Engineer P.W.D

Submitted for the sanction of Government with the remark that the provision of bamboo tatties to keep out rain from beating into clerks' rooms is opposed to the orders contained in para 4. Chapter XI Vol I of the P W code and has therefore been struck out, the amount of the estimate being reduced from Rs 4.330 to Rs 4.280.

Pkl.


Secy.
H.L.H.

~~Judicial~~ (1899) Department.

6526

CURRENT No. ~~3108~~

C.S.



28

From The Registrar,
High Court of Judicature,
Madras.

~~Order~~ Endorsement No. 2005 dt. 8-99.

Transferred to the
Public Works Deptt:

Ref on Corr No. 1770.

A. Knapp.
Under Secretary.

Dated 25th. July 1899.
Received abstracted 28-8-99
Registered 29 " "
Enclosures Two (Plan & Others) 10
Spare copies

Ned.
2/9/99.

1784.

SUBJECT.

Forwarding for sanction of His Excellency the Governor in Council an estimate and plan for remodelling and terracing the roof of the Subordinate Judge's Court of Tinnevelly

I.

The Public Works Deptt.

I
For check
Plan
11.8.99

Mem
os 5403
Rv 13/9

569

BACK PAPERS.

G.O.	No.	Department.	Date.
	1660 & 26. x. 98.		
	463 & 17.3.98		

FURTHER PAPERS.

G.O.	No.	Department.	Date.
	2524c Jw		30-5-99
	2677w.		14-10-98
	9328.		9-9-98
	742w.		18-3-98

CURRENT NO. 3108

No. 220A/1,000 22—12—98.

Ref. on Cur. No. 1770/99.

High Court of Judicature,

Madras, 25th July 1899.

No.

From

A. L. Hannay, Esquire, I.C.S.,

Registrar of the High Court of Judicature,

Madras,

To

The Honourable Mr. G. Stokes, I.C.S.,

Chief Secretary to the Government of Madras.

Honourable Sir,

1660 / 26. x. 98.

With reference to G. O. No. 2677,W, dated 14th October 1898, read in G. O. No. 1660, dated 26th. idem,

Boden attached

I am directed to forward for the sanction of His Excellency the Governor in Council, an estimate amounting to Rs. 4330./ and a plan for remodelling and terracing the roof of the Subordinate Judge's Court of Tinnevelly at Kokkarakolu, prepared by the Superintending Engineer, 6th Circle.

I have the honour to be,

Honourable Sir,

Your most obedient servant,

A. L. Hannay

Registrar.

V.A. 26/7/99.

DB

CN: 65-26.

bw

For orders

(1) with reference to the last para of T's note.

(1) As regards provision of funds.

According to the Register here we have Rs 7326 in Reserve - and we have had urgent demands amounting to Rs16000 from the S.E. IV and the C.A. for works in progress - The papers are at Ootacamund.

The work appears to be urgent as the rafters of the building are said to be much sagged, several being rotten - vide para 4 of T's note.

The Estimate for the correspondence Office of the Collectors office which is in the same building was

bw
W has called for a list of urgent works for which funds are required. This work will be included in the
Vgs. list.
Old
P/Rs 17/8/59

Bwd 1
65-26/59

was recently sanctioned for execution when funds are available". The G.O. (No 2109 W dt 10.8.99) is in the Press.

J.J.
15/8/99

Funds for this should be provided for execution at the same time

H.E.S

Ys - Sanctioned for the very urgent works

17/8/99

14275

Public Works Department.

Current No. 6526

Letter No 2005 G

Dated 8th August 1899

From the Judicial Dept:

NOTE BY TECHNICAL SECTION.

Name of work Removing and Terracing the roof of the Subordinate Court at Kokkarakolam - Tinnevelly Dist:

Est: Rs 4330.

The Dist: Judge brought to notice, that the roof of the Court room was in a very leaky condition - and in the raining Season very dark, - and suggested that the existing tiled roof carried on timber rafters should be removed and a terraced roof substituted. On examination it was found that the rafters were old and much sapped, several being rotten - So the Dist: Judge's suggestion for terracing the whole roof was adopted. This Estimate provides for such a roof - Lately an Estimate was sent in for remodelling the roof of the Court room Dept: of the Collector's Cutcherry on the same lines. These alterations were sanctioned in G.O. 1155 - Fins dt 8.3.98 and 2677 W dt 14.10.98.

W. The Estimate may be sanctioned

H.E.S

Yes - 2 punkahs [illegible]

17.8.99

Sanctioned in G.O. 2109 W dt 10-8-99 (in press)

[P. W. 60. 250—5-9-98.]

In addition to removing the roof, the Dist: Surveyor wants a small room enclosed for the use of the Inside Canoe Clerk, and a Awning Wheeled the Terrace roof — to an Block it closed. These additions have been included in this Estimate.

From enquiries the Engr: has ascertained, that the existing foundations which rest on a Stratum of hard clay are quite strong enough to carry the Iron roof with safety.

Details of Construction.

For new Room

Foundn: 5ft deep of Concrete, Rubble Stone in lime mortar

Basement 1 foot - of Brickwork in lime mortar

Superstructure of all walls. Brick in lime mortar

Plastering Inside two coats of lime mortar

Flooring - Cut Stone on 6" of Concrete

Roofing - corrugated Iron Terrace

Roof timbers - Teakwood

Doors - panelled - Windows panelled - Ventilators pierced - Teakwork

Painting - Oil Colour

Girders - Wrought steel - Section sufficient - Loads - Dead Live 130 lbs - access to the roof not allowed.

Rates - detailed data accompanies Estimate - Rates are fair.

Plans and Estimate have been countersigned by the Dist: Surveyor and approved by me for the Govt: and Deptt:

Bamboo Trellis 4 ft: high along the boundaries, and wooden in the Verandahs, so as to keep out rain drift. This is a Customary arrangement and is objectionable, vide Vol I P.W. Code para 4 Chap. X.

It should be struck out from this Estimate in accordance with the rules.

H.C.

Vo
12.8.99

Approved
14.8.99