

Public Works (1899) Department.

G.O., No. 539
540

DATED ²⁶ June 1899

[Despatch Abstract.]

Periyar Project

Estimate of Rs 1450 for excavating a distributary and field channel from the head sluice in Athalai tank, 3rd Branch Channel — sanctioned — and a copy of these Pros: ordered to be forwarded to the Govt of India.

Periyar Project

Forwarding copy of Pros: sanctioning ~~and estimate~~ an estimate of Rs 1450 for excavating a distributary and

IRRIGATION.
ACCOUNT.

Government {1899} of Madras.
PUBLIC WORKS.

Recd.

Regd.

Enclosures

Spare copies

1899.

G.O., Nos. 539, 540 I., 26th June 1899.

JUNE.

Periyar Project

Forwarding copy of Proceedings sanctioning an estimate of Rs. 1,450 for excavating a distributary and field channel from the head sluice in Athalai tank, 3rd Branch channel.

GOVERNMENT OF MADRAS.
PUBLIC WORKS DEPARTMENT.

Irrigation.
Account.

READ—the following papers:—

From Lieutenant-Colonel O. V. BODDY, R.E., Superintending Engineer, VI Circle, to the Chief Engineer for Irrigation, dated Trichinopoly, 17th April 1899, No. 591 M.D.

I have the honour to forward, for sanction, an estimate amounting to Rs. 1,200, for excavating a distributary and field channel from the head sluice in Athalai tank 3rd reach, Periyár Project.

2. The channel is designed to irrigate 120 acres of land, of which 100 acres are waste sold in auction and 20 acres of dry land to be converted. The general fall of the ground is a little over 18 feet per mile; a 4-feet drop is proposed to be built at 1,400 feet, up to which point the channel will be maintained by Government.

3. The work is remunerative, the expected revenue per annum being Rs. 940 (*vide* statement enclosed).

4. The rates are fair and the estimate is recommended for sanction.

ENCLOSURES.

REPORT to accompany the estimate for excavating a distributary channel and constructing necessary masonry works from head sluice in Athalai tank.

Amount of estimate	...	...	...	...	...	...	...	Rs.
								1,200

An irrigation sluice is built in Athalai tank for irrigating the waste lands in Koilpappagudi village.

The present estimate provides for excavating a channel and constructing a drop of 4 feet in the same for irrigating the waste lands which have been sold in auction, and also for providing a pipe sluice at 100 feet below the head.

The channel will be maintained up to 1,400 feet.

The work will be carried out in accordance with the provisions of the standard specification current in the department.

MADURA,
21st March 1899.

(Signed) A. V. RAMALINGA AIYAR,
Asst. Engineer in charge of Periyár Works.

Estimate Form—Abstract—Classified.

Sub-head.	Names of works.	Amount of estimate for individual work.	Total of sub-heads.	Total for each canal or distributary.	Total of each main head.
1	2	3	4	5	6
	CAPITAL EXPENDITURE NOT CHARGED TO REVENUE.	RS.	RS.	RS.	RS.
	49. IRRIGATION.				
	Periyár Project Work.				
	Open Capital Account.				
	1. Works.				
	3. Distributaries.				
	III. Branch Channel.				
	Remunerative Work.				
	Excavating a distributary and field channel from Head Sluice in Athalai tank.				
Land ..	1. Compensation for land	128	128		
3. Works ..	2. Six-inch pipe sluice	80			
	3. Four-feet drop	360			
			390		
4. Earthwork ..	4. Cutting channel and banking, &c.	664			
			664		
5. Miscellaneous.	5. Demarcation stones	18			
			18		
	Total, I. Works			1,200	
	II. Establishment			247	
	III. Tools and plant			3	
	Total estimate				1,450

(Signed) O. V. BODDY, Lt.-Col., R.E.,
Superintending Engineer, VI Circle.
17th April 1899.

No. 107 I.

Note by the Chief Engineer for Irrigation.

The accompanying estimate, amounting to Rs. 1,200, submitted by the Superintending Engineer, VI Circle, provides for excavating a distributary and field channel from the head sluice in Athalai tank, 3rd Branch channel, Periyár project. The channel will be 3,500 feet in length, of which 1,400 feet will be maintained by Government. It will irrigate 100 acres of waste, and 20 acres of dry land, from which a revenue of Rs. 940 is anticipated. The estimate may be sanctioned.

(Signed) W. HUGHES,
Chief Engineer for Irrigation.
10th May 1899.

ORDER—No. 539 I., dated 26th June 1899.

The estimate of Rs. 1,200, or Rs. 1,450 including establishment and tools and plant, for excavating a distributary and field channel from the head sluice in Athalai tank, 3rd Branch channel, Periyár project, is sanctioned.

2. This sanction is registered as No. 28 I. of 1899–1900, and will expire on the 31st March 1900.

No. 539 I., 26TH JUNE 1899.

3. Ordered that a copy of these Proceedings be forwarded to the Government of India for information.

[Here enter No. 540 I., dated 26th June 1899.]

(True Extract.)

(Signed) W. HUGHES,
Joint Secy. to Government,
Irrigation Branch.

To the Chief Engineer for Irrigation.

„ Superintending Engineer, VI Circle, with five enclosures.
„ Examiner of Public Works Accounts.

ENDORSEMENT—No. 540 I., dated 26th June 1899.

Forwarded.

(By order.)

(Signed) W. HUGHES,
Joint Secy. to Government,
Irrigation Branch.

SUBJECT

Exd. T. K. Narayana Aiyangar.

Public Works (1899) Department.

CURRENT No. 4420

1079

From the Chief Engineer for Irrigation

Order

No. 1079

Dated 10 May 99

Received

Registered

Enclosures

Spare copies.

SUBJECT.

Excavation of a distributary
and field channel from
the head sluice in Athalai
tank 3rd Br chl. Periyar
Project. Estt of Rs 1200 for —
Note recommending for sanction
the —

FURTHER PAPER.

PUBLIC WORKS DEPARTMENT,
IRRIGATION BRANCH.

PROCEEDINGS OF THE MADRAS GOVERNMENT.

READ the following

on the Supp: Engineer O. F. Friele - N^o 591 M.D. of 17th April 1899.
classified abstract estimate amounting to Rs 1450.

no 10724108-58

Note by the Chief Engineer
for Irrigation

The accompanying estimate, amounting to Rs. 1200, submitted by the Supg. Engineer, 6.th Circle, provides for excavating a distributary and field channel from the head sluice in Athalai tank, 3rd Branch channel, Periyar project. The channel will be 3500 feet in length, of which 1400 feet will be maintained by Government. It will irrigate 100 acres of waste, and 20 acres of dry land, from which a revenue of Rs. 940 is

30.5.99 Wff.

anticipated. The estimate may be sanctioned.

2. The work may be classed as remunerative and will probably be completed by the 31st March 1900.

Order Hereon. No: 539 Lg 26-6-99

The estimate of Rs 1200, or Rs 1450 including establishment and tools and plant, for excavating a distributary and field channel from the head sluice in Athalai tank, 3rd Branch channel, Periyar project, is sanctioned.

2. This sanction is registered as No. 28 I of 1899-1900, and will expire on the 31st March 1900.

3. Ordered that a copy of these Proceedings be forwarded to the Government of India for information.

Endorsement No: 540 Lg 26-6-99
Forwarded.

10/5/99

10/5/99

To,
The Chief Engineer for Irrigation
" Supdt: do - & file
" Examiner of P.W. Accounts

14

Public Works (1899) Department.

CURRENT No. 41 m.d.

From

The Superintending Engineer

No. 591 m.d.

Order

Check to S.M.

21/4/99

Sanction

20/4/99

Dated 17 April 1899.

Received 19 — do —

Registered

Enclosures 5

Spare copies

SUBJECT.

Estimate has been checked and corrected.

15/5/99.

D.S.

Distributary & field Channel from the Head Sluice in Athalai tank 3rd Branch - Periyar Project. — Submitting for sanction an estimate of Rs 1200 for excavating a

15/4/99

BACK PAPERS.

FURTHER PAPERS.

38 Report to accompany the Estimate
for excavating a distributary channel
and constructing necessary masonry
works from head sluice in Attalai
tank.

Amount of Estimate Rs. 1200.

closures.
 Este file.
 Fracings
 Land Staff.
 Financial
 Staff.
 Staff to
 accompany Disty
 8 Total.

An irrigation sluice is built in Athalai tank for irrigating the waste lands in Koidappagum village.

The present estimate provides for excavating a channel and constructing a drop of 4 ft in the same for irrigating the waste lands which have been sold in auction. and also for providing a pipe sluice at 100 ft below the head.

The channel will be maintained
up to 1400 feet

The work will be carried out in accordance with the provisions of the standard specification current in the department.

A. V. Ramalingam
asstt Engineer
officer in charge of
Periyar works. 21/11/54
Madurai

17/41 m.d.

ESTIMATE FORM—ABSTRACT—CLASSIFIED.

Sub-head.	Names of Works.	Amount of Estimate for individual Work.	To Sub-head.	Total for each Canal or Distributary.	Total of each main head.	REMARKS.
1	2	3	4	5	6	7
	Capital expenditure not charged to Revenue.					3 Bn
	49- Irrigation					
	Pembar Project work					
	Open capital account					
	I- Works					
	3. Distributaries					
	III Branch Channel					
	Remunerative work.					
	Excavating a distributary & field channel from Head sluice in Thalaitank.					
2 Land-	Compensation for land.	128				
3- Works	2. Six inch pipe sluice	30				
	3- Four feet drop	360				
				390		
4- Earth work	4- Cutting channel + banking &c.	664				
				664		
5- Miscellaneos	5- Demarcation stones	18				
				18		
Total I Works				1200		
II Establishment				247		
III Tools & plant				13		
Total Estimate				1450.		

STATION

Dated

188

11/No 244
17-4-99 Supd Engineer,
6th circle.

06.8.2
4420/99

ESTIMATE FORM—ABSTRACT CLASSIFIED.

IRRIGATION.

Scinth CIRCLE.

DIVISION—*Madura*

DISTRICT—*Madura*

To accompany the Detailed Estimate No.

of 188 -8 . for * *Excavating distribu-*
tary & field channel from
Head sluice in Athalai tank
3rd Branch Channel

* Here enter the Name and Description of work in full.

OFFICE OF THE SUPERINTENDING ENGINEER,

6TH CIRCLE,

Trichinopoly,

17 April 189 *9*.

2/18.

From

W. O. V. Roady Esq.
Superintending Engineer,
6th Circle.

To

The Chief Engineer,

for Irrigation

APR. 1899

41 M.D.

SIR,

ENCLOSURES.

*1. with
post tea
etch map
and Section
survey Glass*

*3rd Branch
channel.*

I have the honor to forward
for sanction an estimate amounting
to Rs 1,200 for excavating a distribu-
-tary and field channel from the
head sluice in Athalai tank (3rd)
Reach. Periyar Project.

2. The channel is designed to
irrigate 120 acres of land of which
100 acres are waste sold in auction
and 20 acres of dry land to be
converted. The general fall of the
ground is a little over 18 feet per
mile, a 4 feet drop is proposed to
be built at 1400 feet, up to which
point the channel will be maintained
by Government.

3. The work is remunerative, the
expected revenue per annum being
£ 940 - Vide statement enclosed.

4. The rates are fair and the
estimate is recommended. *Instruction*

I have the honor to be
Sir,

Yours most obed^t Servant

J. V. Bodley, Esq. M.C. R.C.

Superintendent, or Clerk

[Signature]
13/10/55

5. p