

MADRAS RECORD OFFICE.

Government of Madras.

Revenue DEPARTMENT.

G.O. No.

1202

Press

~~Mis.~~

Dated

2 - 5 - 1868.

Not to be folded or roughly handled

14

*Proceedings of the Madras Government, Revenue Department,
2nd May 1868.*

No. 38. Read the following Proceedings of the Board of Revenue, dated 15th April 1868, No. 2,735.

Read the following letter from the Superintending Engineer, 1st Division, to the Secretary to Government, Public Works Department, dated Camp at Dowlaishweram, 12th March 1868, No. 273:—

1. I have the honor to submit for sanction the estimate, (amounting to Rupees 54,100,) for the road to be constructed in the Western Delta of the Godavery district, from the bank of the Vasishita Godavery at Kodair *via* Asunta, Martair Penumentra, and Munchilly to Uttelly.

2 Survey sheets.
7 Plans of masonry works.
1 Abstract Estimate.
1 Specification.

11 Despatched by banghy.

2. The total length of road provided for in this estimate is 19½ miles. The bank canal and Nursapur main canal will be crossed by bridges not obstructing the canal traffic, and provision is made for bridging the two main drainages, the Nukkla and Gostanuddy, as well as all irrigation channels and minor drainages.

3. Rupees 22,000 is entered (Item No. 213) in the Budget for 1863-69, for expenditure on this work.

ENCLOSURES Nos. 1 to 9.—Plans.

ENCLOSURE No. 10.—Estimate.

ENCLOSURE No. 11.—Specification.

Transferred to the Revenue Department.

(Signed) C. A. ORR. Colonel, R. E.,
Secretary to Government.

20th March 1868.

Referred to the Board of Revenue.

(Signed) W. HUDLESTON,
Secretary to Government.

21st March 1868.

1. The Board beg to submit, for the sanction of Government, the estimate, amounting to Rupees 54,100, for the road from Koderu to Attali, which is entered in the District Road Fund Budget for 1863-69 as Item No. 16.

2. This estimate should have been submitted by the Superintending Engineer to the Board, through the Collector of the Godavery district.

No. 39. ORDER THEREON, 2nd May 1868, No. 1,202.

Local Funds, No. 1.

Civil Works.

The estimate is sanctioned.

(True Extract.)

(Signed) W. HUDLESTON,
Secretary to Government.

To the Board of Revenue.

„ the Accountant General.

„ the Department Public Works.

Exd. S. T. Augustin.

Rev. 1863. Department.
Pro. of Govt. for May
No. 1298.

PROCEEDINGS OF THE BOARD OF REVENUE,

Dated 15th April 1863.
Depd 15-0
Rev 20 a.
E. H. O. O. O.

No. 2,735.

21/202

Submitting for sanction estimate amounting to
Rupees 54,100 for road from Koderu to Attali
in the Godavery district.

The estimate is correct.
W. H. H.

N. 38439

21/202

As per Rev. 1863. Department.
21/202