

MADRAS RECORD OFFICE.

Government of Madras.

Revenue DEPARTMENT.

G.O. No. 1226

Press
~~Mis.~~

Dated 4 — 5 — 18 68

Not to be folded or roughly handled

1226
Mis

*Proceedings of the Madras Government, Revenue Department,
4th May 1868.*

No. 89. . . Read the following Proceedings of the Madras Government in the
Public Works Department:—

Sanctioning Estimates, amounting to Rupees }
10,000, for constructing regulating sluices in } (Here enter 29th April 1868, No. 1,323.)
Trivellore Talook, Madras District.

No. 90. . . ORDER THEREON, 4th May 1868, No. 1,226.

Irrigation, No. 2.

Communicated to the Revenue Board.

(True Extract.)

(Signed) F. BRANDT,
Under Secretary to Government.

To the Board of Revenue, with Proceedings Public Works Department, No. 1,323.

Exd. S. T. Augustin.

*Proceedings of the Madras Government, Public Works Department,
29th April 1868.*

No. 584. Read the following letter from the Superintending Engineer, 4th Division, to the Secretary to Government, Public Works Department, dated Madras, 16th April 1868, No. 218:—

16 Plans.
16 Estimates.
1 Specification.

1. Constructing sluices to the Codunjavu river supply channel	650
2. Do. do. to the Penjerakum river supply channel	680
3. Do. do. Athigathur do.	660
4. Do. do. Agarum do.	530
5. Do. do. Casingoo Nullathoor do. ...	310
6. Do. do. Cadunbathoor do.	310
7. Do. do. Yagattoor do.	800
8. Do. do. Poongathoor do.	920
9. Do. do. Salary do.	800
10. Do. do. Peryacoopum do.	930
11. Do. do. Polyencoopum do.	310
12. Do. do. Poottoor do.	530
13. Do. do. Thunnecroolum do.	810
14. Do. do. Thodoor do.	730
15. Do. do. Theroovoor do.	550
16. Do. do. Aranveil do.	250
Sandries and superintendence	230
	10,000

1. With reference to the list of works for which estimates are awaited, which accompanied the G. O., No. 3,950, dated 20th December 1867, I have the honor to submit for sanction sixteen plans and estimates as per margin, for constructing regulating sluices to the heads of all channels taken off from the Kuam river between Kesaveram and Korattoor Anicuts, in the Trivellore Talook, Madras District.

2. These estimates, amounting in the aggregate to Rupees 10,000, have been approved of by the Collector, who has promised to send in the usual Ayacut particulars shortly.

3. The object in building these works is to prevent a waste of water from the Kuam river into the different tanks while giving each its fair share, and to admit of a larger supply reaching the Chembrambaukum tank in the Poonamallee division of the Sydapet talook.

4. The sluices are to be built of brick-in-chunam, with dressed granite cross and grooved stones to receive the teakwood shutters.

5. These works were the subject of remarks in Mr. Fraser's report on the Chembrambaukum Tank project, and are provided for in the current year's Budget Part II, with an allotment of Rupees 10,000 forming item No. 155.

No. 585. ORDER THEREON, 29th April 1868, No. 1,323.

IRRIGATION, No. 25.

1. The estimates submitted with this letter amounting in the aggregate to Rupees 10,000 are sanctioned for execution from the funds allotted for the works in Part II of the Budget estimate of the current official year.

2. Under the Orders of the 14th November 1867, No. 3,512, these estimates should have been laid before Government through the Chief Engineer for Irrigation.

(True Extract.)

[Signature]
Colonel R. E.
Secretary to Government.

To the Superintending Engineer, 4th Division
Accountant General.
Controller of Public Works Accounts
Revenue Department
Justin.

December 1868 Dec
No. of amt for chas

Proceeding of the
Court J. H. O. H.

Dated 29th 3rd 4th
Receives 30th 1868
87-1323.

Sanctioning salaries
amount to \$10,000 for
conducting regulating
clauses in the
Schools otherwise
directed

With Order

Common, with
Receives 1868

189490

14 Ohio State

189490 11/11/1868