

MADRAS RECORD OFFICE.

Government of Madras.

Revenue DEPARTMENT.

G.O. No.

1612

Press

~~Mis.~~

Dated

19-5-1868.

Not to be folded or roughly handled

*Proceedings of the Madras Government, Revenue Department,
19th May 1868.*

No. 471. Read the following Proceedings of the Madras Government in the
Public Works Department:—

Sanctioning revised estimate of Rupees 1,600
for a scouring-sluice and ring-channel near
the Cocanada lock on the Junction Canal, in
Godavery district, also a further sum of Ru-
pees 1,007 for completion of the work. } (Here enter 15th May 1868, No. 1,556.)

No. 472. ORDER THEREON, 19th May 1868, No. 1,412.

Irrigation, No. 15.

Communicated to the Revenue Board.

(True Extract.)

(Signed) H. SEWELL,
Acting Under Secretary to Government.

To the Board of Revenue, with Proceedings Public Works Department, No. 1,556.

Edw. S. T. Augustin.

*Proceedings of the Madras Government, Public Works Department,
15th May 1868.*

No. 415. Read the following letter from the Executive Engineer in charge of 1st Division, to the Secretary to Government, Public Works Department, dated Dowlaishweram, 30th April 1868, No. 26:—

1. I have the honor to submit for sanction a revised estimate, amounting to Rupees 1,600, for a scouring sluice, &c., for which the original estimate, amounting to Rupees 1,000, was sanctioned in G. O., No. 3,082, of 4th October 1867.

1 Estimate.
1 Copy of letter from Mr. Sage.
1 Comparative Statement.

2. Owing to the sandy nature of the soil where the sluice is proposed to be built, it has been found necessary to revet the floor and side-slopes of channels with rough-stone, as reported by the Executive Engineer of No. 1 Range, in his letter No. 127, of 27th April 1868, a copy of which is enclosed.

3. This extra work is estimated to cost Rupees 520, to which a small sum is added on account of the pay of the work establishment, which has hitherto been treated as "Petty Establishment."

4. No provision is made in my statement of Incomplete Works for the completion of the work under reference, because the unexpended balance of the original estimate was only Rupees 407, and I have now the honor to request that a sum of Rupees (600 + 407) 1,007 may be granted for the completion of the work in question.


5. The usual comparative statement is herewith forwarded.

No. 416. ORDER THEREON, 15th May 1868, No. 1,556.

IRRIGATION, No. 25.

Under the explanation afforded in this letter, the Government sanction the revised estimate of Rupees 1,600 for a scouring sluice and ring-channel near the Cocanada lock on the Junction Canal in the Godavery District, and they resolve to grant a sum of Rupees 1,007 for the completion of the work from the Reserve under "Agricultural."

(True Extract.)


Colonel, R. E.,
Secretary to Government.

To the Superintending Engineer, 1st Division, with one Letter and one comparative Statement.
" Controller of Public Works Accounts.
" Accountant General.
" Revenue Department.

Exl. S. T. Augustin.

Permanence 1868: 6/14.
 Saw of Gault for 1692.

Proceedings of the
Genl. & J. D. Webb

Noted 15th of May.
Received 16th of 1868.
J. 1836-

Dec 14/12 - 19 May

With Order

Estimated of \$1600

for a second time
being changed over

the Governor back
on the Union

Canada's Forestry

It also a further notice
at No 1007 West Court & Co. have

of the book

88-1412

Committee
Revenue Board

19. May/68

1/2 Cakes of Mincion of Blue with On On 222 or 1550 282414221

Chicago Aug 2