

MADRAS RECORD OFFICE.

Government of Madras.

Revenue DEPARTMENT.

G.O. No. 214

Press
~~Mis.~~

Dated 27—1—1868.

Not to be folded or roughly handled

*Proceedings of the Madras Government, Revenue Department,
27th January 1868.*

No. 430. Read the following Proceedings of the Madras Government in the
Public Works Department:—

Passing orders on letter from Superintend-
ing Engineer, 5th Division, submitting esti-
mate for masonry works to be built in the } (Here enter 20th January 1868, No. 178.)
Wallajah Channel, in Cuddalore Talook.

No. 431. ORDER THEREON, 27th January 1868, No. 214.

Irrigation, No. 8.

Communicated to the Revenue Board.

(True Extract.)

(Signed) F. BRANDT,
Under Secretary to Government.

To the Board of Revenue, with Proceedings Public Works Department, No. 178.

Exd. F. R. Bantleman.

*Proceedings of the Madras Government, Public Works Department,
20th January 1868.*

No. 344. Read the following letter from the Superintending Engineer, 5th Division, to the Chief Engineer for Irrigation Works and Joint Secretary to Government, Department Public Works, dated Cuddalore, 21st December 1867, No. 192:—

1. I have the honor to submit, for the sanction of Government, an estimate of Rupees 2,850, accompanied by plans and specifications, for masonry works to be built in the Wallajah Channel, in the Cuddalore Talook.
 - 11 Estimates.
 - 1 Abstract Estimate.
 - 2 Plans.
 - 2 Specifications.

2. The channel is cut from the Pooniar, and has branches to thirteen tanks, the last of which is the large tank of Trivady about fourteen miles west of Cuddalore. The works consist of a bridge of one arch of 18 feet to be built near Kurumboor, where the channel is difficult to cross, and ten head sluices for the branch channels with dams or pavements across the main channel just below the branches.

3. The object of the works is to secure a fair division of the water, and to take away the excuse for putting banks across the main channel, which prevent the water getting down to the tanks at the lower end of the channel. The sluices are to be covered over, in order that there may be a continuous roadway along the channel embankment. The estimates have been approved of by the Collector, and the work has been entered in my Budget for the ensuing year. The revenue dependent on the channel is about 8,063 Rupees.

No. 345. ORDER THEREON, 20th January 1868, No. 178.

IRRIGATION, No. 17.


* Rupees 1,530.

different interests under the Wallajah Channel in the South Arcot District, and of a bridge† of 18 feet span across the channel, at the village of Kurumboor.

† Rupees 1,320.

2. The Government entirely approve of the proposed works, but the Superintending Engineer will report on the necessity for including the cost of the proposed bridge as expenditure under the head "Agricultural." If the channel is an old one, it should properly be a charge on Local Funds, under the head "Communications."

(True Extract.)



Colonel, R. E.,

Secretary to Government.

To the Superintending Engineer, 5th Division.

- „ Accountant General.
- „ Controllor of Public Works Accounts.
- „ Revenue Department.

Exd. F. R. Bantleman.

80-214

Communicated to the
Revenue Board.

86-178

10
4368401.

Passing notes
on letter from Capt^l Eng^s
5th Divⁿ submitting Esti-
mate for improvements
needed & be built in
the Malabar Channel
in Cuddalore Harbour.
1820/14. 20th June
Attest order &

14 Caprii veldte 3000 Rente in the Gro Oor Oor 1780 Doughty 27

29/2/88