M.R.O. 1—39,000—16 10-29.

MADRAS RECORD OFFICE.

Government of Madras.

Revenue **DEPARTMENT.**

G.O. No. 2491 Press ~~Mis.~~

411-12. Dated 28—9— M 1868.

Not to be folded or roughly handled

Proceedings of the Madras Government, Revenue Department, 28th September 1868.

No. 411. Read the following Proceedings of the Madras Government in the Public Works Department:—

Communicating sanction of the supplemental estimate for additional improvements to the Turanjeccoopum Tank in the North Arcot District. } (Here enter 19th September 1868, No. 2,971.)

No. 412. ORDER THEREON, 28th September 1868, No. 2,491.

Irrigation, No. 17. Communicated to the Revenue Board.

(True Extract.)

(Signed) H. SEWELL,
Acting Under Secretary to Government.

To the Board of Revenue, with Proceedings Public Works Department, No. 2,971.

Exd. F. R. Bantleman.

No. 364. Read the following letter from the Superintending Engineer, 4th Division, to the Chief Engineer for Irrigation and Joint Secretary to Government, Public Works Department, dated Madras, 10th September 1868, No. 2,875 :—

1 Estimate.

1. I have the honor to report that I inspected the Turanjeecoopum tank in the Polur Talook, Polur Range, North Arcot District, recently restored at a cost of Rupees 5,512 on an estimate of Rupees 5,300, sanctioned in G. O., No. 588, dated 27th February 1867, on the 31st July 1868, and was generally well pleased with the work done.

2. It occurred to me, however, that the tank would be rendered more secure by the execution to it of the following works, viz., raising the stone revetment three feet; turfing the face of the earth bank on the inside above the stone facing; gravelling the top of the bund, and building a rear revetment wall at one point where the surplus channel water will act on the rear of the bund, and I accordingly directed the preparation of a supplemental estimate providing for these works.

* Rupees 620.

3. I have now the honor of enclosing the estimate,* and of requesting that it may be sanctioned for early execution. I shall endeavour to provide the funds required from savings later in the year.

4. The supplemental demand is about $11\frac{3}{4}$ per cent. on the original sanctioned amount, but the estimate had already been exceeded by 212 Rupees.

The estimate amounting to Rupees 620, submitted with the foregoing letter, is recommended for sanction.

(Signed) J. C. ANDERSON, Colonel, R. E.,
Chief Engineer for Irrigation.

FORT ST. GEORGE,
12th September 1868.

To the Secretary to Government, Public Works Department.

No. 365. ORDER THEREON, 19th September 1868, No. 2,971.

IRRIGATION, No. 18.

The Government sanction the supplemental estimate of Rupees 620, submitted with this letter, for certain additional improvements to the Turanjeecoopum tank in the North Arcot District, which sum together with the excess of Rupees 212 reported to have been incurred over the original estimate of Rupees 5,300 will raise the cost of the restoration of the tank to Rupees 6,132.

(True Extract.)

Colonel, R. E.,
Secretary to Government.

To the Superintending Engineer, 4th Division.
" Accountant General.
" Controller of Public Works Accounts.
" Chief Engineer for Irrigation.
" Revenue Department.

Ext. S. T. Augustin.

Govt. of [1868] Madras.

PUBLIC WORKS.

To

THE SUPERINTENDING ENGINEER,

4th DIVISION.

&c., &c., &c.

Dated September, 1868.

Read. Rec.

G. O., 19th September 1868, No. 2,971.

SEPTEMBER.

Nos. 2971-3075

Pennycooputa Tank.—The supplemental estimate (Rupees 629-12-0) for additional improvements to — in the North Arcot District, sanctioned.

3/

B-2491.

Comm^d to the Revenue Board.

28th Sept^r/68

14 Copies Forwarded Rec^d Records. Pro MDC B 2971 Dated 29