M.R.O. 1—38,000—16-10-29.

MADRAS RECORD OFFICE.

Government of Madras.

Revenue DEPARTMENT.

G.O. No. 1367 Press Nil.

337—338

Dated 14 May 1869

Not to be folded or roughly handled

Proceedings of the Madras Government, Revenue Department, 14th May 1869.

No. 337. Read the following Proceedings of the Madras Government in the Public Works Department :—

Sanctioning Rupees 600 from the Reserve for completing the improvements to the Colinjevady Anicut and channel in the Caroor Range of the Coimbatore District. } (Here enter 8th May 1869, No. 1,500.)

No. 338. ORDER THEREON, 14th May 1869, No. 1,347.

Irrigation, No. 6. COMMUNICATED to the Revenue Board.

(True Extract.)

(Signed) H. WELLESLEY,
Acting Under-Secretary to Government.

To the Board of Revenue, with Proceedings Public Works Department, No. 1,500.

Exd. E. C. Shunker.

Copy of (1869) Collrate's
REVENUE.

To

THE BOARD OF REVENUE.

Dated May, 14th.

Read.

G. O., 14th May 1869, No. 1,347.

FAY.

Nos. 337-339.

Colinjevady Anicut and channel in Coimbatore District—Order sanctioning the completion of improvements to them, communicated to Revenue Board.

Proceedings of the Madras Government, Public Works Department, 8th May 1869.

No. 148. Read the following letter from the Superintending Engineer, 7th Division, to the Secretary to Government, Public Works Department, dated Coonoor, 21st April 1869, No. 16 :—

1. I have the honour to submit, herewith, the supplemental estimate* for improvements to the Colinjevady anicut and channel, called for in paragraph 12 of G. O., No. 1,715, of 29th May 1868, together with survey, comparative statement, and Range Officer's report illustrative of the same. I inspected the work in July 1868, and was satisfied with all but a portion near the spot marked B., the section of which struck me as very inferior to that generally prevalent throughout the rest of the work, and to which it has subsequently been altered, according to my orders on the spot.

* Rupees 2,275.

1 Estimate No. 7 of 1869-70.
1 Survey.
1 Comparative Statement.
1 Report.

2. Owing, presumedly, to so much of Mr. Wiffen's time having been taken up with the Nerinjeepett Projects and change of Range Officers, some of the channel work remained unexecuted at the close of 1868-69, so that I have to make a demand of Rupees 600 on this account on the Reserve of 1869-70.

No. 149. ORDER THEREON, 8th May 1869, No. 1,500.

IRRIGATION, No. 14.

1. In Proceedings No. 3,824, dated 1st December 1866, the Government sanctioned estimates, aggregating Rupees 17,696, for certain improvements to the Colinjevady anicut and channel in the Caroor Range of the Coimbatore District. The Superintending Engineer now reports that owing to a portion of the island which separates the two sections of the anicut having been washed away, and to part of the western section having sunk, it has been found necessary to lengthen the front retaining wall and to rebuild a portion of it. These additional works, with the increased rate paid for kunkur, which had to be blasted, have raised the cost of the improvements to Rupees 19,971, or Rupees 2,275 in excess of the original estimate.

2. The value of work remaining unexecuted at the close of the past official year is stated to be Rupees 600, which the Government resolve to allot from the Reserve under "Agricultural."

(True Extract.)

Colonel, R. E.,
Secretary to Government.

To the Superintending Engineer, 7th Division.
,, Chief Engineer for Irrigation.
,, Controller of Public Works Accounts.
,, Accountant General.
,, Revenue Department.

Exd. S. T. Augustin.

F. 1347
Comm to the
Revenue Board.

14 May 69.

Revenue 1869 Oct.
No. 1505.

Govt. of [1869] Madras.

PUBLIC WORKS.

To

THE SUPERINTENDING ENGINEER,

7TH DIVISION.

&c., &c., &c.

Dated May, 8th.

Recd. 11th. —— Encl.

G. O., 8th May 1869, No. 1,500.

MAY.

Nos. 148-149

Con

No 1347-16 Nov

Colinjevady Anicut and Channel.—Rupees 600 sanctioned from the Reserve for completing the improvements to the Colinjevady anicut and channel in the Caroor Range of the Coimbatore District.

With Order 2d