M.R.O. 1—38,060—16-10-29.

MADRAS RECORD OFFICE.

Government of Madras.

Revenue DEPARTMENT.

G.O. No. 1559 Press Mis.
66-67
Dated 2 nd June 1869

Not to be folded or roughly handled

Proceedings of the Madras Government, Revenue Department, 2nd June 1869.

No. 66. Read the following Proceedings of the Madras Government in th Public Works Department :—

Sanctioning estimate of Rupees 1,380 for a surplus sluice in the Thimmachipuram limits in the north bank of the Kattoovari, in the Trichinopoly District. } (Here enter 27th May 1869, No. 1,730.)

No. 67. ORDER THEREON, 2nd June 1869, No. 1,559.

Irrigation, No. 1. COMMUNICATED to the Board of Revenue

(True Extract.)

(Signed) H. WELLESLEY,
Acting Under-Secretary to Government.

To the Board of Revenue, with Proceedings Public Works Do partment, No. 1,730.

Exd. E. C. Shunker.

Proceedings of the Madras, Government, Public Works Department 27th May 1869.

No. 605. Read the following letter from the Superintending Engineer, 6th Division, to the Secretary to Government, Public Works Department, dated Tanjore, 13th May 1869, No. 204:—

I HAVE the honour to enclose, for the sanction of Government, an estimate for reconstructing a surplus sluice in the Thimmachipuram limits in the north bank of the Katoovari, in the Trichinopoly District. This sluice drains about one square mile of land between the Cauvery and the Katoovari. The Katoovari, as the name implies, is a jungle stream which drains a very large area of country, and is constantly subject to breaches; there are numerous dams across it for the purpose of irrigation, and the discharge of flood waters is therefore much impeded.

1 Plan.
1 Abstract Estimate, Rupees 1,380.

2. The original sluice, which was a very old work, was destroyed by a breach in the north bank above the sluice, and the sluice being incapable of discharging the extra water thus thrown upon it, the water breached the bank in the neighbourhood of the sluice, and a deep scour was formed round the wing, which completely undermined the entire work and destroyed it in June last. It is not possible to make use of any of the original work.

3. This work was entered in the list of works to be provided for from the Reserve forwarded on the 30th April, No. 146.

No. 606. ORDER THEREON, 27th May 1869, No. 1,730.

IRRIGATION, No. 32.

SANCTIONED.

2. The outlay on the work will be charged to the Reserve under "Agricultural."

(True Extract.)

Colonel, R. E.,
Secretary to Government.

To the Superintending Engineer, 6th Division.
,, Controller of Public Works Accounts.
,, Accountant-General.
,, Revenue Department.
,, Chief Engineer for Irrigation.

Exd. S. T. Augustin.

Copy of Letter from Board of Revenue,
To
THE BOARD OF REVENUE.
Dated June, 2nd.
Recd. 4th
G. O. 2nd June 1869, No. 1,559.
JUDL.
Sluice in the north bank of the Katoovari in Trichinopoly District.—Order sanctioning the outlay on this work, communicated to Board of Revenue.

Revenue Despatch

No. 1766.

Govt. of [1869] Madras.

PUBLIC WORKS.

To

THE SUPERINTENDING ENGINEER,

6th Division.

&c., &c., &c

Dated May, 27th.

Recd. 31st. — Inst.

G. O., 27th May 1869. No. 1,709.

MAY.

Nos. 605-606

Surplus Sluice.—Estimate of Rupees 1,380 for a surplus sluice in the Thimmachipuram limits in the north bank of the Katoovari in the Trichinopoly District, sanctioned

With Order

No. 1559 dt 2d June 69