

(1) Number of pages 4

(2) Date of repair 6.8.1965

(3) Initials of the Referencer _____

MADRAS RECORD OFFICE

Government of Madras

Revenue DEPARTMENT

G.O. No.	104	Press
B.P. No.		Mis.
Dated	15 - 4. 1872	195

Not to be folded or roughly handled

104
4/4

*Proceedings of the Madras Government, Financial Department,
4th April 1872,*

No. 35. Read the following Proceedings of the Board of Revenue, dated 5th March 1872, No. 1672 (Miscellaneous):—

Read the following letter from the President of the Local Fund Board, Northern Circle, to the Acting Secretary to the Board of Revenue, dated Coimbatore, 9th September 1871, No. 3:—

With reference to Clause 10, Rule XXX., of the Local Fund Rules, I have the honour to forward an estimate, amounting to Rupees 8,550, for the construction of a railway feeder from Chinnimalay to Perindoray Railway Station, together with a survey of the proposed road, as well as a plan of culverts, and to request that the sanction of Government may be obtained for the same.

2. The necessity for the work in question is explained in the accompanying copy of letter from the Acting Superintending Engineer, 7th Division, dated 6th instant, No. 20. A sum of Rupees 2,500 has been provided for it in the Local Fund Budget of the current official year.—*Vide* item No. 2, in Enclosure II.-A, Part I.

From the President of the Local Fund Board, Coimbatore, to the Secretary to the Board of Revenue, dated Coimbatore, 17th January 1872, No. 3.

With reference to your Official Memorandum, No. 1351, of 12th October 1871, I have the honour to forward an original communication from the Superintending Engineer, 7th Division, from which it will appear that the heavy compensation on the proposed Chinnimalay and Perindoray Road cannot be avoided, about 32 Acres of land along the old road will be available for cultivation, and that the avenue trees might be sold.

The estimate, amounting to Rupees 8,550, for the construction of a road from Chinnimalay to Perindoray Railway Station (length six miles) is submitted for the sanction of Government.

2. The estimate is made up of the following items:—

	RS.
1. Earthwork	2,412
2. Gravelling	1,659
3. Clearing jungle	25
4. Blasting rock	250
5. Masonry works	2,011
6. Rough stone work, dry	263
7. Sundries at about 5 per cent.	330
8. Compensation for 40 Acres of land, at 40 Rupees per acre	1,600
Total ...	8,550

3. The work is provided for in Part I. of the current year's revised Road Fund Budget of the Northern Circle.

4. The road in question is a most useful railway feeder, connecting many important villages with the Perindoray Station.

5. The delay in the submission of the estimate was caused by a reference made to the President regarding the heavy charge for compensation, amounting

*Proceedings of the Madras Government, Financial Department,
4th April 1872.*

to about 19 per cent. of the whole cost of the road. It will be observed from the President's reply, recorded at the head of these Proceedings, that it is not possible to reduce the charge.

(True Copies and Extract.)

(Signed) J. GROSE,
Secretary.

No. 36.

ORDER THEREON, 4th April 1872, No. 413.

Sanctioned.

(True Extract.)

[Signature]

Officiating Chief Secretary.

To the Board of Revenue, with enclosures returned.
Revenue Department.
.. Public Works ..
.. Accountant-General.

Exd. J. Wright.

10/2/1872

Order

Revenue Dept.

7-12-61

Obbt. of 18723 Mndras.

FINANCIAL.

To

THE BOARD OF REVENUE,

&c.,

&c.,

&c.

Dated April, 4th.

Recd.

12

Ref.

G. O., 4th April 1872, No. 413.

APRIL.

Nos. 35-36.

Sanctioning the estimate for the construction
a road from Chinnimalay to Perindoray Railway
Station in the Coimbatore Northern Circle.

RECORDED.

15-4-72