

1203

Proceedings of the Madras Government, Revenue Department,
28th October 1873.

No. 303. Read the following Proceedings of the Court of Wards, dated 15th October 1873, No. 2,111 :—

Read the following letter from W. F. GRAHAME, Esq., Acting Principal Assistant Collector, to C. G. MASTER, Esq., Collector of Ganjam, dated Chicacole, 3rd September 1873, No. 249 :—

WITH reference to paragraph 2 of your docket No. 1,663, dated 25th July 1873, I have the honour to forward, herewith, a copy of the report received from the Assistant Engineer in charge of No. 2 Range, on paragraph 11 of the Proceedings of the Court of Wards, No. 821, dated 17th May 1873, regarding the Koramagudda Calingula, in the Purla Kimedy Estate.

From Ensign J. LEVER, Assistant Engineer, No. 2 Range, to W. F. GRAHAME, Esq., Acting Principal Assistant Collector of Ganjam, dated Chicacole, 28th August 1873, No. 294.

WITH reference to your letter No. 225, dated 12th instant, I have the honour to inform you that I have inspected the calingula, therein alluded to on the 21st July last. I made enquiries from Maistry V. Narasiah what the materials were collected at site for; he told me they were for the repairs of the calingula. I immediately wrote to the Overseer in charge of Kimedy Sub-division, ordering him not to attempt to repair the ruined calingula, as it was in a state beyond repairs. I have referred the ruined work to the District Engineer, who also inspected it on the 8th instant. The District Engineer ordered the ruined work to be removed after the rains, if not washed away entirely. The design of the work was by Supervisor Toy Ramiah Naidu, and was a bad one, as the whole work was constructed within the nullah instead of inserting wing walls in its banks and allowing the full width of waterway over the calingula; but, however, it was impossible that the work would stand, as there were no foundations. Supervisor Toy Ramiah Naidu is in fault for the design and bad work, as I believe he partly superintended the work, which was never completed. The original estimate was for Rupees 1,451, and the expenditure Rupees 1,444-7-3. I see from Progress Reports that an emergent estimate for Rupees 420 was sanctioned. The District Engineer ordered me to inspect the nullah higher up, after the rains, and see if a better project could be obtained.

(True Copy.)

(Signed) W. F. GRAHAME,
Acting Principal Assistant Collector.

No. 2,161.

SUBMITTED to the Court of Wards with reference to paragraph 11 of their Proceedings, dated 17th May 1873, No. 821.

CHETTERPORE,
10th September 1873.

(Signed) C. J. MASTER,
Collector.

*Proceedings of the Madras Government, Revenue Department,
23rd October 1873.*

THE Court regret to find that the faulty construction of the Koramagudda Calingula has entailed needless expense upon the Purla Kimeddy Estate.

2. They submit the Assistant Engineer's letter to Government in continuation of their Proceedings, dated 20th September 1873, No. 1,889.

3. It appears that not only was the design faulty but the work was also built without foundations.

No. 304.

ORDER THEREON, 28th October 1873, No. 1,203.

Miscellaneous.

TRANSFERRED to the Department
Public Works, in continuation of former
papers.

(True Extract.)

(Signed) R. A. DALYELL,
Acting Secretary to Government.

Pw 1873 Sept
No 3385

1873.

Court of Wards,
MADRAS.

PROCEEDINGS, 15TH OCTOBER 1873, No. 2,111.

Sup 22 Oct 173

Encl.

G.O. 1203 - 28 Oct

Received 24 Oct 73

OCTOBER.

No. 2,111.

Purla Kimedy Estate — in Ganjam District, now under charge of Court of Wards. — Report of Assistant Engineer, No. 2 Range, Ganjam, on ruined state of Koramagudda Calingula in — which was designed by Supervisor Ramiah, submitted to Government.

Under Secy
10th Oct 73

Pw. Sept. 1873
Court of Wards

28 Oct 73

No 1203