M.R.O. 1—20,002—12-3-65.

(1) Number of Pages 4

(2) Date of repair 6-8-68

(3) Initials of the Referencer

MADRAS RECORD OFFICE

GOVERNMENT OF MADRAS

Revenue DEPARTMENT

G.O. No. / B.P. No.	1524	Press / Mis.
Dated	21-7-1875	196 .

Not to be folded or roughly handled

No. 88. Read the following:—

No. 6

MEMORANDUM.

THE following Estimate has been submitted by the District Engineer, Cuddapah:—Repairing Ramapooram Pundivari spring channel Rupees 180.

				Assessment.
Ayacut area	Government, Acres	11	... ...	Rs. 71
	Inam, do.	4	... ...	„ 43
Average Revenue	... ...		... ...	„ 41
Highest do.	... ...		... ...	„ 48

Date of last repairs 1870-71. Cost Rupees 194. Under ordinary circumstances it is clear that with the maintenance of a work of this kind Government should have nothing to do, and indeed in the orders as per margin it has been decided that the clearance of spring channels should be carried out by those irrigating under them. In the present case, in consideration of the unusual character of the floods which so greatly injured the channel, it may be well to help the ryots by clearing its upper part as provided for in the estimate, although it will be observed that the cost of maintenance in six years will thus amount to Rupees 374, or more than nine times the average revenue.

G. O., No. 3,019, dated 23rd October 1874.

OOTACAMUND, 17*th June* 1875. (Signed) JOHN MULLINS, Lieut.-Colonel, R.E., *Officiating Chief Engineer.*

EMERGENT ABSTRACT ESTIMATE.

CUDDAPAH DISTRICT, MADANAPULLY RANGE, VOILPAUD TALUQ.

WORK.—*Putting a bund by the side of Vunkah with revetment and also clearing the silt from the spring head and channel of Ramapooram Pundivari Calva.*

Quantity.	Description of work.	Per.	Rate.	Amount.	Total.
			RS. A. P.	RS. A. P	RS. A. P.
189¾	Cubic yards of earthwork for placing bund across the channel	C. yds.	0 1 3	14 13 2	
43¹¹⁄₁₇	Cubic yards of rough stone revetment to the bund..	Do.	0 12 0	32 9 4	
2,004	Cubic yards of excavating the silt from the channel	Do.	0 1 0	125 4 0	
	Total ..	..	..	172 10 6	
	Sundries and Superintendence at 5 per cent.	..	..	7 5 6	
	Total amount of this estimate	..	..	..	180 0 0

I do hereby certify that everything that is necessary to carry out the work is provided for in the estimate, and that no supplemental estimate will be required hereafter.

MADANAPULLY, 30*th April* 1875. (Signed) W. M. MONTSERRAT, *Assistant Engineer.*

(„) A. S. MOBERLY, Colonel, R.E., *District Engineer.*

Proceedings of the Madras Gov nment, Public Works Department,
3rd ly 1875.

No. 89. ORDER THEREON, 3r uly 1875, No. 1,874.

IRRIGATION, No. 8.

Account.

UNDER the special circumstances noticed the estimate of Rupees 180 for clearing the Ramapooram Pundivari spring channel is sanctioned.

(Tru Extract.)

Lt. Collett.

Major, R.E.,

Offg. Joint Secretary to Government.

To the District Engineer, Cuddapah.
,, Chief Engineer for Irrigation.
,, Controller of Public Works Account
,, Revenue Department.

Exd. S. T. Austin.

Spare Copies will follow

Rev: 1875: Dept
No 2683

Govt. of {1875} Madras.

PUBLIC WORKS.

To

THE DISTRICT ENGINEER,

CUDDAPAH,

2 Part

&c., &c., &c.

Dated July 3rd.

Issued

Recd. 12th *Encl.*

G. O., 3rd July 1875, No. 1,874.

JULY

Nos. 88-89

Ramapcorum Pundivari Spring Channel, Cuddapah District.—The estimate of Rs. 180 for clearing the —, sanctioned.

No 1524 Comm^r to the Board of Revenue

21st July/75.

12 Govt Orders dated 2d July