M.R.O. 1—20,002—12-8-65.

(1) Number of Pages 4

(2) Date of repair 7-8-68

(3) Initials of the Referencer [illegible]

MADRAS RECORD OFFICE

GOVERNMENT OF MADRAS

Revenue DEPARTMENT

G.O. No. / B.P. No.	1537	Press / Mis.
Dated	22-7-1875	196 .

Not to be folded or roughly handled

No. 292. Read the following letter from J. O'SHAUGHNESSY, Esq., Acting District Engineer, Tanjore, to Lieutenant-Colonel J. MULLINS, R.E., Officiating Secretary to Government, Public Works Department, dated Tanjore, 10th June 1875, No. 949 :—

WITH reference to G. O., No. 2,836, dated 6th October 1874, I have the honor to submit, herewith, a plan, specification, and estimate, amounting to Rupees 870, for an additional room for the general duty Deputy Collector's Office at Tanjore.

2. The plan and estimate have been countersigned by the Collector in token of his approval.

TANJORE DISTRICT.

No. 1 OR TANJORE RANGE.

TANJORE TALUQ.

ABSTRACT ESTIMATE No. —— of 1875-76.

WORK.—*Providing additional accommodation for Clerks and Records in the Office of the Deputy Collector on general duties, Tanjore.*

Quantity.	Particulars of Work.	Rate.			Per	Amount.		
		RS.	A.	P.		RS.	A.	P.
243¾	Cubic feet of concrete	0	2	0	Cubic feet..	30	7	6
1,859⅔	Do. of brick-in-chunam	0	2	6	Do. ..	290	9	0
15·28⅛	Square feet of plastering with two coats chunam	2	8	0	Square ..	38	3	6
882	Do. of flooring with square tiles ..	8	0	0	Do. ..	70	8	11
19¼	Cubic yards of terracing with terrace bricks (6″ × 3″ × 1″) on edge as per specification	6	0	0	Cubic yards.	118	10	8
48¾	Cubic feet of teakwood wrought and put up	3	8	0	Cubic feet ..	170	10	0
1	Teakwood pannelled door 4′ × 8′ with frames, hinges, bolts, and lock, &c., complete	32	0	0	Each ..	32	0	0
3	Batten windows 3½′ × 4½′ including frames with iron rods, shutter, complete with English bolts	16	0	0	Do. ..	48	0	0
8	Pot ventilators as per specification ..	3	0	0	Do. ..	24	0	0
292½	Cubic feet of demolishing	0	0	3	Cubic feet..	4	9	0
	Excavating foundation and filling in	....			....	10	0	0
	Sundries and Contingencies	....			....	32	5	5
	Total Estimate ..	....			....	870	0	0

TANJORE,
28th April 1875.

(Signed) R. A. ROBERTS, Lieut.-Colonel, R.E.,
Superintending Engineer, Tanjore.

(Signed) H. S. THOMAS,
Collector.

Proceedings of the Madras Government, Public Works Department,
10th July 1875.

No. 293. ORDER THEREON, 10th July 1875, No. 1,952.

CIVIL WORKS, No. 21.

SANCTIONED.

2. No funds are available at present.

(True Extract.)

Major, R.E.,
Offg. Joint Secretary to Government.

To the District Engineer, Tanjore.
„ Controller of Public Works Account
„ Revenue Department.

Rev: 1875 Dept
No. 2837.

Govt. of {1875} Madras.

PUBLIC WORKS.

To

THE DISTRICT ENGINEER,

TANJORE.

&c., &c., &c.

2 Sheets

Dated July 10th.

Issued

Read. 21st

Encl.

G. O., 10th July 1875, No. 1,952.

Rec'd

JULY.

Nos. 292-293

14 Folio Ogan Dept Revenue 29 July

Additional room for the general duty Deputy Collector's Office at Tanjore.—Plan and estimate of Rupees 870 for—, sanctioned with remarks.

No 1537
Comm.r to the
Board of Revenue
22 July 75.