

(1) Number of Pages 4(2) Date of repair 13 9-68(3) Initials of the Referencer 268**MADRAS RECORD OFFICE****GOVERNMENT OF MADRAS**Revenue**DEPARTMENT**

G.O. No.

2086

Press

B.P. No.

Mis.

Dated

7-10-1885196*Not to be folded or roughly handled*

*Proceedings of the Madras Government, Public Works Department,
16th September 1875.*

No. 359.

Read the following:—

*TAMBRAPURNI IRRIGATION—CAPITAL, ORDINARY—ARIYANAIAKAPURAM
SECTION.*

ABSTRACT ESTIMATE, No 2 OF 1875-76.

Tinnevely District, Ambasamudram Taluq.

WORK.—Constructing a Head-sluzee for the Kodagan Channel.

Quantity.	Description of Work.	Rate.			Amount.			Total.
		RS.	A.	P.	RS.	A.	P.	
88	C. yards of concrete in hydraulic mortar, at...	3	8	0	308	0	0	
111½	„ of brick in do., at...	5	8	0	614	10	0	
434½	„ of brick in mortar, at...	5	0	0	2,122	8	0	
55	„ of cutstone in mortar and pointed with Portland cement for flooring, at...	21	0	0	1,155	0	0	
46	C yards of do. do. for casing, at...	22	0	0	1,012	0	0	
8½	„ of do. do. for coping, at...	27	0	0	236	4	0	
23½	„ of archwork including centring, at...	6	8	0	185	4	0	
3,187	Square feet of pointing per square...	4	0	0	127	7	8	
196½	Cubic yards of loose rough-stone, at...	2	0	0	210	8	0	
20	Cubic feet of Vangay or Congoewood wrought and put up, at...	3	8	0	70	0	0	
4	Teakwood shutters with iron lifting bolts and all fittings, &c., complete, at...	250	0	0	1,000	0	0	
	Excavation for foundation and filling-in...				200	0	0	
	Temporary embankment...				200	0	0	
	Baling...				200	0	0	
	Lascars' huts...				150	0	0	
					7,791	9	8	
	Scaffolding, sundries, and contingencies...				258	6	4	
	Extra establishment...				150	0	0	8,200
	<i>Constructing an embankment to prevent the Volleday water outflanking the new head-sluzee to the Kodagan Channel.</i>							
29,857	Cubic yards of earth, at...	0	1	8	2,322	9	8	
2	Acres of nanjuli (compensation), at...	500	0	0	1,000	0	0	
	Levelling, tamping and sundries, and providing escapes for water...				117	6	9	
	Extra establishment...				50	0	0	3,500
	Total Estimate...							11,700

No. 1,051.

Note by the Chief Engineer for Irrigation.

In G. O. No. 3,193, of the 11th November 1874, an estimate of Rupees 7,250 was sanctioned for constructing a head-sluzee for the regulation of the supply to the Kodagan Channel from the Tambrapurni, and, as in the case of the Pallem Channel head-sluzee, attention was called in the note on the estimate to the necessity for

*Proceedings of the Madras Government, Public Works Department,
16th September 1875.*

ascertaining accurately maximum flood level and providing a sufficient margin there-
above. Revised arrangements for the Paliem head-slucice have recently been
sanctioned,* and the Officiating District
* G. O., No. 2,502, dated 1st September 1873. Engineer has now transmitted a revised
design for the Kodagan head-slucice, and an estimate, amounting to Rupees 11,700,
showing an increase of Rupees 4,450.

2. The alteration of the sluice so as to place its roadway 3 feet above maximum
ascertained flood level accounts for only Rupees 950 of the excess, while Rupees 3,500
are required for flood banks in connection with the sluice to prevent the latter being
turned. The roadway will now be 15.72 feet above the mean level of the crest of the
Ariyanakapuram Anicut, and the revised arrangements having been based on careful
investigations checked by levels, there is good reason for supposing that the intended
object of the works will be fully secured. No sections of the flood bank have been
forwarded, neither has its direction and extent been shown on the site plan. Its top
should be made up in the first instance to 1 foot above the sluice roadway to allow
for settlement, and all unequal settlements should be made good, so that the proper level
may be permanently maintained.

Ootacamund, (Signed) JOHN MULLINS, Lieut.-Colonel, R.E.,
15th September 1875. Chief Engineer for Irrigation.

No. 360. ORDER THEREON, 16th September 1875, No. 2,663.

IRRIGATION, No. 34-A.

Account.

Under the circumstances reported, the
revised estimate of Rupees 11,700 for the
Kodagan Channel Head-slucice and for the
flood bank therewith connected is sanc-

tioned, in lieu of that for Rupees 7,250 approved in G. O., No. 3,193, of the 11th
November 1874.

(True Extract.)

(Signed) G. W. WALKER, Major-General, R.E.,
Secretary to Government.

/True Copy/

To the District Engineer, Tinnevely.

Chief Engineer for Irrigation.

Controller of Public Works Accounts.

Revenue Dept.
Collector, Tinnevely

Secretary to Govt.

Ed. E. C. Shaker.

Printed Copies.

*Rev: 1875. Dept
N. 3854*

Gobt. of (1875) Madras.

PUBLIC WORKS.

To

THE DISTRICT ENGINEER,

TANJAVELLY.

Esq. &c. &c.

Dated September 23rd.

Respectfully

Yours

Oct. 6th

Encs.

At the 11th September 1875, No. 354.

SEPTEMBER.

Nos. 359-380

1 Lot. Drawing Quarter 1875

*N^o 2086
Comm. to the
Board of Revenue
7 Oct/75*

K. S. S. Chund. Head-Office, Tanjore.
Dated—The act of estimate of Rs. 22,500
for construction of — and for the Road
bank in the district, sanctioned to the
at the 1st Decr. 1874 approved in G. O.,
No. 3499 of 21 November 1874.