

(1) Number of Pages 4

(2) Date of repair 28-10-68

(3) Initials of the Referencer 22-11-68

MADRAS RECORD OFFICE

GOVERNMENT OF MADRAS

Revenue DEPARTMENT

G.O. No.

B.P. No.

2452

Press

Mis.

Dated

22-11-1875 196 .

Not to be folded or roughly handled

2452
1

*Proceedings of the Madras Government, Public Works Department,
10th November 1875.*

Read the following:—

No. 1,275.

No. 235. *Note by the Chief Engineer for Irrigation.*

In the Budget for the current year Rupees 5,000 have been provided for a head-sluiice for the Nathiyuny Anicut Channel from the Tambrapoorny. The District

Rupees 3,300.

From District Engr., No. 24, 26th April 1875.

To " " 496, 11th May "

From " " 53, 20th July "

Engineer, Tinnevely, has forwarded a plan and estimate for this, the last of the head-

sluices, the construction of which was in

G.O., 20th January last, No. 256, ordered

to be undertaken, and it will be seen that

the design has been revised, and that the District Engineer is of opinion that the arrangements as therein proposed are sufficient for security and for the effective supply of the irrigation.

2. Mr. Grant in a recent letter applies for the transfer of the grant to the

No. 86, 18th ultimo.

Cannadien and Pauliem Channel head-sluiices on the ground that the allotments

for these works are insufficient and that no money will be required for the Nathiyuny Sluice this year. It having, however, been decided that all the sluices are to be constructed as soon as possible, this, though perhaps of less importance than others, should not be deferred, and the collection of materials should be gone on with, and as much as possible done in getting in foundations and flooring during the next dry season, so that by this time next year the sluice may be finished or sufficiently so to exclude floods.

3. It is therefore recommended that Rupees 1,500 be reserved for expenditure in this year on the Nathiyuny Sluice, and that the balance of Rupees 3,500 be transferred to—

	RS.
Cannadien Sluice	1,500
Pauliem do.	2,000

The further grant required for the Pauliem Sluice may be made available from the sums surrendered by the Collectors of Kurnool and Cuddapah out of provision for land compensation, Madras Irrigation and Canal Company's Canal, about to be reported to Government.

FORT ST. GEORGE,
3rd November 1875.

(Signed) A. DEC. SCOTT, Major, R.E.,
for Chief Engineer for Irrigation.

CAPITAL—ORDINARY—TAMBRAPOORNY IRRIGATION.

ABSTRACT ESTIMATE OF 1875-76.

Tinnevely District, Ambasamoodrum Taluq.

WORK.—Constructing a Head-sluiice for Nathiyuny Channel.

Quantities.	Description of Work.	Rate.			Amount.			Total.		
		RS.	A.	P.	RS.	A.	P.	RS.	A.	P.
15½	Cubic yards of concrete, at	3	8	0	54	4	0			
75½	Do. of brickwork in hydraulic mortar, at	5	8	0	416	10	0			
175	Do. of do. in mortar, at	5	0	0	875	0	0			

Proceedings of the Madras Government, Public Works Department,
10th November 1875.

WORK.—Constructing a Head-sluiice for Nathiyuny Channel.—(Concluded.)

Quantities.	Description of Work.	Rate.			Amount.			Total.		
		RS.	A.	P.	RS.	A.	P.	RS.	A.	P.
14½	Cubic yards of archwork, at ...	6	8	0	94	4	0			
30½	Do. of cut-stone in mortar, at ...	25	0	0	768	12	0			
1,756	Square feet of pointing, per square ...	3	0	0	52	10	10			
22	Cubic yards of loose rough stone for revetment, at ...	2	8	0	55	0	0			
16½	Do. do. for apron, at ...	2	0	0	33	0	0			
8	Cubic feet of Pangay or Congoo wood wrought and put up, at ...	3	0	0	24	0	0			
2	Teakwood shutters with iron lifting bolts and all fittings, &c., complete, at ...	230	0	0	460	0	0			
	Excavation for foundation and filling in ...				45	0	0			
	Temporary embankment and diversion channel ...				50	0	0			
	Baling ...				50	0	0			
	Extra establishment ...							2,978	8	10
	Scaffolding, sundries, and contingencies, including huts for lascars ...							120	0	0
	Total of estimate ...							201	7	2
								3,300	0	0

No. 236.

ORDER THEREON, 10th November 1875, No. 3,209.

IRRIGATION, No. 13.
Account.

THE estimate, amounting to Rupees 3,300, for constructing a head-sluiice to the Nathiyuny Channel in Tinnevelly is sanctioned, and its amount being less than the Budget allotment of Rupees 5,000 and only part of the work being capable of being carried out this year, the allotment will be reduced to Rupees 1,500, and the following transfers are authorized:—

To Cannadien Channel Head-sluiice	RS.
To Pauliem do do	1,500
2. A further appropriation on account of the last-named sluiice will be made in due course.	2,000

(True Extract.)

Major-General, R.E.,

Secretary to Government.

To the District Engineer, Tinnevelly.
" Chief Engineer for Irrigation.
" Controller of Public Works Accounts.
" Collector of Tinnevelly.
" Revenue Department.

Erd. E. C. Shunker.

14 Spare Copies

Revenue Department
No. 4491
Govt. of 1875 Madras.
PUBLIC WORKS.

To

THE DISTRICT ENGINEER,
TINNEVELLY,
&c., &c., &c.

Dated November 10th.

Issued 19-11-75

Recd. 20-11-75

Encl.

G. O., 10th November 1875, No. 3,209.

NOVEMBER.

Nos. 235-236

Nathiyuni Channel, Tinnevelly District.—
Estimate amounting to Rupees 3,300 for
constructing a head-sluice to the — submit-
ted by the Chief Engineer for Irrigation
with note, sanctioned.

No. 2452
Comm. to the
Board of Revenue
22nd Nov. 75

9 To the District Revenue Officer
Office