

(1) Number of Pages 4(2) Date of repair 12-11-68

(3) Initials of the Referencer _____

MADRAS RECORD OFFICE**GOVERNMENT OF MADRAS**Revenue DEPARTMENTG.O. No.
B.P. No.2519~~Press~~
Mis.Dated 30-11-1875 196Not to be folded or roughly handled

*Proceedings of the Madras Government, Public Works Department,
19th November 1875.*

No. 444. Read the following letter from J. D. GRANT, Esq., Officiating District Engineer, Tinnevely, to Lieutenant-Colonel J. MULLINS, R.E., Chief Engineer for Irrigation, dated Puttugudi, 22nd October 1875, No. 88:—

I HAVE the honor to forward to you an estimate for the head sluice to the Pauliem channel, the flood bank; &c., being altered in the manner pointed out by you in your Note,* a saving of Rupees 700 being thus effected.

1 Estimate with comparative Statement.

* Printed with G.O., No. 2,502, dated 1st September 1875.

2. In this estimate the cost of the head sluice remains unaltered, three of the masonry works are omitted, and the return of the bank is raised 2 feet as directed, the gradient being carried down from that level to the bund level at the head sluice as proposed in the previous estimate.

3. There is an increase necessarily in the compensation for land, as more requires to be taken up for the drainage channel, and also in the quantity of earthwork.

4. The three masonry works which are retained in the estimate are required for irrigation sluices, as the embankment is carried over three patches of nunjah, to avoid which it would have been necessary to make the embankment line much more tortuous than as now designed. The embankment in this estimate is also intended to go round the small village near the head sluice, instead of through it as originally intended, this will serve to protect the village, while if carried through its streets the bank being several feet high, could not but be inconvenient to the inhabitants.

5. In this estimate all the instructions conveyed in your Note have been complied with, and I would beg your early approval and the return of the plans.

CAPITAL—ORDINARY. TAMBRAPOORNY IRRIGATION. PALAVUR SECTION.

REVISED ABSTRACT ESTIMATE.

Tinnevely District, Tinnevely Taluk.

WORK.—Constructing Head Sluice for Pauliem Channel, and raising bund from head sluice along river bank.

Quantity	Description of Work	Rate			Amount			Total		
		Rs.	A.	P.	Rs.	A.	P.	Rs.	A.	P.
1	Head Sluice at	8,200	0	0	8,200	0	0	8,200	0	0
<i>Embankment.</i>										
32,479½	Cubic yards earth	0	1	6	3,044	15	8			
5,843	Do.	0	3	0	1,095	0	0			
2½	Acres Nunjah compensation, per acre	450	0	0	1,012	8	0			
	Compensation for Palmyrah and other trees				150	0	0			
	Cutting channel, constructing drop into Pauliem channel, revetting bunds in odays, &c.				390	0	0			
	Sundries about 2½ per cent.				98	15	9			
	Appendices of Nos. 1, 3, and 5	170	0	0	510	0	0	5,790	0	0
	Superintendence							510	0	0
	Total Estimate revised Amount							15,000	0	0

PALAVUR,
13th October 1875.

(Signed) W. HUGHES,
Tinnevely Range Officer.

(Signed) J. D. GRANT,
Officiating District Engineer, Tinnevely.

*Proceedings of the Madras Government, Public Works Department,
19th November 1875.*

No. 445. ORDER THEREON, 19 November 1875, No. 3,308.

IRRIGATION, No. 46-A.

Account.

The arrangements in connection with the Pauliem channel head sluice, which have been revised in accordance with the instructions contained in Proceedings of Madras Government, No. 2,502, of the

1st September last, are approved, and the revised estimate of Rupees 15,000 is sanctioned.

(True Extract.)

Major-General R.E.
Secretary to Government.

To the District Engineer, Tinnevely.
Chief Engineer for Irrigation.
Controller of Public Works Accounts.
Revenue Department.
Collector of Tinnevely.

Enc. B. E. A. 11

Spate Unpaid

1875
1875

PUBLIC WORKS.

RECEIVED
T. W. KELLY
35, 36, &

1875

29

Date

1875

NOVEMBER

Nos 444-445

to the O. B. of the O. B.

1875

1875
1875
1875