M.R.O. 1—20,002—12-3-65.

(1) Number of Pages 2

(2) Date of repair 11. 6. 68.

(3) Initials of the Referencer

# MADRAS RECORD OFFICE

## GOVERNMENT OF MADRAS

Revenue DEPARTMENT

| | |
|---|---|
| G.O. No. 2554. | Press |
| B.P. No. | Mis. |
| Dated 4. 12. 1878 | 196 . |

*Not to be folded or roughly handled*

1/2554.

*Proceedings of the Madras Government, Public Works Department, 26th November 1875.*

No. 593. Read the following endorsement of the Chief Engineer for Irrigation, dated Danaincheroovoo, 16th November 1875, No. 1,358:—

From J. D. GRANT, Esq., Officiating District Engineer, Tinnevelly, to Lieutenant-Colonel J. MULLINS, R.E., Chief Engineer for Irrigation, dated Camp at Ambasamudram, 6th November 1875, No. 99.

I HAVE the honor to forward, for sanction, an estimate of Rupees 170 for constructing an apron to the surplus weir of Marathony Periakulam Tank in Sunkernarcovil Taluq. More than one year's revenue having been spent on the tank in the last five years, this estimate cannot be sanctioned locally.

1 Estimate.
1 Plan.

2. From the plan it will be seen that the scour through the vents has dangerously scooped out the soft rock in rear of the weir and that protection is necessary.

3. The estimate provides for filling in the hollow with earth and rough stone, and laying over that a rough stone apron 1 foot 6 inches thick with a rear retaining wall.

---

SUBMITTED to Government.

2. The filling in under the aprons should consist of small stone or clean gravel rather than earth. The outer apron had better extend to the ends of the rear wing returns, unless the rock on which the latter is founded be harder than that which has been washed away.

3. No provision appears to have been made in the estimate for the rough (dry) stone apron beyond the retaining wall. Its width is $7\frac{1}{2}$ feet and the length about $67\frac{1}{2}$, say 22 yards. The cost will be $23 \times 22\frac{1}{2} \times \frac{1}{2}$ at $1\frac{1}{2}$ Rupees, say, with sundries, 50 Rupees, making the total 220 Rupees.

(Signed) JOHN MULLINS, Lieut.-Colonel, R.E.,
*Chief Engineer for Irrigation.*

---

No. 594. ORDER THEREON, 26th November 1875, No. 3,380.

IRRIGATION, No. 56.
*Account.*

THE estimate of Rupees 220 for repairing the escape of the Marathony large tank is sanctioned.

(True Extract.)

Major-General, R.E.,
*Secretary to Government.*

To the District Engineer, Tinnevelly.
„ Controller of Public Works Accounts.
„ Chief Engineer for Irrigation.
„ Collector of Tinnevelly.
„ Revenue Department.

Exd. S. T. Austin.

Spare Copies

Revenue Department

No 4865

Govt. of H.E.H. Madras.

PUBLIC WORKS.

THE DISTRICT ENGINEER,
TINNEVELLY.

Dated 27th October 1870.

Rec'd Dec. 3rd

Rec'd Dec. 3rd

REVENUE.

Nos. 503-504

Madras Letter No. 2534, dated 27th October 1870, forwarding estimate of Rupees 240 for repairing the bridge at Gudalur.

No 2534
Committed
Board of Revenue
4 Dec 70