

- (1) Number of pages 4  
(2) Date of repair 6-2-70  
(3) Initials of the Referencer \_\_\_\_\_

## MADRAS RECORD OFFICE

### GOVERNMENT OF MADRAS

*Revenue* DEPARTMENT

|          |           |       |
|----------|-----------|-------|
| G.O. No. | 1719      | Press |
| B.P. No. |           | Mis.  |
| Dated    | 21-7-1876 | 196   |

Not to be folded or roughly handled

Read the following:—

No. 64 W.

No. 516.

*Note by the Chief Engineer for Irrigation.*

THE District Engineer, Madura, forwards, with his letter marginally noted, an estimate in connection with the Athe-karicolum tank of Vadakary, situated in the Pereacolum Taluq, Dindigul Range.

2. The nature of the work proposed for execution and the heads of account to which it is chargeable are as follow:—

|                                                                                                                                 | RS.   |
|---------------------------------------------------------------------------------------------------------------------------------|-------|
| Raising and repairing the bund, calingulahs and sluice, also repairing and improving the supply channel. Ordinary Agricultural— | 1,750 |
| Repairs ... ..                                                                                                                  | ...   |
| Constructing a new masonry weir and improving the existing calingulahs. Ordinary Agricultural—Original Works ...                | 515   |
| Total ...                                                                                                                       | 2,265 |

3. The following particulars of this tank are recorded:—

|                                                |                |
|------------------------------------------------|----------------|
| Ayacut area...                                 | ... Acres 124  |
| Assessment ...                                 | ... Rupees 711 |
| Average revenue ...                            | ... " 702      |
| Highest do. ...                                | ... " 711      |
| Expenditure during the previous four years ... | Nil.           |

The area of the catchment basin is 4 square miles; the maximum flood supply is calculated at 1,512 cubic feet per second, for discharging which, as surplus, there are two calingulahs, one at the eastern end of the bund and the other in the channel. It is proposed to remove the dam stones from these calingulahs and to raise their body walls to F.T.L., and also to construct a new masonry weir 66 feet in length, which will make a total length of 109 feet available for the surplus discharge.

The estimate is recommended for sanction, it being noted that the high rate of Anna 1 and Pice 3 per cubic yard for earthwork is explained to be owing to the demand for labor on coffee estates in the neighbourhood, and that the repairs have already been carried on on emergency.

30th May 1876.

(Signed)

A. DEC. SCOTT, Major, R.E.,  
Dy. Chief Engineer for Irrigation,  
for Chief Engineer for Irrigation.

To the Secretary to Government, Public Works Department.

*Proceedings of the Madras Government, Public Works Department,  
26th June 1876. No. 1,596.*

No. 517.

ORDER THEREON, 26th June 1876, No. 1,596.

## IRRIGATION, No. 33.

## Account.

THE following estimate from the Dindigul Range, forwarded by the District Engineer, Madura, is sanctioned :—

ATHEKARIOLUM TANK.

### *Irrigation.*

R8.

- |    |                                                                                                                                                 |           |              |
|----|-------------------------------------------------------------------------------------------------------------------------------------------------|-----------|--------------|
| 1. | Raising and repairing the bund, repairing the calingulahs and sluice, repairing and improving the supply channel. Ordinary Agricultural—Repairs | ... ..    | 1,750        |
| 2. | Constructing a new masonry weir and improving the existing calingulahs. Ordinary Agricultural—Original Works                                    | ...       | 515          |
|    |                                                                                                                                                 | Total ... | <u>2,265</u> |

2. This sanction has been registered as No. 55 I. of 1876-77.

(True Extract.)

W. H. L. Colonel,  
Off. Under Secy. to Govt., P.W.D.

To the District Engineer, Madura.  
 " Collector of Madura.  
 " Chief Engineer for Irrigation.  
 " Examiner of Public Works Accounts.  
 " Revenue Department. ✓

Exd. A. Grubert.

Spare Copies

*N. 2506*  
*Revenue 1876 Defunct*  
Govt. of 1876 Madras.  
PUBLIC WORKS.

To

THE DISTRICT ENGINEER,  
MADURA.  
&c., &c., &c.

Dated June 26th.

Issued

Recd. *17 July 1876* Encl.

G. O., 26th June 1876, No. 1,596.

JUNE.

Nos. 516-517.

*2*

*Dis. Am.*

Athokaricottam Tank, Madura District.  
Estimate for repairing the —, sanctioned.

*No. 1712*  
*Commenced work 1st July 1876*

*21 July 1876*

Dated

196

Not to be folded or roughly handled