

(1) Number of pages 4

(2) Date of repair 2-2-70

(3) Initials of the Referencer _____

MADRAS RECORD OFFICE

GOVERNMENT OF MADRAS

Revenue DEPARTMENT

G.O. No.
B.P. No.

1748

Press
Mis.

Dated

22-7-1876

196

Not to be folded or roughly handled

Read the following :—

No. 60 W.

No. 75.

Note by the Chief Engineer for Irrigation.

THE Officiating District Engineer, Tinnevely, forwards, with his letter marginally noted, an estimate in connection with the Ninarcolum tank situated in the Tinnevely Taluq, Tinnevely Range.

2. The nature of the work proposed for execution and the heads of account to which it is chargeable are as follow :—

Removing the existing calingulah and reconstructing a weir in its stead.	Ordinary Agricultural—Original Works.	Rs. 1,340
Raising and repairing the bund where necessary.	Ordinary Agricultural—Repairs	260
Total		1,600

3. The following particulars of this tank are recorded :—

Ayacut area	Acres 632
Assessment	Not given.
Average revenue	Do.
Highest do.	Do.
Expenditure during the previous four years	Rupees 605.

The area of the catchment basin is .5 square miles ; the maximum flood supply is calculated at 1,150 cubic feet per second, for discharging which as surplus there is a calingulah 113 feet in length, effective 40 feet.

It is proposed to replace the calingulah by a weir 117 feet in length, as the former is very old and irregular, and the repairs would cost nearly as much as to construct the weir. The particulars of assessment, average revenue, &c., are not stated. It will be necessary to return estimates which do not give information which is so important.

OOTACAMUND,
22nd May 1876.

(Signed) A. DEC. SCOTT, Major, R.E.,
Depy. Chief Engineer for Irrigation,
for Chief Engineer for Irrigation.

*Proceedings of the Madras Government, Public Works Department,
5th July 1876. No. 1,702.*

No. 76.

ORDER THEREON, 5th July 1876, No. 1,702.

IRRIGATION No. 6.
Account.

THE following estimate from the
Tinnevelly Range, forwarded by the
Officiating District Engineer, Tinnevelly,
is sanctioned :—

NINARCOLUM TANK.

Irrigation.

Group or Project.	Fund.	Class.	Particulars of Work.	Amount.
Tambrapurny Irrigation.	Ordinary Agricultural.	Original Works.	1. Reconstructing the escape of the Ninarcolum tank	rs. 1,340
Tinnevelly Section.	Do.	Repairs.	2. Repairing the bund of the Ninarcolum tank	260

To be carried out by
the Public Works
Department Officer
in charge, Tinne-
velly Range.

2. This sanction has been registered as No. 57 I. of 1876-77.

(True Extract.)

Amphibio
Major R
Signal,

~~Off.~~ Under Secy. to Govt., P.W.D.

To the District Engineer, Tinnevelly.
" Collector of Tinnevelly.
" Chief Engineer for Irrigation.
" Examiner of Public Works Accounts.
" Revenue Department. ✓

Exd. A. Grubert.

14 Spare Copies

No 2985
Revenue 1875 Department
Govt. of 1876 Madras.
PUBLIC WORKS.

To

THE DISTRICT ENGINEER,
TINNEVELLY,
&c., &c., &c.

Dated July 5th.

Issued

Recd. *22 July 76* Encl.

G. O., 5th July 1876, No. 1,702.

JUNE.
Nos. 75-76.

Des 10/1

Ninarcolum Tank, Tinnevelly District.—
Estimate of Rupees 1,600 for certain repairs,
&c., to the —, sanctioned.

No 1748
Communicated to the D. E. of the
22 July 1876

11 Filed 20 July 1876