New No. Sectt. I (i)-1—Old No. M.R.O. 1—10,006—10-6-63.

(1) Number of pages 4

(2) Date of repair 25.2.1970

(3) Initials of the Referencer

MADRAS RECORD OFFICE

GOVERNMENT OF MADRAS

Revenue DEPARTMENT

G.O. No. / ~~B.P. No.~~	2307	Press / Mis.
Dated 3.10.1876		~~196~~ .

Not to be folded or roughly handled

Do

GOVERNMENT OF MADRAS

2302/1

Read the following :—

No. 179-W.

No. 183. *Note by the Chief Engineer for Irrigation.*

The Officiating District Engineer, Salem, forwards, with his letter marginally noted, an estimate in connection with the Moothooray Supply Channel Tank situated in the Tripatore Taluq, No. 3 or Tripatore Range.

No. 30, dated 17th July 1876.

2. The nature of the work proposed for execution and the heads of account to which it is chargeable are as follow :—

Ordinary Agricultural.

Repairs.

	Rs.
Reconstructing a head sluice	900
Repairing the supply channel	315
Total ...	1,215

3. The following particulars of this tank are recorded :—

Ayacut area	Acres 61
Assessment	Rupees 687
Average revenue	,, 675
Highest do.	,, 777
Expenditure during the previous four years	Nil.

The existing head sluice in this channel is in a very dilapidated condition and cannot be made use of, neither can it be efficiently repaired. The only vent it has is without shutters, and is not capable of passing a sufficient supply of water to the fields. The supply channel also is silted up at the head, and the sides are not of proper section. The estimate provides for removing the existing head sluice and reconstructing it in a more efficient and substantial form, and deepening and sectioning the channel for a length of 1,100 feet from the head in order to insure a better supply of water.

The design for the sluice has been revised under instructions from this office, and the estimate is now recommended for sanction.

Ootacamund,
7th September 1876.

(Signed) A. deC. SCOTT, Major, R.E.,
Dy. Chief Engineer for Irrigation,
for *Chief Engineer for Irrigation.*

To the Secretary to Government, Public Works Department.

No. 184. Order thereon, 13th September 1876, No. 2,437.

IRRIGATION, No. 22.
Account.

The following estimate from the No. 3 or Tripatore Range forwarded by the Officiating District Engineer, Salem, is sanctioned :—

Proceedings of the Madras Government, Public Works Department,
13th September 1876. *No.* 2,437.

Irrigation.

Group or Project.	Fund.	Class.	Name of Tank, Canal, or Channel.	Particulars of Work.	Amount.	
					Rs.	
...	Ordinary Agricultural.	Repairs.	Moothooray Supply Channel.	1. Reconstructing a head sluice ...	900	To be carried out by the Public Works Department Officer in charge No. 3 or Tripatore Range.
				2. Repairing the supply channel.	315	

2. This sanction has been registered as No. 147-I of 1876-77.

(True Extract.)

H. Harcourt Colonel,
Offg. Under Secy. to Govt., P.W.D.

To the District Engineer, Salem.
" Collector of do.
" Chief Engineer for Irrigation.
" Examiner of Public Works Accounts.
" Revenue Department.

Exd. A. Grubert.

14 Spare Copies

N. 4088
Rev. 1876. Sept

Govt. of [1876] Madras.

PUBLIC WORKS.

To

THE DISTRICT ENGINEER,
SALEM,
&c., &c., &c.

Dated September 13th.

Issued

Recd. Oct 3rd Encl.

G. O., 13th September 1876, No. 2,437.

SEPTEMBER.

Nos. 183-184.

Moothooray Supply Channel, Salem.—Estimate for repairs to the —, sanctioned.

No. 2907
Communicated to the Board
Revd
3rd October 1876