

(1) Number of pages 4

(2) Date of repair 23-2-71

(3) Initials of the Referencer _____

MADRAS RECORD OFFICE

GOVERNMENT OF MADRAS

DEPARTMENT

Revenue

G.O. No.	<u>2071</u>	Press
B.P. No.	<u>2901</u>	Mis.
Dated	<u>24-12-1876</u>	196

Not to be folded or roughly handled

100

Read the following:—

No. 245 W.

No. 349.

Note by Chief Engineer for Irrigation.

THE District Engineer, Kurnool, forwards with his letter marginally noted an estimate in connection with the Peddamal-lalaman tank, situated in the Nandicotkoor talug, Kurnool Range.

2. The nature of the work proposed for execution and the heads of account to which it is chargeable are as follow:—

ORDINARY AGRICULTURAL.

Repairs.

	RS.
Repairing the bund and closing a breach in the natural escape	490
Reconstructing an irrigation sluice	750
Total	1,240

3. The following particulars of this tank are recorded:—

Ayaout area	...	...	...	Acres	{	Circar 37.2	Acres.
						Inam 48.74	
Assessment	...	...	...	303 Rupees	{	Circar 124	Rupees.
						Inam 179	
Average revenue	...	...	...			491	"
Highest do.	...	...	...			509	"
Expenditure during the previous four years	...	...	...			144	"

The area of the catchment basin is 2 square miles; the maximum flood-supply is calculated at 1,066 cubic feet per second, discharging which, as surplus, there is 75 feet of natural escape which has a cut in supposed to have been made by the ryots for irrigation purposes. As the sluice is defective and in a ruined condition, it is proposed to close the cut with a masonry wall. The estimate also provides for repairing and raising the bund to a height of 4 feet above the crest of escape, clearing bushes and reconstructing the irrigation sluice, and is recommended for sanction.

FORT ST. GEORGE,
10th November 1876.

(Signed)

JOHN MULLINS, Lt.-Col., R.E.,

Chief Engineer for Irrigation.

To the Secretary to Government, Public Works Department.

Mis.
Press

G.O. No.
B.P. No.

*Proceedings of the Madras Government, Public Works Department,
20th November 1876. No. 3,106.*

No. 350. ORDER THEREON, 20th November 1876, No. 3,106.

IRRIGATION, No. 31-A.
Account.

THE following estimate from the Kurnool Range, forwarded by the District Engineer, Kurnool, is sanctioned :—

PEDDAMALLALAMAH TANK.

Irrigation.

Group or Project.—Velgode Group.

Fund.—Ordinary Agricultural.

Class.—Repairs.

Name of Tank, Canal, or Channel.—Peddamallalah Tank.

<i>Particulars of Work.</i> —1. Repairing the bund and closing a breach in the natural escape	rs.
2. Reconstructing an irrigation sluice	750
Total	1,240

To be carried out by the Public Works Department Officer in charge, Kurnool Range, I.

2. This sanction has been registered as No. 177 I of 1876-77.

(True Extract.)

Ernst Major-General, R.E.,
Secretary to Government.

To the District Engineer, Kurnool.

„ Collector of Kurnool.

„ Chief Engineer for Irrigation.

„ Examiner of Public Works Accounts.

„ Revenue Department.

Exd. S. T. Austin.

14 Spare Copies

Revenue Dept
No 5344

Govt. of 1876 Madras.

PUBLIC WORKS. ✓

To

THE DISTRICT ENGINEER,

KURNOOL,

&c., &c., &c.

Dated November 20th.

Issued

Recd. 2 Dec.

Encl.

G. O., 20th November 1876, No. 3,106.

See Memo

NOVEMBER.

Nos. 349-350.

Peddammallamah Tank, Karnool District.
—Estimate of Rupees 1,240 for repairing
the —, sanctioned.

No 2901 ✓

Comm'd to the
Bd of Rev.

9 Feb 1877 Board of P.W. Engineer