

(1) Number of pages 4
(2) Date of repair 27.10.1969
(3) Initials of the Referencer _____

MADRAS RECORD OFFICE

GOVERNMENT OF MADRAS

Revenue DEPARTMENT

G.O. No.	849	Press
B.P. No.		Mis.
Dated	8.4.1876	196

Not to be folded or roughly handled

DA

849
1

*Proceedings of the Madras Government, Public Works Department,
27th March 1876.*

Read the following :—

No. 8 W.

No. 411. *Note by the Chief Engineer for Irrigation.*

THE District Engineer, Cuddapah district, forwards, with his letter marginally noted, an estimate in connection with the
No. 2,303, dated 12th February 1876. Madichervoo large tank situated in the
Voilpaul taluq, Madanapully range.

2. The nature of the work proposed for execution and the heads of account to which it is chargeable are as follows :—

Raising and strengthening the bund.	Revenue Repairs	... Rupees	250
Constructing a masonry weir.	Capital, Ordinary—Original Works.	"	310
		"	560

3. The following particulars of this tank are recorded :—

Ayacut area		Acres	153
Assessment		Rupees	698
Average revenue		"	386
Highest do.		"	528
Expenditure during the previous four years. Not stated.			

The area of the catchment basin is 5 square miles; the maximum flood supply is calculated at 1,336 cubic feet per second, for discharging which as surplus there is an old rough-stone weir 40 feet in length and a natural escape 56 feet, total length 96 feet. The estimate provides for raising and strengthening the bund and constructing a masonry weir; but it is impossible to understand from the report where the weir is placed, or what actual addition of means of escape it will give. It is not stated whether it replaces wholly or in part the rough-stone weir now in existence, or whether it takes the place of the natural escape. About 160 feet of length of escape should be provided in some form or other. Subject to these remarks the estimate may be carried out.

(Signed) A. DEC. SCOTT, Major, R.E.,
Deputy Chief Engineer for Irrigation,
for Chief Engineer for Irrigation.

16th March 1876.

No. 412. ORDER THEREON, 27th March 1876, No. 767.

IRRIGATION, No. 37.

Account.

The following estimate from the Madanapully range, forwarded by the District Engineer, Cuddapah, is sanctioned :—

(1) Raising and strengthening the bund, and (2) constructing a masonry weir to the Madichervoo large tank—

(1.) Revenue Repairs		... Rupees	250
(2) Capital, Ordinary Works		"	310
		Total	560

G.O. No.
B.P. No.
Mis.
Press

*Proceedings of the Madras Government, Public Works Department,
27th March 1876.*

2. This sanction has been registered as Irrigation No. 67 I. of 1875-76.

(True Extract.)

Lynna the Major-General, R.E.,
Secretary to Government.

To the District Engineer of Cuddapah.
„ Collector of Cuddapah.
„ Chief Engineer for Irrigation.
„ Examiner of Public Works Accounts.
„ Revenue Department.

Exd. A. Gruberl.

1/4 Spare Copies.

Revenue Department
No 1417
Govt. of 1876 Madras.
PUBLIC WORKS.

To
THE DISTRICT ENGINEER,
CUDDAPAH,
&c., &c., &c.

Dated March 27th.

Issued

Recd. *Appl 7* Recd.

G. O., 27th March 1876, No. 767.

Do. M. C.
MARCH
Nos. 411-412

Maddur-see large Tank, Cuddapah Dis-
trict.—Estimate of Rupees 500 for improving
the same, sanctioned.

N. 849
Commr. to the
Board of Revenue
8. April 76

Ed. O. and of O. G. 11/4/76.