

- (1) Number of pages 4
(2) Date of repair 27.10.1969
(3) Initials of the Referencer _____

MADRAS RECORD OFFICE

GOVERNMENT OF MADRAS

Revenue DEPARTMENT

G.O. No.	852	Press
~~BP~~ No.		~~Misc~~
Dated	10.4.1876	196

Not to be folded or roughly handled

852
1

*Proceedings of the Madras Government, Public Works Department,
27th March 1876.*

Read the following:—

No. 12 W.

No. 423. *Note by the Chief Engineer for Irrigation.*

THE District Engineer, Cuddapah District, forwards, with his letter marginally noted, an estimate in connection with the No. 2,305, dated 12th February 1876. Muttayobal Reddy Cheravoo tank situated in the Royachoty taluq, Madanapully range.

2. The nature of the work proposed for execution and the heads of account to which it is chargeable are as follow:—

Raising and strengthening the bund and repairing the sluice and existing weir—Revenue Repairs	Rs. 236
Extending the existing weir 59 feet—Revenue Extensions	224
Total	460

3. The following particulars of this tank are recorded:—

Ayacut area	Acres 26
Assessment	Rupees 55
Average revenue	" 42
Highest do.	" 58
Expenditure during the previous four years	" 100

The area of the catchment basin is $4\frac{1}{2}$ square miles; the maximum flood supply is calculated at 1,089 cubic feet per second, for discharging which, as surplus there is one rough stone weir 51 feet in length, and an escape 50 feet in length; it is proposed to close the latter and extend the former 59 feet in addition to its present length, making in all a length of 110 feet available for the surplus discharge.

This tank is the head of a series of four, and it is necessary to incur the proposed expenditure which is very large compared with the revenue in order to secure the lower tanks. But the particulars of the revenue, &c., of the other tanks might in such cases well be given and the circumstances of the whole series discussed.

FORT ST. GEORGE,
17th March 1876.

(Signed) A. DE C. SCOTT, Major, R.E.,
Deputy Chief Engineer for Irrigation,
for Chief Engineer for Irrigation.

No. 424. ORDER THEREON, 27th March 1876, No. 773.

IRRIGATION, No. 40.

Account.

The following estimate from the Madanapully range, forwarded by the District Engineer, Cuddapah, is sanctioned:—

(1) Raising and strengthening the bund, repairing the sluice and weir; and (2), extending the existing weir of the Muttayobal Reddy Cheravoo tank—

(1.) Revenue Repairs	Rs. 236
(2.) Do. Extensions	224
Total	460

Press

G.O. No.
B.P. No.

DEPARTMENT

*Proceedings of the Madras Government, Public Works Department,
27th March 1876.*

2. This sanction has been registered as Irrigation, No. 65 I. of 1875-76.
(True Extract.)

Major-General, R.E.,
Secretary to Government.

To the District Engineer, Cuddapah.
„ Collector of do.
„ Chief Engineer for Irrigation.
„ Examiner of Public Works Accounts.
„ Revenue Department.

Exd. T. O'Connor

14 Spare Copies

DEPARTMENT

Revenue Department
N^o 1425
ORDR. OF 1876
PUBLIC WORKS.

THE DISTRICT ENGINEER,
QUADRAH,
CO. CO. CO.

1000 March 1876.

1000

April 8.

1000

G. O. 1000 March 1876, No. 1425.

1000

1000

1000

1000

1000
Comd. to the
Board of Revenue
1000

DEPARTMENT